



iTool User's Guide

IDL Version 7.0
November 2007 Edition
Copyright © ITT Visual Information Solutions
All Rights Reserved

Restricted Rights Notice

The IDL®, IDL Analyst™, ENVI®, and ENVI Zoom™ software programs and the accompanying procedures, functions, and documentation described herein are sold under license agreement. Their use, duplication, and disclosure are subject to the restrictions stated in the license agreement. ITT Visual Information Solutions reserves the right to make changes to this document at any time and without notice.

Limitation of Warranty

ITT Visual Information Solutions makes no warranties, either express or implied, as to any matter not expressly set forth in the license agreement, including without limitation the condition of the software, merchantability, or fitness for any particular purpose.

ITT Visual Information Solutions shall not be liable for any direct, consequential, or other damages suffered by the Licensee or any others resulting from use of the software packages or their documentation.

Permission to Reproduce this Manual

If you are a licensed user of these products, ITT Visual Information Solutions grants you a limited, nontransferable license to reproduce this particular document provided such copies are for your use only and are not sold or distributed to third parties. All such copies must contain the title page and this notice page in their entirety.

Export Control Information

This software and its associated documentation are subject to the controls of the Export Administration Regulations (EAR). It has been determined that this software is classified as EAR99 under U.S. Export Control laws and regulations, and may not be re-transferred to any destination expressly prohibited by U.S. laws and regulations. The recipient is responsible for ensuring compliance to all applicable U.S. Export Control laws and regulations.

Acknowledgments

ENVI® and IDL® are registered trademarks of ITT Corporation, registered in the United States Patent and Trademark Office. ION™, ION Script™, ION Java™, and ENVI Zoom™ are trademarks of ITT Visual Information Solutions.

Numerical Recipes™ is a trademark of Numerical Recipes Software. Numerical Recipes routines are used by permission.

GRG2™ is a trademark of Windward Technologies, Inc. The GRG2 software for nonlinear optimization is used by permission.

NCSA Hierarchical Data Format (HDF) Software Library and Utilities. Copyright © 1988-2001, The Board of Trustees of the University of Illinois. All rights reserved.

NCSA HDF5 (Hierarchical Data Format 5) Software Library and Utilities. Copyright © 1998-2002, by the Board of Trustees of the University of Illinois. All rights reserved.

CDF Library. Copyright © 2002, National Space Science Data Center, NASA/Goddard Space Flight Center.

NetCDF Library. Copyright © 1993-1999, University Corporation for Atmospheric Research/Unidata.

HDF EOS Library. Copyright © 1996, Hughes and Applied Research Corporation.

SMACC. Copyright © 2000-2004, Spectral Sciences, Inc. and ITT Visual Information Solutions. All rights reserved.

This software is based in part on the work of the Independent JPEG Group.

Portions of this software are copyrighted by DataDirect Technologies, © 1991-2003.

BandMax®. Copyright © 2003, The Galileo Group Inc.

Portions of this computer program are copyright © 1995-1999, LizardTech, Inc. All rights reserved. MrSID is protected by U.S. Patent No. 5,710,835. Foreign Patents Pending.

Portions of this software were developed using Unisearch's Kakadu software, for which ITT has a commercial license. Kakadu Software. Copyright © 2001. The University of New South Wales, UNSW, Sydney NSW 2052, Australia, and Unisearch Ltd, Australia.

This product includes software developed by the Apache Software Foundation (www.apache.org).

MODTRAN is licensed from the United States of America under U.S. Patent No. 5,315,513 and U.S. Patent No. 5,884,226.

FLAASH is licensed from Spectral Sciences, Inc. under a U.S. Patent Pending.


Portions of this software are copyrighted by Merge Technologies Incorporated.

Support Vector Machine (SVM) is based on the LIBSVM library written by Chih-Chung Chang and Chih-Jen Lin (www.csie.ntu.edu.tw/~cjlin/libsvm), adapted by ITT Visual Information Solutions for remote sensing image supervised classification purposes.

IDL Wavelet Toolkit Copyright © 2002, Christopher Torrence.

IMSL is a trademark of Visual Numerics, Inc. Copyright © 1970-2006 by Visual Numerics, Inc. All Rights Reserved.

Other trademarks and registered trademarks are the property of the respective trademark holders.



Contents

Chapter 1	
Introducing the IDL iTools	17
Introducing the iTools	18
Using This Guide	20
Chapter 2	
Importing and Exporting Data	23
About the Data Manager	24
Data Manager Interface	25
Data Item Management	26
Data Import Methods	27
Using the Data Import Wizard	28
Using File Open	32
Using the Data Manager Dialog	33
Importing Data from a File	34

Importing Image Data	34
Importing ASCII Data	34
Importing Binary Data	35
Importing Shapefile Data	36
Working with Unknown Data	37
Using the Gridding Wizard	38
Importing Data from the IDL Session	41
Importing Graphic Objects	42
Parameter Data and the Command Line	42
Exporting Data	44
Exporting Data to a File	45
Exporting Data to the IDL Session	48

Chapter 3

Visualizations 51

About Visualizations	52
Visualization Creation Methods	53
Creating Visualizations Automatically	53
Inserting Visualizations	54
Modifying Existing Visualizations	56
The Parameter Editor	56
Removing Data Associations	57
Replacing Data Associations	57
Exporting Visualizations	58
Exporting to a File	58

Chapter 4

Manipulating the Display 59

Introduction	60
Selection of Objects	61
Select All	61
Undo/Redo	62
Adding a Data Space	63
Translation	64
Scaling	65
Zooming	70
Canvas Zoom	70

View Zoom	70
View Panning	72
Window Layouts	73

Chapter 5

Adding Annotations 75

Introduction	76
Legends	77
Annotations	79
Text Annotations	79
Line Annotations	80
Rectangle Annotations	81
Oval Annotations	82
Polygon Annotations	82
Freehand Annotations	83
Additional Axes	84

Chapter 6

Property Sheets and Browsers 85

Introduction	86
Property Sheets	87
Visualization Property Sheets	88
Operations Property Sheets	88
The Visualization Browser	90
The Operations Browser	93
The Preferences Browser	95
General Settings	97
File Readers	99
File Writers	105

Chapter 7

Common Operations 111

Introduction	112
File Operations	113
Opening Files	113
Importing Variables and Files	113
Saving Files	113

Exporting Variables and Files	114
Exiting the iTool	114
Rotation	115
Mouse Rotation	115
Rotate Left and Rotate Right	117
Rotate by Specified Angle	118
Transformations	119
Resample	119
Rotate Data	120
Scale Data	121
Filtering	122
Smooth Filter	122
Median Filter	123
Convolution Filter	124
Unsharp Mask Filter	125
Morphing	127
Additional Operations	128
Plotting a Histogram	128
Displaying Statistics	129
Resetting Dataspace Ranges	131
Rendering Translucent Objects	132
Operations on Regions of Interest	133
Operations Modifying ROI Data	133
Operations Modifying ROI Vertices	133
Printing	134
Print Preview	134
Chapter 8	
Working with Macros	139
Introduction	140
What Are Macros?	141
Recording Macros	143
Capturing Intermediate Manipulations	144
Running Macros	146
Running from the Operations Menu	147
Running from the Macro Editor	148

Running from the Command Line	148
Using the Macro Controls Dialog	149
Using the Macro Editor	153
Understanding the Macro Editor	154
Understanding Items in the Macro Editor	164
Macro Items	164
Source Items	165
Making Selection and Tool Changes	179
Macro Type Based on Recording Selection	179
About Containers	179
Selection Changes	180
Tool Changes	183
Importing and Exporting Macros	186
Chapter 9	
Working with Styles	187
What Are Styles?	188
Type of Styles	189
Applying a Style	189
Creating Styles	190
Creating a Style from the Current Visualization	190
Creating a New Style from the Style Editor	193
Working with the Current Style	195
Copying an Existing Style	195
Applying Styles	196
Applying a Style to a Selected Item	196
Applying a Style to All Items	199
Applying a Style When Launching an iTool	201
Editing Styles	202
Copying Properties Within Styles	202
Cutting and Deleting Properties within Styles	203
Selecting Multiple Properties for Editing	203
Setting the Default Style	205
Importing and Exporting Styles	206
Exporting a File to Share	206
Importing a Received File	206

Chapter 10	
Working with Images	207
Introduction	208
Displaying Images	209
Displaying Multiple Images	211
Using the Image Panel	213
Image ROIs	214
The Palette Editor	215
Window Level Control	215
Image Properties	216
Modifying Properties	216
Adding a Colorbar	217
Adding Axes	218
Resampling an Image	219
Filtering an Image	220
Convolving an Image	220
Applying a Median Filter	220
Smoothing an Image	220
Applying a Roberts Filter	221
Applying a Sobel Filter	221
Applying an Unsharp Mask	221
Applying a Morphological Operator	222
Contouring an Image	223
Surfacing an Image	225
Manipulating the Image Display	226
Rotating an Image	226
Scaling an Image and Byte Scaling an Image	226
Inverting an Image	226
Flipping an Image	226
View Zoom	227
Canvas Zoom	227
Pixel Scaling	227
Region Growing	227
Adding Annotations	228
Line Profiles	228
View Panning	229

Cropping an Image	229
iImage Tool Operations	231
Viewing a Histogram	231
Viewing Image Statistics	231
Cropping Images	231
Chapter 11	
Working with Surfaces	233
Introduction	234
Displaying Surfaces	235
Surface Properties	237
The Visualization Browser	237
The Operations Browser	237
Adding a Colorbar	239
Adding a Light	240
Adding a Legend	241
Adding Axes	242
Imaging a Surface	243
Contouring a Surface	244
Resampling a Surface	246
Filtering a Surface	247
Convolving a Surface	247
Median a Surface	247
Smoothing a Surface	247
Adding a Texture Map	248
Manipulating Surface Displays	249
Rotating a Surface	249
Scaling a Surface	251
Adding Annotations	252
View Zoom	252
Canvas Zoom	253
Extracting a Line Profile	253
iSurface Tool Operations	254
Viewing a Histogram Plot	254
Viewing Statistics	254

Chapter 12	
Working with Contours	255
Introduction	256
Displaying Contours	257
Displaying Regular-grid Data	257
Displaying Irregular-grid Data	258
Contour Properties	264
Labeling Contours	266
Changing the Contour Colors	268
Filling Contours	269
Adding a Colorbar	271
Adding a Legend	272
Adding Axes	273
Filtering a Contour	274
Contour Smoothing	274
Contour Convolution	275
Manipulating the Contour Display	276
Translating	276
View Zoom	276
Flipping a Contour	276
Canvas Zoom	276
Scaling a Contour Display	277
Adding Annotations	277
iContour Tool Operations	279
Viewing a Histogram	279
Viewing Statistics	279
Chapter 13	
Working with Plots	281
Introduction	282
Displaying Two-Dimensional Plots	283
Displaying Three-Dimensional Plots	284
Displaying Polar Plots	285
Overplotting	286
Plot Properties	288
Modifying Properties	288

Adding Legends	289
Adding a Colorbar	291
Adding Error Bars	292
Curve Fitting	294
Filtering a Plot	297
Plot Smoothing	297
Plot Convolution	298
Plot Median	298
Manipulating the Plot Display	299
Translating	299
Adding Annotations	299
View Zoom	300
Canvas Zoom	300
Selecting the Data Range	300
iPlot Tool Operations	301
Scaling a Plot Display	301
Viewing a Histogram	301
Viewing Statistics	301

Chapter 14

Working with Volumes 303

Introduction	304
Displaying Volumes	305
Multi-Channel Volumes	305
Rendering Volumes	306
Using the Volume Panel	309
Volume Properties	311
Modifying Properties	311
Adding a Colorbar	312
Adding Axes	313
Resampling Volumes	314
Showing an Image Plane	315
Viewing the Image Plane in iImage	315
Extracting an IsoSurface	316
Extracting an Interval Volume	318
Manipulating the Volume Display	320

Rotating a Volume	320
Scaling a Volume	320
View Zoom	320
Canvas Zoom	320
Adding Annotations	320
iVolume Tool Operations	322
Viewing a Histogram	322
Viewing Statistics	322
Smoothing a Volume	322
Opening an Image Stack	322

Chapter 15

Working with Maps 325

Introduction	326
Displaying Maps	327
Applying a Map Projection	328
Using the Map Panel	332
Displaying an Image	334
Registering an Image	335
Registering an Image in Meters	337
Registering an Image in Degrees	340
Displaying a Contour	342
Creating a Shape Visualization	343
Inserting a Map Grid	344
Inserting an IDL Shapefile	345
Inserting the Continents	345
Inserting the Countries (Low Resolution)	346
Inserting the Countries (High Resolution)	346
Inserting the Rivers	348
Inserting the Lakes	349
Inserting the United States	350
Inserting the Canadian Provinces	351

Chapter 16

Working with Vectors 353

Introduction	354
Displaying Vectors	355

Vector Fields	355
Wind Barbs	356
Streamlines	359
Vector Properties	360
Modifying Properties	360
Subsampling	360
Coloring Vectors Using Auxiliary Data	362
Manipulating the Vector Visualization	363
Translating	363
Adding Annotations	363
View Zoom	364
Canvas Zoom	364
iVector Tool Operations	365
Adding and Modifying Streamlines	365
Adding Magnitude Contours	366
Adding Direction Contours	366
Vectors and Mapping	367

Appendix A

iTools Interface Reference **369**

Introduction to iTools Interface Elements	370
Menu Bar Items	370
Toolbar Items	370
File Menu	371
Edit Menu	373
Insert Menu	376
Operations Menu	377
Window Menu	380
Help Menu	382
File Toolbar	383
Edit Toolbar	384
Manipulator Toolbar	385
Annotation Toolbar	386
Context Menu	387

Appendix B	
Property Controls	389
Appendix C	
Operations Properties	393
The Operations Browser	394
Macros Properties	395
Statistics Properties	396
Histogram Properties	397
Filter Properties	398
Convolution Properties	398
Median Properties	400
Smooth Properties	401
Roberts Filter Properties	401
Sobel Filter Properties	402
Unsharp Mask Properties	402
Curve Fitting Properties	403
Rotate Properties	405
Rotate Left Properties	405
Rotate Right Properties	405
Rotate By Angle Properties	405
Flip Horizontal	405
Flip Vertical	405
Transform Properties	406
Resample Properties	406
Rotate Data Properties	407
Scale Data Properties	408
Invert Image Properties	409
Byte Scale Properties	409
Map Projection Properties	410
Map Register Image Properties	411
Morphing Properties	412
Crop Properties	413
Region Grow Properties	414
Contour Properties	416
Image Properties	417


Surface Properties	418
Vector Properties	419
Streamlines	419
Contour Magnitude	419
Contour Direction	419
Volume Properties	420
Image Plane	420
Isosurface	420
Render Volume	420
Interval Volume	421
Image Plane Properties	422
Launch iImage	423

Appendix D

Visualization Properties 425

Introduction to Visualization Properties	426
The Visualization Browser	427
Window Properties	428
View Properties	430
Visualization Layer Properties	431
Data Space Properties	433
Rendering Objects at Data Space Depth	436
Visualization Type Properties	437
Image	438
Plot	441
Plot 3D	445
Surface	448
Contour	453
Vector	458
Volume	463
Isosurface	469
Interval Volume	471
Image Plane	474
Colorbar	477
Histogram	481
Axes	485

Lights	494
Polygonal ROI	497
IDL Graphics Objects	499
Map Grid	500
ShapePolygon	505
ShapePolyline	507
ShapePoint	509
Streamlines	510
2D Annotation Layer Properties	513
Text Annotation Properties	514
Line Annotation Properties	516
Line Profile Annotation Properties	517
Rectangle Annotation Properties	520
Oval Annotation Properties	521
Polygon Annotation Properties	522
Freehand Annotation Properties	523
Legend Properties	524
Legend Contour Items	527
Legend Contour Level Items	528
Legend Plot Items	530
Legend Surface Items	531
Index	533



Chapter 1

Introducing the IDL iTools

This chapter introduces you to the new IDL iTools and aids in using this guide.

Introducing the iTools	18	Using This Guide	20

Introducing the iTools

The new IDL Intelligent Tools (iTools) are a set of interactive utilities that combine data analysis and visualization with the task of producing presentation quality graphics. Based on the IDL Object Graphics system, the iTools are designed to help you get the most out of your data with minimal effort. They allow you to continue to benefit from the control of a programming language, while enjoying the convenience of a point-and-click environment.

In IDL, seven pre-built iTools are exposed for immediate interactive use. Each of these tools is designed around a specific data or visualization type, including:

- Two- and three-dimensional plots (line, scatter, polar, and histogram style)
- Surface representations
- Contour data
- Map data
- Image displays
- Volume visualizations
- Vector displays

The iTools are built upon a new object-oriented framework, or set of object classes, that serve as the building blocks for the interface and functionality of the iTools. IDL programmers can easily use this framework to create custom data analysis and visualization environments. Such custom iTools may be called from within a larger IDL application, or they may serve as the foundation for a complete application.

A Single Tool with Many Faces

What sets the iTools apart from precursors such as the Live Tools (now obsolete) — and what gives them their optimal power, flexibility, and extensibility — is the cohesive, open architecture of the iTools system. The iTools system is actually comprised of a single tool, which adapts to handle the data that you pass to it. The plot, surface, image, contour, and volume tools are simply shortcut configurations, which facilitate ad hoc data analysis and visualization. Each tool encapsulates the functionality (data operations, display manipulations, and visualization types) required to handle its data or visualization type. However, you are not constrained to work with a single data or visualization type. Instead, using the iTools system, you may start by bringing up a surface plot in a surface tool and then import scattered point data into the same plot to see the relationship between two data sets. Or, you may start with an image display, overlay contours from another data set, and map

both the image and contours onto a three-dimensional surface representation of a third data set. By throwing new data into an iTool, it is easy to end up with a hybrid tool that can handle complex, composite visualizations.

Of course, you have always been able to create these kinds of powerful, composite visualizations in IDL to reveal important relationships and trends in data. The main enhancements the new iTools provide are more mouse interactivity, WYSIWYG (What-You-See-Is-What-You-Get) printing, built-in analysis, undo-redo capabilities, layout control, and better-looking plots. These robust, pre-built tools reduce the amount of programming IDL users must do to create interactive visualizations. At the same time, the iTools integrate in a seamless manner with the IDL Command Line, user interface controls, and custom algorithms. In this way, the iTools maintain and enhance the control and flexibility IDL users rely on for data exploration, algorithm design, and rapid application development.

Foundation for the Future

As you will discover, the iTools are compelling new tools to add to your arsenal. They complement the strong foundation that IDL has maintained over the course of its evolution. This foundation has made possible countless valuable user-written applications across many disciplines and industries. However, the iTools also represent the start of a new, updated display paradigm for IDL. While the iTools system in IDL is a powerful and flexible environment that will allow you to immediately accelerate your data interpretation and reporting, it is only the beginning. We will continue to build on this new technology in future releases. You can look forward to more functionality, flexibility, and optimization as the iTools system continues to grow.

We look forward to members of the IDL community building on the iTools system as well. The iTools source code is included in the IDL distribution to allow you to:

- extend the pre-built tools with your own operations, manipulations, visualization types, and GUI controls
- create your own custom tools based on the iTools component framework
- share your inventions with others in the IDL community via the ITT Visual Information Solutions User-Contributed Library (www.ittvis.com/codebank) or other avenues of collaboration and distribution

Note

For more information on building your own iTools or building hybrid iTools, see the *iTool Developer's Guide*.

Tips and instructions for using this guide are detailed in the following section.


Using This Guide

The *iTool User Guide* can show you important iTool functionality such as how to start the iTools, how to import data into an iTool, how to export data out of an iTool, the general layout of the iTools, and how to perform common iTool tasks.

This *User Guide* is organized to help you make the most of the IDL iTools. The User Guide contains the following chapters:

- [Chapter 2, “Importing and Exporting Data”](#) — This chapter introduces you to bringing data into the iTools as well as exporting data.
- [Chapter 3, “Visualizations”](#) — This chapter introduces what an iTool visualization is and how to work with visualizations.
- [Chapter 4, “Manipulating the Display”](#) — This chapter describes the various ways that you can manipulate your displays within an iTool.
- [Chapter 5, “Adding Annotations”](#) — This chapter describes the various types of annotations available in iTools and how to work with them.
- [Chapter 6, “Property Sheets and Browsers”](#) — This chapter describes the property sheets and browsers that are common to all iTools.
- [Chapter 7, “Common Operations”](#) — Many iTool operations are common to each tool. These operations are described in this chapter.
- [Chapter 8, “Working with Macros”](#) — This chapter describes macros in iTools and how they are created and used.
- [Chapter 9, “Working with Styles”](#) — This chapter describes iTool styles and how to create and work with them.
- [Chapter 10, “Working with Images”](#) — This chapter describes the iImage tool and gives you insight into unique image visualization and manipulation tasks.
- [Chapter 11, “Working with Surfaces”](#) — This chapter describes the iSurface tool and gives you insight into unique surfacing and surface manipulation tasks.
- [Chapter 12, “Working with Contours”](#) — This chapter describes the iContour tool and gives you insight into unique contouring and contour manipulation tasks.
- [Chapter 13, “Working with Plots”](#) — This chapter describes the iPlot tool and gives you insight into unique plotting and plot manipulation tasks.

- [Chapter 14, “Working with Volumes”](#) — This chapter describes the iVolume tool and gives you insight into unique volume visualization and volume manipulation tasks.
- [Chapter 15, “Working with Maps”](#) — This chapter describes the iMap tool and gives you insight into unique mapping and map manipulation tasks.
- [Chapter 16, “Working with Vectors”](#) — This chapter describes the iVector tool and gives you insight into unique vector and vector manipulation tasks.
- [Appendix A, “iTools Interface Reference”](#) — This appendix gives you a detailed look at the iTool interface and its components.
- [Appendix B, “Property Controls”](#) — This appendix describes the iTool controls used to set properties in the iTool property sheets.
- [Appendix C, “Operations Properties”](#) — This appendix describes the properties of the iTools found in the Operations Browser of each iTool.
- [Appendix D, “Visualization Properties”](#) — This appendix describes the properties of the iTools found in the Visualization Browser of each iTool.



Chapter 2

Importing and Exporting Data

This chapter describes how to access data using the iTool.

About the Data Manager	24	Importing Data from the IDL Session	41
Data Import Methods	27	Parameter Data and the Command Line ..	42
Importing Data from a File	34	Exporting Data	44
Working with Unknown Data	37		

About the Data Manager

All data used by any iTool is first loaded into the iTools *Data Manager*, which keeps track of which data items are associated with an iTool visualization. The Data Manager provides a convenient and structured environment in which to import and view files and variables.

The process of loading data into the Data Manager is entirely automatic if you specify data when launching an iTool at the IDL command line or if you open a data file using the **Open** command from the iTool's **File** menu. In these cases, the iTool will import the data in the specified file or variable and create a visualization of the default type for the selected data and the iTool you are using.

If you want more control over the process of creating a visualization, you can load data into the Data Manager manually, either from a data file or from one or more variables that exist in your current IDL session. Once a data item is placed in the Data Manager, it is available to all iTools until it is removed.

The IDL iTools support several *data types*. Data import and export capabilities within each iTool allow you to access these various types of data. Methods used to place data into the Data Manager are described in [this chapter](#). *File readers* allow you to import data stored in binary formats, ASCII files, and several image file types.

Note

You can also create file readers for other data types besides those provided in IDL. For more information on creating file readers and creating your own iTools, see [Chapter 9, “Creating a File Reader”](#) (*iTool Developer's Guide*).

Data Manager Interface

The Data Manager's graphical user interface consists of these elements:




Figure 2-1: The iTools Data Manager

- **Data Tree View** — This window, on the left side of the dialog, shows all of the data items available within the Data Manager. Depending on how data items were added to the Data Manager, they may be collected into groups of related items; for example, individual image channels associated with a true-color image will show up underneath the Data Manager entry for the image itself. The data tree view will be empty unless you have read or imported data into the Data Manager.
- **Data Properties**— This window, on the right side of the dialog, shows you all properties and their values for the data item selected in the data tree view.
- **Help** — This button will invoke the IDL online help system.
- **Import Variable** — This button allows you to select a variable in the IDL Main scope to import into the Data Manager. For more information on importing a variable into your Data Manager, see [“Importing Data from the IDL Session”](#) on page 41.
- **Import File** — This button allows you to select a data file to import into the Data Manager.
- **Dismiss** — This button will dismiss the dialog.

Data Item Management

In addition to the ability to import new data into the Data Manager, you can rename, duplicate, or remove existing data items.

- **Renaming data** — To rename a data item, enter a new name in the **Name** field on the data property sheet.
- **Deleting data** — To delete an unused or outdated data item, select the item in the tree view, click the right mouse button to display the Data Manager context menu, and choose the **Delete** option.

Note

Deletion is not reversible.

- **Duplicating data** — To create a copy of an existing data item, select the item in the tree view, click the right mouse button to display the Data Manager context menu, and choose the **Duplicate** option.

Data Import Methods

Data items in the Data Manager are available to all iTools until it they are removed. You can bring data into the iTool Data Manager in the following ways:

- Using the Data Import Wizard (**File** → **Import**)
- By opening a data file directly (**File** → **Open**)
- Using the **Import Variable ...** or **Import File...** buttons on the Data Manager dialog (**Window** → **Data Manager**)
- By specifying data parameters at the IDL command line. For example, specifying the following at the IDL command line:

```
iPlot, myDataVariable
```

places the variable `myDataVariable` in the Data Manager.

These methods are described in the following sections.

- [“Using the Data Import Wizard”](#) on page 28
- [“Using File Open”](#) on page 32
- [“Using the Data Manager Dialog”](#) on page 33
- [“Importing Data from the IDL Session”](#) on page 41

Note

Once data has been imported into the iTool and is visible in the Data Manager, there are a numerous ways to visualize the data. To learn more about visualizing data, see [Chapter 3, “Visualizations”](#).

Using the Data Import Wizard

The iTool *Data Import Wizard* steps you through the process of importing data into the Data Manager. Launch the Data Import Wizard by selecting **File** → **Import...** The Data Import Wizard has three screens:

1. Select the data source.

You can import data either from a data file or from the IDL session:

- **From a File** — allows you to select a data file to import.
- **From an IDL Variable** — allows you to select an IDL variable to import. For more information on importing a variable into your Data Manager, see [“Importing Data from the IDL Session”](#) on page 41.

2. Select the data and specify a data name.

If you are importing data from a file, the second screen of the Data Import Wizard contains the following items:

- **File Name** — The full path of the file want to open. You can populate this field using a standard dialog by clicking the **File Open** button.
- **File Open** button  — Displays the standard file-selection dialog.
- **File Type** — After a file is selected, the **File Type** field displays the format of the file.
- **Type Properties Window** — After a file is selected the properties window shows properties of the file reader that will import the data, if any exist. Modify these properties as necessary to import your data correctly.

Note

For more information about file format types that are available in iTools, see [“File Readers”](#) on page 99.

- **Data Import Name** — The name that will be used for the imported data in the Data Manager.

Importing some types of data files may cause IDL to present additional screens that describe the data before import.

- For image data see [“Importing Image Data”](#) on page 34
- For ASCII data see [“Importing ASCII Data”](#) on page 34
- For binary data see [“Importing Binary Data”](#) on page 35

If you are importing data from an IDL variable, the second screen of the Data Import Wizard contains the following items:

- **List of IDL Variables** — All variables available in the current IDL session are listed in a tree view.
- **Variable Information** — Information about the selected variable is displayed to the right of the tree view.
- **Data Import Name** — The name that will be used for the imported data in the Data Manager.

3. Select the type of visualization you want to create.

The Data Import Wizard will automatically create a new visualization of the selected type. Choosing <Default> will create the default visualization for the selected data type, regardless of the type of iTool into which you are importing the data.

Example: Importing a JPEG File

The following example describes how to import a JPEG image file using the Data Import Wizard and display the image:

1. From an iTool window select **File** → **Import**.




Figure 2-2: The IDL Data Import Wizard, Showing Step 1 of 3

2. Select **From a File** and click **Next**.




Figure 2-3: The IDL Data Import Wizard, Showing Step 2 of 3

3. Click the **File Open** button  just to the right of the **File Name** field and select the `endocell.jpg` file from the `examples/data` directory of the IDL distribution. Click **Next**.




Figure 2-4: The IDL Data Import Wizard, Showing Step 3 of 3

4. Select **Image** as the desired visualization to create since we have a JPEG image.
5. Click **Finish**. The data is imported into the Data Manager, and a new image visualization appears in the iTool window.

Note

The process of creating visualizations is discussed in detail in [Chapter 3, “Visualizations”](#).

Using File Open

Selecting a data file using **File** → **Open** will open the file using the default iTool file reader for the type of file you select. The data will be added to the Data Manager and the iTool will automatically create the default visualization for the data contained in the file.

If the data in the file you select is binary or ASCII, you will be prompted to specify further information that will allow the binary or ASCII file readers to correctly import the data. For an explanation of the handling of various file types see the following sections:

- For ASCII data see [“Importing ASCII Data”](#) on page 34
- For binary data see [“Importing Binary Data”](#) on page 35
- For ShapeFile data see [“Importing Shapefile Data”](#) on page 36
- For data of an unrecognized format see [“Working with Unknown Data”](#) on page 37

Using the Data Manager Dialog

Selecting **Window → Data Manager** opens the Data Manager dialog. You can then click the **Import Variable...** or **Import File...** button.

Importing a File

If you are importing data from a file, the File Import dialog appears. It contains the following items:

- **File name** — The full path of the file want to open. You can populate this field using a standard dialog by clicking the **File Open** button.
- **File Open** button  — displays the standard file-selection dialog.
- **Import options** — Displays a properties window shows properties of the file reader that will import the data, if any exist. Modify these properties as necessary to import your data correctly.

Note

For more information about file format types that are available in iTools, see [“File Readers”](#) on page 99.

- **Data import name** — The name that will be used for the imported data in the Data Manager.

Importing a Variable

If you are importing data from an IDL variable, the IDL Variable Browser appears. It contains the following items:

- **List of IDL Variables** — All variables available in the current IDL session are listed in a tree view.
- **Variable Information** — Information about the selected variable is displayed to the right of the tree view.
- **Data Import Name** — The name that will be used for the imported data in the Data Manager.
- **Import Type** — The variable type to be used for the imported data in the Data Manager.

Importing Data from a File

You can import data from several types of files into the iTool Data Manager. The following sections describe the process of importing different types of data.

- [“Importing Image Data”](#) on page 34
- [“Importing ASCII Data”](#) on page 34
- [“Importing Binary Data”](#) on page 35
- [“Importing Shapefile Data”](#) on page 36

Importing Image Data

You can visualize image data stored in many common file formats. Common image file formats accepted are:

- DICOM Images
- Graphics Interchange Format Images (GIF)
- Joint Photographic Experts Group (JPEG)
- JPEG2000 (JP2 or JPX)
- Macintosh PICT
- Portable Network Graphics (PNG)
- Tag Image File Format (TIFF)
- Windows Bitmap (BMP)

Note

You can also use the iTool’s export and export variable features to export image data and variables. For more information on exporting, see [“Exporting Data”](#) on page 44.

Note

For more information on the iImage tool and its functions and features, see [Chapter 10, “Working with Images”](#).

Importing ASCII Data

When you open a file containing ASCII data, you must specify the format of the file before the iTool can read the data and place it into the Data Manager. The iTool opens the **ASCII Template** dialog to allow you to specify the format of the ASCII data.

Note

You can also use the iTool's export and export variable features to export ASCII data and variables. For more information on exporting, see [“Exporting Data”](#) on page 44.

To import ASCII data in an iTool, select **File** → **Open** or click the **Import File** button in the Data Manager or Insert Visualization dialog. See [“Using the ASCII Template Dialog”](#) under [“ASCII_TEMPLATE”](#) (*IDL Reference Guide*) for instructions on how to use the dialog to define the structure of your ASCII data.

Note

Once data has been imported into the iTool and is visible in the Data Manager, there are a few ways to visualize the data. To learn more about visualizing data, see [Chapter 3, “Visualizations”](#).

For more information on using the ASCII file reader, see [“ASCII_TEMPLATE”](#) (*IDL Reference Guide*).

Importing Binary Data

When you open a file containing binary data that is not of a format recognized by any other file reader available to your iTool, you must specify the format of the file before the iTool can read the data and place it into the Data Manager. The iTool opens the **Binary Template** dialog to allow you to specify the format of the binary data.

Note

If the file contains binary data of a recognized format, such as TIFF or JPEG, the iTool will automatically choose the correct file reader to read the binary data.

Note

You can also use the iTool's export and export variable features to export binary data and variables. For more information on exporting, see [“Exporting Data”](#) on page 44.

To import binary data in an iTool, select **File** → **Open** or click the **Import File** button in the Data Manager or Insert Visualization dialog. See [“Using the BINARY_TEMPLATE Interface”](#) under [“BINARY_TEMPLATE”](#) (*IDL Reference Guide*) for instructions on how to use the dialog to define the structure of your binary data.

Note

Once data has been imported into the iTool and is visible in the Data Manager, there are a few ways to visualize the data. To learn more about visualizing data, see [Chapter 3, “Visualizations”](#).

For more information on the binary file reader, see [“BINARY_TEMPLATE”](#) (*IDL Reference Guide*).

For more information on plotting and plot functions, see [Chapter 13, “Working with Plots”](#).

Importing Shapefile Data

For more information on shapefiles and inserting them into an iTool, see [“Inserting an IDL Shapefile”](#) on page 345.

Note

Once data has been imported into the iTool and is visible in the Data Manager, there are a few ways to visualize the data. To learn more about visualizing data, see [Chapter 3, “Visualizations”](#).

Working with Unknown Data

If you supply data in a format not recognized by the current iTool, the **Create Visualization** dialog allows you to specify how the data is to be used.




Figure 2-5: The iTools Create Visualization Dialog

You will see this dialog if the data you supply when launching an iTool from the IDL command line does not match a known data organization for the selected tool, or if you open an ASCII text file containing data that appears to be irregularly gridded.

The **Create Visualization** dialog contains the following choices:

- **Launch the gridding wizard**
This option lets you transform irregularly-gridded data into regularly-gridded data using IDL's gridding routines. The resulting data is displayed by the iTool. See [“Using the Gridding Wizard”](#) on page 38 for details.
- **Select a visualization and specify parameters**
This option lets you manually specify how the data should be assigned to a selected visualization's parameters.
- **Do not create a visualization**

Using the Gridding Wizard

The iTools Gridding Wizard allows you to convert irregularly-gridded data into regularly-gridded data using a variety of methods. The gridding wizard processes your irregularly-gridded data in three steps.




Figure 2-6: The IDL Gridding Wizard Step 1 of 3

The **IDL Gridding Wizard Step 1 of 3** dialog contains the following items:

- **Number of points entered**
- **X Coordinates** — The X coordinate range
- **Y Coordinates** — The Y coordinate range
- **Data values** — The data minimum and maximum values
- **Spherical data checkbox** — Check this box if the data is spherical
- **Coordinate diagram** — Shows coordinates of grid data
- **Show points checkbox** — Select to show all points (default = checked)
- **Help** — Obtain help on this dialog
- **Back** — Return to previous step

- **Next** — Proceed to Step 2 of 3
- **Cancel** — Dismiss the Gridding Wizard



Figure 2-7: The IDL Gridding Wizard Step 2 of 3

The **IDL Gridding Wizard Step 2 of 3** dialog contains the following items:

- **X Coordinates** — modify dimension, start or end
- **Y Coordinates** — modify dimension, start or end
- **Coordinate diagram** — shows coordinates of grid data
- **Show points checkbox** — select to show all points (default = checked)
- **Help** — obtain help on this dialog
- **Back** — return to previous step
- **Next** — proceed to Step 3 of 3
- **Cancel** — dismiss the Gridding Wizard




Figure 2-8: The IDL Gridding Wizard Step 3 of 3

The **IDL Gridding Wizard Step 3 of 3** dialog contains the following items:

- **Choose gridding method** — choose from pull-down list. See [“GRIDDATA”](#) (*IDL Reference Guide*) for a discussion of the gridding methods.
- **Preview** — click to preview selected method and data
- **Auto preview** — checkbox to turn auto preview on (default = off)
- **Statistics tab** — shows data statistics
- **Options tab** — set options for missing values, smoothing, weighting, and anisotropy between axes
- **Search tab** — set options for using search ellipse
- **Coordinate diagram** — shows coordinates of grid data
- **Show points checkbox** — select to show all points (default = checked)
- **Help** — obtain help on this dialog
- **Back** — return to previous step
- **Finish** — dismiss the Gridding Wizard with data gridded
- **Cancel** — dismiss the Gridding Wizard

Importing Data from the IDL Session

Variables in your current IDL session can be imported into the Data Manager to be visualized in an iTool. Once you have entered variables into the IDL session at the command line, you can import a variable directly from the **Data Manager** dialog, or by using **File** → **Import**. See [Chapter 3, “Importing and Writing Data into Variables” \(Using IDL\)](#) for information on how to create variables that contain data within an IDL session.

Note

If you specify a variable as a parameter to the iTool at the IDL command line, the variable is automatically imported into the Data Manager.

The following is an example of importing a variable using the **Data Manager** dialog:

1. From the **Data Manager** dialog, select **Import Variable**. The **IDL Variable Browser** appears.




Figure 2-9: The IDL Variable Browser

2. From the **IDL Variable Browser** you can select available variables which you have created in your IDL session and click **Import** to add them to your Data Manager as available variables.




Figure 2-10: Imported Variable with Imported Files

After importing data into the Data Manager, you can display the data using the Insert Visualization dialog. See [“Inserting Visualizations”](#) on page 54 for details.

Importing Graphic Objects

You can import graphic objects into your iTool using the **Visualization** pull-down menu on the **Insert Visualization** window. Select **IDL Graphics Object** and then import your variable from the Data Manager into the **Graphics Object** field and select **Insert**.

When importing graphic objects into an iTool it is important to remember:

- If the object hierarchy being inserted as a graphic object does not have the `REGISTER_PROPERTIES` keyword set, then no properties will be available in your iTool when the object is visualized.

If the object hierarchy being inserted as a graphic object includes an image object, rotation may not behave as expected. For more information on image objects and their behavior, see [“Transformations of IDLgrImage Objects”](#) (Chapter 32, *IDL Reference Guide*).

Parameter Data and the Command Line

Parameter data can often be entered at the IDL command line in IDL when creating an iTool. Consider the following example:

1. At the IDL Command Line, enter the following:

```
myPlotData = RANDOMU(seed, 30)
iPlot, myPlotData
```

2. The variable `myPlotData` is inserted into the iTool Data Manager.
3. The following is produced in an iPlot window:




Figure 2-11: Reading Parameter Data in at the IDL Command Line

Note

See [Chapter 3, “Importing and Writing Data into Variables”](#) (*Using IDL*) for more information on Command Line data access.

Exporting Data

Data of many common file formats can be exported by IDL iTools. File formats that are exportable are:

- ASCII text
- Binary data
- Encapsulated Postscript (EPS)
- Graphics Interchange Format (GIF)
- iTools State
- Joint Photographic Experts Group (JPG)
- JPEG2000
- Macintosh PICT
- Portable Network Graphics (PNG)
- Tag Image File Format (TIFF)
- Windows Bitmap (BMP)
- Windows Enhanced Metafile (WMF)

You can export data from an iTool to a data file or back to the current IDL session:

- [“Exporting Data to a File”](#) on page 45
- [“Exporting Data to the IDL Session”](#) on page 48

These methods are discussed next.

Exporting Data to a File

You can export the contents of an entire iTool window into a single image or data file using the IDL Data Export Wizard.

For example, to export a file:

1. Select **File** → **Export**. The **IDL Data Export Wizard** appears.




Figure 2-12: The IDL Data Export Wizard, Showing Step 1 of 3

2. The first step asks you to choose to export the data to either a file or an IDL variable. Select **To a File** and then **Next**.

Note

For more information on exporting data to an IDL variable, see the following section, [“Exporting Data to the IDL Session”](#) on page 48.




Figure 2-13: The IDL Data Export Wizard, Showing Step 2 of 3

3. From the next screen, select the data which you wish to export. Notice that only the Window level or View level can be exported. Click **Next**.




Figure 2-14: The IDL Data Export Wizard, Showing Step 3 of 3

4. You are now prompted for selection of the destination and file type. After entering a desired filename, extension, and destination, click **Finish**. The file is then exported.

Exporting Data to the IDL Session

You can export data from an iTool into a single variable using the IDL Data Export Wizard.

For example, to export data to an IDL variable:

1. Select **File** → **Export**. The **IDL Data Export Wizard** appears.



Figure 2-15: The IDL Data Export Wizard, Exporting a Variable Step 1 of 3

2. Select **To an IDL Variable**.




Figure 2-16: The IDL Data Export Wizard, Exporting a Variable Step 2 of 3

3. From the next screen, select the data that you wish to export. Notice that only data items can be exported as variables. Click **Next**.





Figure 2-17: The IDL Data Export Wizard, Exporting a Variable Step 3 of 3

4. The final screen and step allow you to name your variable as you wish. A default name also appears as representative of the data item. Name your variable and click **Finish**.
5. The variable will now appear in the IDL Variable Watch window.

Exporting via Context Menu

An alternate way to export a variable to IDL is to select the variable within the Visualization browser and right-click to choose **Export to IDL**. For more information on the Visualization browser, see [Appendix D, “Visualization Properties”](#).



Chapter 3

Visualizations

This chapter describes how working with visualizations within the iTool.

About Visualizations	52	Inserting Visualizations	54
Visualization Creation Methods	53	Modifying Existing Visualizations	56
Creating Visualizations Automatically	53	Exporting Visualizations	58

About Visualizations

A *visualization* is a graphical representation of data that has been imported into the iTool Data Manager. This might mean a plot, image, or surface just to name a few. Visualizations can be created in any iTool window either automatically or manually. Visualizations can also be modified and exported. These topics are all discussed in [this chapter](#).

When data is imported into the IDL iTools system, it resides in the Data Manager. The Data Manager provides a convenient interface within which you can organize and manage data. For more information on importing and exporting data in an iTool and the use of the Data Manager, see [Chapter 2, “Importing and Exporting Data”](#).

This chapter deals with the process of visualizing data that is already imported into an iTool. Visualizations can be created automatically at the IDL Command Line or can be inserted manually within an existing tool window. Once created, visualizations contain parameters which can be modified in various ways. Visualizations can also be exported from an iTool. These topics are all discussed in detail in this chapter.

Visualization Creation Methods

Visualizations can be created either automatically or manually. The following sections discuss automatic and manual creation methods.

Creating Visualizations Automatically

Visualizations can be created automatically in the following ways:

- By specifying some data when creating an iTool at the IDL Command Line. For example:

```
myPlotData = RANDOMU(seed, 30)
iPlot, myPlotData
```

These statements will create a new data item in the iTool Data Manager and create a new iPlot tool that visualizes the data in a line plot.

- By opening a file in an existing iTool, either by selecting **File** → **Open** or using the Data Import Wizard (**File** → **Import...**).
- By using the Data Import Wizard (**File** → **Import...**) to import a variable from the IDL Session.

Both the Data Import Wizard and the process of using **File** → **Open** are described in detail in [Chapter 2, “Importing and Exporting Data”](#).

Note

Certain data types (such as binary or ASCII) may require you to supply IDL with further information before they can be visualized. For more information about reading certain data types into iTools, see [“Importing Data from a File”](#) in Chapter 2.

Inserting Visualizations

If you already have the necessary data in the iTool Data Manager, you can manually create a visualization in your iTool. This is done from your desired iTool window by selecting **Insert** → **Visualization**.

To access data using **Insert** → **Visualization** from your tool:

1. Start an iTool.
2. Select **Insert** → **Visualization**. The **Insert Visualization** Dialog appears.




Figure 3-1: Insert Visualization Dialog With Image Visualization Type Selected

The **Insert Visualization** dialog contains the following items:

- **Data Tree View** — this tree contains any imported data and/or variables available for visualization in the Data Manager.
- **Data Properties** — this area, to the right of the Data Tree View, shows the properties of any selected Data Tree elements.
- **Select a Visualization Drop-down Menu** — this menu allows you to select the visualization type to use with the selected data.

- **Parameter Property Sheet**— these are the input parameters for the visualization type selected in the Visualization Type Drop-down Menu. These input variables will change per visualization type.
 - **Parameter Data Types Window** — this window to the right of the parameters table shows the properties of the selected parameter.
 - **Help** — this button will invoke the help system.
 - **Import Variable** — gives you the ability to select a variable to import into the Data Manager. For more information on importing a variable into your Data Manager, see [“Importing Data from the IDL Session”](#) on page 41.
 - **Import File** — gives you the ability to select data from a file to import into the Data Manager. For more information on importing a file into your Data Manager, see [“Importing Data from a File”](#) on page 34.
 - **Insert Button** — this button will insert the specified visualization into the current iTool. Insert is only active if data is associated with all required parameters.
 - **Dismiss** — this button will dismiss the dialog.
3. Select the visualization type from the visualization type drop-down menu.
 4. Next, assign data in the dialog to the parameters of the visualization being inserted.
 5. Now click **Insert** to finish inserting the visualization.

Modifying Existing Visualizations

Once you have created your visualization, you can modify it as you wish. Use the Parameter Editor to modify parameter data.

The Parameter Editor

The Parameter Editor is very similar to the Insert Visualization dialog. It shows the data tree view and parameter property sheet and parameter data types window.

If you have already created a visualization, you can change the data associated with one or more visualization parameters using the Parameter Editor. To display the Parameter Editor, select your visualization, then select **Edit** → **Parameters....**




Figure 3-2: Parameter Editor

Note

The Parameter Editor contains all of the fields shown in the Insert Visualization dialog, with the exception that you cannot change the visualization type of the selected visualization. See “[Inserting Visualizations](#)” on page 54 for details.

To associate data with a visualization's parameters using the Parameter Editor:

1. Select **Edit** → **Parameters**.
2. Do one of the following:
 - Select an item already in the Data Tree View.
 - Click **Import File** to import a file into the Data Tree View, and select the file.
 - Click **Import Variable** to import a variable into the Data Tree View, and select the variable.
3. Assign items to the appropriate input parameter and data item, then double-clicking or by selected the down arrow just below the Data Tree View.
4. Click **Apply** to apply your new changes or **Dismiss** to close the Parameter Editor.

Note

The **Apply** button will not be available unless all required parameters have been assigned within a visualization.

Removing Data Associations

Once a visualization has been created, you can always remove associations within the parameter editor. Select the parameter in the parameter property sheet and click the X button between the data tree view and the parameter property sheet.

Note

If you remove a required parameter, you will not be able to apply your changes until you select a new data item for that parameter.

Replacing Data Associations


To replace the data associated with a given parameter, select the parameter in the parameter property sheet, then select a new data item in the data tree. Double-click or click the down arrow button to replace the data associated with the selected parameter.

Exporting Visualizations

Any iTool visualization can be saved. In order to save your visualization, select **File** → **Save As...** and then name the file. The file will automatically be assigned the extension `.isv`.

Exporting to a File

You can export data from an iTool to a data file or back to the current IDL session. For more information on exporting to a file, see [“Exporting Data”](#) in Chapter 2.



Chapter 4

Manipulating the Display

This chapter describes the following common tasks that can be performed with all of the IDL Intelligent Tools:

Introduction	60	Scaling	65
Selection of Objects	61	Zooming	70
Undo/Redo	62	View Panning	72
Adding a Data Space	63	Window Layouts	73
Translation	64		

Introduction

The Standard IDL iTools supplied in the IDL distribution comprise seven distinct tools: iImage, iPlot, iSurface, iContour, iVolume, iMap, and iVector. Each tool performs a specific set of tasks related to the type of data it is designed to use. In addition to these specific tasks, all six tools have a number of manipulation tasks in common. This chapter describes only these common display manipulation tasks; for information about specific tasks performed by the individual iTools, refer to the chapters describing those tools.

Note

This chapter describes manipulation tasks related only to the Standard IDL iTools, those iTools supplied in the IDL distribution. Other iTools written by users and third-party developers share a common interface with the ITT Visual Information Solutions iTools because the iTools framework is used to create all iTools. However, the specific functionality of such iTools may be different from the functionality of the iTools described here.

Selection of Objects

iTool elements such as axes and annotations have objects associated with them. These objects have their own associated *properties* — such as color, line style, size, and so on. There are two ways to select objects in IDL iTools:

- With the Select arrow
- From the Visualization Browser

To select an object or group of objects with the Select arrow:

1. If necessary, click the Select button  on the toolbar to enter Select mode.
2. Position the arrow mouse pointer over the object and click. A selection box appears around the object.
3. To select additional objects, hold down the SHIFT key while clicking them.

To select an object or group of objects from the Visualization Browser:

1. Select **Window** → **Visualization Browser**.
2. Click the name of the object in the Visualization Browser list. A selection box or selection highlight appears on that object in the iTool window.
3. To select additional objects, hold down the Shift key while selecting the names of additional objects in the Visualization Browser list.

Select All

Select All selects all objects (visualizations, annotations, legends, etc.) displayed in the iTool window.

To select all objects:

1. Select **Edit** → **Select All**. All displayed objects are selected.
2. CTRL + click to deselect any objects that you do not want to include.

Undo/Redo

Any action performed in an iTool window can be undone or redone. The Undo and Redo mechanism provides a useful way of retracing and repeating steps that have been performed in the iTool window.

Note

Operations which cannot be undone are Open, Save, Export, Export variable, Print, Exit, and window moving and resizing.

To undo the most recent action, do one of the following:

- Select **Edit** → **Undo**
- Click 

To undo multiple actions, simply repeat these commands. When no more actions remain to be undone, the Undo menu item or toolbar button is no longer active.

To repeat actions that have been undone, do one of the following:

- Select **Edit** → **Redo**
- Click 

Tip

Look at the text following the Undo or Redo menu item, or hover the mouse pointer over the Undo or Redo button on the toolbar to display the tooltip, to identify the action that will be undone or redone.

Adding a Data Space

The data space is the area within your visualization window where imported data appears. A data space is added automatically when data is visualized directly into an iTool window. However, if you desire to add a data space manually to any of the iTools, you can select **Insert** → **Data Space** from the iTool window.

Translation

Translation moves an object or group of objects in a specified direction. When an object is selected, a bounding box appears around the object.

To translate a selected object to another location:

1. Position the pointer inside the bounding box. The mouse pointer changes to the translation pointer .
2. Drag in the desired direction. The entire object moves to the new location.




Figure 4-1: Translating Objects

Note

For information on creating a surface visualization which you can translate such as the one shown in the previous figure, see [Chapter 11, “Working with Surfaces”](#).

Note

An axis (or axes) will behave differently during translation if any other object is also selected.

Scaling

Two types of scaling are possible: constrained scaling and unconstrained scaling.

Constrained Scaling

Constrained scaling permits scaling of only one dimension while preserving the other dimensions.

Constrained Scaling of 2-D Objects

To scale one dimension of a 2-D object, click on the object so that eight small selection-boxes appear at each corner of the object and also midway along each side of the object. Then position the mouse onto one of these boxes so that the mouse pointer changes to a four-headed arrow pointer (see the following figure). Drag the mouse in the desired direction to scale the object in the selected dimension.




Figure 4-2: Resizing a 2-D Plot

Constrained Scaling of 3-D Objects

Two types of constrained scaling are available for 3-D objects: multiple-axis scaling and single-axis scaling.

The multiple-axis scaling mouse pointer for 3-D objects is a three-headed arrow  displayed when the mouse pointer is positioned over a corner of a 3-D object's data space. Dragging the constrained scaling pointer scales the object a fixed distance along all axes in the direction of the drag.




Figure 4-3: Constrained Scaling

The single-axis scaling pointer for 3-D objects is a two-headed arrow $\updownarrow$, displayed when the pointer is positioned over an axis “whisker” in a 3-D image. Dragging an axis “whisker” scales the object only in the direction of the arrows.




Figure 4-4: Resizing a 3-D Surface

Unconstrained Scaling

Unconstrained scaling allows you to scale all dimensions of an object at once from any point within the object. Unconstrained scaling is different for 2-D and 3-D objects.

Unconstrained Scaling of 2-D Objects

Unconstrained scaling of 2-D objects occurs when a corner of the data set bounding box is dragged. The mouse pointer changes to an unconstrained scaling pointer , and the object is scaled in the direction of the drag.




Figure 4-5: Unconstrained Scaling of a 2-D Plot

Unconstrained Scaling of 3-D Objects

Unconstrained scaling of 3-D objects occurs when a single side of the data set bounding box is dragged. The mouse pointer changes to an unconstrained scaling pointer , and the object is scaled along the dimensions of the selected side.




Figure 4-6: Unconstrained Scaling of a 3-D Surface

Zooming

Two types of zooming are available in all iTools:

- **Canvas Zoom** changes the magnification of the entire display canvas (everything in the iTool window). If the display canvas is larger than the iTool window, scroll bars appear.
- **View Zoom** changes the magnification applied to the selected view. If the size of the view is larger than the visible portion of the view (that is, if the view zoom is greater than 100%), the *view pan* manipulator becomes active, allowing you to move different portions of the view into the visible area.

Canvas Zoom

Canvas Zoom increases or decreases magnification of the entire iTool window without moving the observer's "eye."

To zoom in or out with Canvas Zoom:

1. Select **Window** → **Canvas Zoom** and select a percentage from the list.
 - To increase magnification, choose a percentage greater than **100%**.
 - To decrease magnification, choose a percentage less than **100%**.
2. Select **100%** to return to the default magnification.

View Zoom

View Zoom increases or decreases magnification of items in the currently selected view in an iTool window. This is similar to moving the observer's "eye" closer to or farther away from the objects in the view. You can change the view zoom using the view zoom button or by using the view zoom pull-down menu.

To use the view zoom button:

1. Click Zoom  on the toolbar to enter Zoom mode.
2. Position the mouse pointer on the viewplane. The pointer changes to a zoom pointer .

3. Do any of the following:
 - Drag the zoom pointer toward the top of the iTool window to enlarge the display
 - Drag the zoom pointer toward the bottom of the iTool window to make the display smaller
 - Use the mouse scroll wheel to make the display larger or smaller
4. Click on the arrow Select button to leave Zoom mode and return to Select mode. The mouse pointer changes to an arrow pointer. In Select mode, dragging the arrow pointer positions the zoomed image.

The view zoom combobox is located just to the right of the view zoom manipulator button on the toolbar and always reports the zoom factor of the currently selected view. You can also use this combobox to set a requested zoom factor for the currently selected view by simply using the pull-down menu to select a value.

View Panning

The view pan button appears on the iTool's toolbar as a hand (shown depressed below) and allows panning within an iTool view by clicking and dragging the mouse.



Figure 4-7: View Pan Selected

Notice that panning will only be possible if the iTool view is not completely within the window, or the iTool view is larger than viewable area of the window.

Window Layouts

You can change the minimum size of the canvas displayed in the iTool window, display multiple views in the iTool window, or select a preset arrangement of views, with the Window Layout dialog.




Figure 4-8: Window Layout Tool

Note

If you are in Freeform mode, canvas size can also be changed interactively by dragging the corners or sides of the iTool window.

To change the minimum size of the canvas displayed in the iTool window:

1. Select **Window** → **Layout**.
2. Edit the pixel values in the **Width** and **Height** text boxes (Default = Width 512, Height 384). A preview of the shape of the new canvas size is displayed in the Preview window.
3. Click **OK** to apply the changes or **Cancel** to close the window without applying changes.


To change the number of views displayed:

1. Select **Window** → **Layout**.
2. Select **Gridded** from the Layout list.
3. Edit the number of columns and rows in the Grid text boxes (Default = 1 by 1).

- Click **OK** to apply the changes or **Cancel** to close the window without applying changes.

To select a preset arrangement of views:

- Select **Window** → **Layout**.
- Select from the following arrangements in the Layout list:



- Click **OK** to apply the changes, or **Cancel** to close the window without applying changes.



Chapter 5

Adding Annotations

This chapter describes the following common tasks that can be performed with all of the IDL Intelligent Tools:

Introduction	76	Annotations	79
Legends	77	Additional Axes	84

Introduction

The Standard IDL iTools supplied in the IDL distribution (iImage, iPlot, iSurface, iContour, iVolume, iMap, and iVector) each possess common annotation capabilities. This chapter describes this common annotation functionality and how it can be used.

Note

This chapter describes Annotation functionality for only the Standard IDL iTools, those iTools supplied in the IDL distribution. Other iTools written by users and third-party developers share a common interface with the ITT Visual Information Solutions iTools because the iTools framework is used to create all iTools. However, the specific functionality of such iTools may be different from the functionality of the iTools described here.

Legends

Legends identify the visualizations displayed in the iTool window. For example, a legend displayed in an iPlot window can include a description of each plot line in a plot. Or a legend can be displayed in an iSurface window to identify surfaces and contour levels displayed on those surfaces.

To insert a legend for a surface or contour:

1. Select specific items to include in the legend, or click in an empty area of the iSurface window dataspace to select the dataspace and include all items in the legend.
2. Select **Insert** → **New Legend**.

To add to a legend:

1. Select the visualization item or items to add to the legend.
2. If there are multiple legends, add the desired legend to the selection by shift-clicking the legend border.
3. Select **Insert** → **Legend Item**.

Note

Only a single legend item may exist for a given visualization. If you are inserting multiple visualization items into an existing legend, only legend items for those visualizations not already represented will be added to the legend.

Each legend entry consists of a sample and a label. For example, in [Figure 5-1](#), the sample for the first entry is an unbroken line of thickness 1, and the label is Noisy Sine Plot. The sample for the second is a broken blue line of thickness 2, and the label is Clean Sine Plot.




Figure 5-1: Legend for Two Plot Lines

Tip

To alter your legend's properties such as in the example shown previously, display the property sheet. To do this, double-click the border of the legend box.

Annotations

The following types of annotations can be added to iTool visualizations:

Annotation Type	Description
Text	Single lines or multiple lines of text can be added to a visualization to provide a label or description.
Line	Straight line annotations can be added to a visualization to link labels to objects or to identify an object.
Rectangle	Rectangular annotations can be added to a visualization to identify rectangular areas.
Oval	Oval annotations can be added to a visualization to identify circular areas.
Polygon	Polygon annotations can be added to a visualization to identify areas bounded by a multi-sided polygon.
Freehand	Freehand annotations can be added to a visualization to identify an area.

Table 5-1: Types of Annotations

Note

Annotations are 2-D in nature and are defined in their own data space. They are most useful for adding notes to a data visualization for which the orientation has been finalized.

Text Annotations

To add a text annotation:

1. Click the Text Annotation button  on the toolbar.
2. Click anywhere on the canvas. A text insertion bar appears where you click.

3. Type the annotation text.
 - To add a new line, press **Ctrl + Enter**
 - To add superscript characters, press **Ctrl + U**
 - To add subscript characters, press **Ctrl + D**
 - To return to normal characters, press **Ctrl + N**

Note

For information on how to embed these and other formatting commands from the Text Annotation property sheet, refer to [“Text Annotation Properties”](#) on page 514.

4. Press Enter. A bounding box appears around the annotation text.
 - To position the annotation, position the mouse pointer within the bounding box so that it changes to a translation pointer . Click and drag the annotation to the desired location.
 - To display and modify text annotation properties such as font, text color and transparency, double-click the bounding box or inside the bounding box.

Line Annotations

To add a line annotation:

1. Click the Line Annotation button  on the toolbar.
2. Click in an empty part of the canvas and, without releasing the mouse button, drag to draw a line of the desired length.
 - To constrain in the direction that you are drawing, hold down the **Shift** key while drawing
 - To draw the line from the center, hold down the **Ctrl** key while drawing

3. Release the mouse button. Selection handles appear at both ends of the line annotation.
 - To position the line annotation, position the mouse pointer over the selected line so that it changes to a translation pointer . Click and drag the annotation to the desired location.
 - To resize the line annotation, position the mouse pointer over the selection handle at one end of the line so that it changes to a resize pointer . Click and drag the selection handle to obtain the desired line length.
 - To display and modify line annotation properties such as line thickness and arrow style, double-click the annotation.

Rectangle Annotations

To add a rectangle annotation:

1. Click the Rectangle Annotation button  on the toolbar.
2. Click in an empty part of the canvas and, without releasing the mouse button, drag to draw a rectangle of the desired size.
 - To constrain the rectangle to a square, hold down the **Shift** key while drawing
 - To draw the rectangle from the center, hold down the **Ctrl** key while drawing
3. Release the mouse button. Selection handles appear at the corners and sides of the rectangle annotation.
 - To position the rectangle annotation, position the mouse pointer inside the selected rectangle so that it changes to a translation pointer . Click and drag the annotation to the desired location.
 - To resize the rectangle annotation, position the mouse pointer over the selection handle on one side of the rectangle so that it changes to a resize pointer . Click and drag the selection handle to obtain the desired shape.
 - To scale the rectangle annotation, position the mouse pointer over the selection handle at one corner of the rectangle so that it changes to an unconstrained scaling pointer . Click and drag the selection handle to obtain the desired scaling.
 - To display and modify rectangle annotation properties such as background color and transparency, double-click the annotation.

Oval Annotations

To add an oval annotation:

1. Click the Oval Annotation button  on the toolbar.
2. Click in an empty part of the canvas and, without releasing the mouse button, drag to draw a circular annotation of the desired size.
 - To constrain the oval to a circle, hold down the **Shift** key while drawing.
 - To draw the oval from the center, hold down the **Ctrl** key while drawing.
3. Release the mouse button. Selection handles appear at the corners and sides of the oval annotation.
 - To position the oval annotation, position the mouse pointer inside the selected oval so that it changes to a translation pointer . Click and drag the annotation to the desired location.
 - To resize the oval annotation, position the mouse pointer over the selection handle on one side of the oval so that it changes to a resize pointer . Click and drag the selection handle to obtain the desired shape.
 - To scale the oval annotation, position the mouse pointer over the selection handle at one corner of the oval so that it changes to an unconstrained scaling pointer . Click and drag the selection handle to obtain the desired scaling.
 - To display and modify oval annotation properties such as background color and transparency, double-click the annotation.

Polygon Annotations

To add a polygon annotation:

1. Click the Polygon Annotation button  on the toolbar.
2. Click in an empty part of the canvas to specify the first point of the polygon.
3. Click again to specify the second point of the polygon. A line is drawn to connect the first and second points.
4. Click to specify the third and each consecutive point of the polygon. Lines are drawn to connect each subsequent point, forming a multi-sided shape.

Tip

To remove the last point, press the Esc key.

5. Double-click to specify the last point of the polygon. Selection boxes appear at the corners and sides of the newly-created annotation.
 - To position the polygon annotation, position the mouse pointer inside the selected polygon so that it changes to a translation pointer . Click and drag the annotation to the desired location.
 - To resize the polygon annotation, position the mouse pointer over the selection handle on one side of the polygon so that it changes to a resize pointer . Click and drag the selection handle to obtain the desired shape.
 - To scale the polygon annotation, position the mouse pointer over the selection handle at one corner of the polygon so that it changes to an unconstrained scaling pointer . Click and drag the selection handle to obtain the desired scaling.
 - To display and modify polygon annotation properties such as background color and transparency, double click the annotation.

Freehand Annotations

To add a freehand annotation:

1. Click the Freehand Annotation button  in the toolbar.
2. Click in an empty part of the canvas and, without releasing the mouse button, drag to draw a freehand shape.
3. Release the mouse button. Selection handles appear at the corners and sides of the selected freehand annotation.
 - To position the freehand annotation, position the mouse pointer inside the selected freehand shape so that it changes to a translation pointer . Click and drag the annotation to the desired location.
 - To resize the freehand annotation, position the mouse pointer over the selection handle on one side of the freehand shape so that it changes to a resize pointer . Click and drag the selection handle to obtain the desired shape.
 - To scale the freehand annotation, position the mouse pointer over the selection handle at one corner of the freehand shape so that it changes to an unconstrained scaling pointer . Click and drag the selection handle to obtain the desired scaling.
 - To display and modify rectangle annotation properties such as background color and transparency, double-click the annotation.

Additional Axes

By default, X, Y, and (for 3-D data spaces) Z axes are displayed in the iTool window. The display of these axes is controlled by property sheets for the axes container and for individual axes (see “[Axes](#)” on page 485). Additional X, Y or Z axes can be added to most data spaces to make it easier to identify characteristics.


To add an additional axis to your data space:

1. Select the data space.
2. Select **Insert** → **Axis**.
3. Choose from the following options:
 - X axis
 - Y axis
 - Z axis

Use the mouse to position the new axis, and double-click the axis to display the axis property sheet.

Note

For a 3-D visualization, you can use the **Shift + Ctrl** to translate an axis in the opposite direction. This will be shown in the Status message when an axis is selected for translation. You can also use the arrow keys to change axes placement direction.



Chapter 6

Property Sheets and Browsers

This chapter describes the following common tasks that can be performed with all of the IDL Intelligent Tools:

Introduction	86	The Preferences Browser	95
Property Sheets	87	The Operations Browser	93
The Visualization Browser	90		

Introduction

The Standard IDL iTools supplied in the IDL distribution (iPlot, iSurface, iContour, iVolume, iMap, and iVector) each share several common property sheets and browsers. This chapter discusses those property sheets and browsers and their uses.

Note

This chapter describes only the Standard IDL iTools, those iTools supplied in the IDL distribution. Other iTools written by users and third-party developers share a common interface with the ITT Visual Information Solutions iTools because the iTools framework is used to create all iTools. However, the specific functionality of such iTools may be different from the functionality of the ITT Visual Information Solutions iTools described here.

Property Sheets

Most iTool visualizations and operations have attributes or *properties* that can be modified to change their characteristics. These properties are organized into *property sheets* for each operation and visualization type. For example, the skin of a surface visualization has a gold color by default. To change this color, modify the surface color property in the surface visualization property sheet.

A property sheet consists of rows and columns. The left-most column identifies the properties, and the other column or columns identify the property values of one or more objects. A single property value can be selected at one time. When a single property value is clicked on, the associated property name appears indented. In the Style Editor and Macro Editor, multiple properties can be selected at a single time as shown in the following figure. Hold down the **Ctrl** key while left-clicking with the mouse to make nonadjacent selections, or hold down the **Shift** key to select an adjacent range of properties.




Figure 6-1: Property Sheet with Multiple Property Selections

Visualization Property Sheets

Visualization property sheets can be displayed from the Visualization Browser or from the iTool window.

To display a visualization's property sheet from the Visualization Browser:

1. Select **Window** → **Visualization Browser**.
2. Select the name of the object in the Visualization Browser list. The object's properties are displayed in the right-hand pane of the Visualization Browser window (the small arrows at the top-left of the Browser window will allow you to display both panes).

To display a visualization's property sheet from the iTool window:

1. Click to select the object in the iTool window.
2. Do one of the following to display the property sheet for the selected visualization:
 - Double-click the visualization in the iTool window
 - Select **Edit** → **Properties**
 - Right-click to display the Context Menu, and select the **Properties** menu item

Note

For detailed information on Visualization Browser properties, see [Appendix D, “Visualization Properties”](#).

Operations Property Sheets

Operations property sheets can only be displayed from the Operations Browser. To display an operations property sheet:

1. Select **Operations** → **Operations Browser**.
2. Select the name of the operation in the Operations Browser list. The operation properties are displayed in the right-hand pane of the Operations Browser window (the small arrows at the top-left of the Browser window will allow you to display both panes).

Note

For detailed information on Operations Browser properties, see [Appendix C, “Operations Properties”](#).

The Visualization Browser

The Visualization Browser provides access to *visualizations* (objects displayed in the iTool window) and the properties of those visualizations. When the Visualization Browser is displayed, you can select graphical objects from a nested list and display the property sheets for those objects. For example, if a surface visualization is displayed and you would like to change the appearance of the X axis in that visualization, you can select the axis in the Visualization Browser (Figure 6-2), display the property sheet for that axis (Figure 6-3), and modify the properties to change the appearance of the axis.




Figure 6-2: Visualization Browser with Axis 0 Selected

To select an object with the visualization browser:

1. Select **Window** → **Visualization Browser**.
2. Select the name of the object in the list. The element is highlighted in the iTool window.
 - To expand a list item, click the + icon 
 - To collapse an expanded list item, click the - icon 

3. To display the property sheet for the object, click the expansion button to the right of the list or double-click the property.




Figure 6-3: Visualization Browser with Property Sheet Displayed

4. To change a property setting, click in the settings column.
 - If a drop-down button  appears in the settings column, click the button to choose a new setting from the list of options, activate a slider to change the setting value, display a selection dialog or list, or display an Edit button providing access to a user-defined property control.
 - If the text is editable, edit the text to change the setting.

See [Appendix B, “Property Controls”](#) for a detailed description of the types of property settings included in property sheets.

5. Click the Close button  to close the Visualization Browser.

Note

Properties of standard graphical objects are described in detail in [Appendix D, “Visualization Properties”](#) and in the “IDL Commands” chapter of the *IDL Reference Guide*.

The Operations Browser

The Operations Browser provides a quick way to display and modify the properties for a given iTool *operation* (task performed on iTool data) before that operation is performed. For example, to display the properties of the Convolution filter, select the name of the filter in the left pane of the Operations Browser (see [Figure 6-4](#)), and modify the Scale factor property value in the right pane to change the default scale factor for convolution.




Figure 6-4: Operations Browser with Convolution Filter Properties Displayed

The Operations Browser displays a nested list of operations available in the current iTool in the left pane, and a property sheet for the currently selected operation in the right pane.

- To expand a list item, click the + icon
- To collapse an expanded list item, click the - icon

To change the properties of an operation from the Operations Browser:

1. Select **Operations** → **Operations Browser**.
2. Select the name of the operation in the list. A list of properties and the property settings appears in the right-hand pane of the Operations Browser window.

3. Locate the property you want to change in the list, and click in the settings column.
 - If a drop-down button  appears in the settings column, click the button to choose a new setting from the list of options, activate a slider to change the setting value, display a selection dialog or list, or display an Edit button providing access to a user-defined property control.
 - If the text is editable, edit the text to change the setting.
- See [Appendix B, “Property Controls”](#) for a detailed description of the types of property settings included in property sheets.
4. Click the Close button  to close the Operations Browser.

Note

Properties of standard iTool operations are described in [Appendix C, “Operations Properties”](#) and in the “IDL Commands” chapter of the *IDL Reference Guide*.

The Preferences Browser

The Preferences Browser provides a means of setting *preferences*, or default properties, for the general settings and file readers and writers used by all iTools. For example, if you prefer default drag quality to be low rather than high, you can change the default property for Default drag quality from **High** to **Low** in the Preferences Browser, as shown in [Figure 6-5](#).




Figure 6-5: Preferences Browser with Contour Projection Properties Displayed

For more information on the property sheets displayed in the right-hand pane of the Preferences Browser, see [Appendix D, “Visualization Properties”](#).

The Preferences Browser displays a nested list of general preferences, file readers, and file writers available for all iTools in the left pane, and a property sheet for the currently selected item in the right pane.

- To expand a list item, click the + icon
- To collapse an expanded list item, click the - icon

To change the properties of a general setting, file reader, or file writer from the Preferences Browser:

1. Select **File** → **Preferences**.
2. Select the name of the general setting, file reader, or file writer in the list. A list of properties and the current property settings appears in the right-hand pane of the Preferences Browser window.
3. Locate the property you want to change in the list, and click in the settings column.
 - If a drop-down button  appears in the settings column, click the button to choose a new setting from the list of options, activate a slider to change the setting value, display a selection dialog or list, or display an Edit button providing access to a user-defined property control.
 - If the text is editable, edit the text to change the setting.
4. Click the Close button  to close the Preferences Browser.

Note

Changes to preferences are saved between iTool sessions. When the **OK** button is clicked, preferences are saved in their current state.

General Settings

The first option on the Preferences Browser is the General Settings option. Settings listed here will be applied to all iTools if altered. The properties listed here are:

Property	Control Type: Values
Unlimited Buffer	Boolean: Set to determine undo/redo buffer size as limited or unlimited: • True (limited) • False (unlimited) Default = True
Zoom on Window Resize	Boolean: Set to determine if iTool visualizations resize upon view resizing: • True • False Default = False
Change directory on open	Boolean: Set to be prompted to change directory upon open: • True • False Default = True
Default working directory	Select Edit to bring up the Browse for folder dialog. Default = none
Default style	Boolean: Select from existing style list. Default = none
Default drag quality	Boolean: Set the window drag quality. • Low • Medium • High Default = High

Table 6-1: General Settings Properties

Property	Control Type: Values
Printer output format	Boolean: Set the format for printing output. • Bitmap • Vector Default = Bitmap
Clipboard output format	Boolean: Set the output format for clipboard copied data. • Bitmap • Vector Default = Bitmap

Table 6-1: General Settings Properties (Continued)

Note

The **Restore Defaults** button at the bottom of the Preferences Browser restores all default settings immediately.

File Readers

Select this folder to edit file reader preferences and properties. Available file reader types and their editable properties are listed in the following tables. For more information on reading in data of various types, see [Chapter 2, “Importing and Exporting Data”](#).

ASCII text

The ASCII text File Reader properties are:

Property	Control Type: Values
None	The ASCII text File Reader has no configurable properties other than Name and Description.

Table 6-2: ASCII Text File Reader Properties

Binary data

The Binary data File Reader properties are:

Property	Control Type: Values
None	The Binary data Graphics File Reader has no configurable properties other than Name and Description.

Table 6-3: Binary Data File Reader Properties

DICOM Image

The DICOM Image File Reader properties are:

Property	Control Type: Values
None	The DICOM Image File Reader has no configurable properties other than Name and Description.

Table 6-4: DICOM Image File Reader Properties

ESRI Shapefile

The ESRI Shapefile File Reader properties are:

Property	Control Type: Values
Combine all shapes	Boolean: If True then combine all of the shapes within the file into a single visualization (ShapePolygon, ShapePolyline, or ShapePoint). The default is to create a separate visualization for each shape.
Name attribute	String List: If the shapefile has attributes associated with each shape, then the Shapefile reader will attempt to use one of these attributes for the Name of the newly-created data and visualizations. The droplist contains all of the available attributes, and allows you to choose a different attribute to be used for the visualization name. If “Combine all shapes” is True then this property is insensitive, and the filename will be used for the Name of the resulting data and visualization.

Table 6-5: ESRI Shapefile File Reader Properties

Graphics Interchange Format

The Graphics Interchange Format (GIF) File Reader properties are:

Property	Control Type: Values
Image index	Number: The index of the image within the GIF file that should be read into the image data object.

Table 6-6: GIF File Reader Properties

iTools State

The iTools State File Reader properties are:

Property	Control Type: Values
None	The iTools State File Reader has no configurable properties other than Name and Description.

Table 6-7: iTools State File Reader Properties

Joint Photographic Experts Group

The Joint Photographic Experts Group File Reader properties are:

Property	Control Type: Values
None	The Joint Photographic Experts Group File Reader has no configurable properties other than Name and Description.

Table 6-8: Joint Photographic Experts File Reader Properties

JPEG2000

The JPEG2000 File Reader properties are:

Property	Control Type: Values
Levels to discard	A droplist giving the number of highest resolution levels which will not appear in the result. Image dimensions are divided by 2 to the power of this number. For example, if the image in the object has dimensions of 1024 x 1026, and DISCARD_LEVELS is set to 3, the resulting image will have dimensions of 128 x 129, which is the ceiling of [1024, 1026] divided by 2^3 . The default is “None”, implying that the full resolution image will be returned.
Quality layers	A droplist giving the maximum number of quality layers which will be returned in the result. Each layer contains the information required to represent the image at a higher quality, given the information from all the previous layers. A value of “All”, the default, implies that all layers should be returned.

Table 6-9: JPEG2000 File Reader Properties

Macintosh PICT

The Macintosh PICT File Reader properties are:

Property	Control Type: Values
None	The Macintosh PICT File Reader has no configurable properties other than Name and Description.

Table 6-10: Macintosh PICT File Reader Properties

Portable Network Graphics

The Portable Network Graphics File Reader properties are:

Property	Control Type: Values
None	The Portable Network Graphics File Reader has no configurable properties other than Name and Description.

Table 6-11: Portable Network Graphics File Reader Properties

Tag Image File Format

The Tag Image File Format File Reader properties are:

Property	Control Type: Values
Image index	Number : Level at which to begin image index. Edit the number to change the value. Default = 0
Image Stacking	String List : Image stacking method. Select a method from the list. Choose between these values: • +X • -X • +Y • -Y • +Z • -Z Default = Read Single Image

Table 6-12: Tag Image File Format File Reader Properties

Windows Bitmap

The Windows Bitmap File Reader properties are:

Property	Control Type: Values
None	The Windows Bitmap File Reader has no configurable properties other than Name and Description.

Table 6-13: Windows Bitmap File Reader Properties

Windows Waveform Audio Stream

The Windows Waveform Audio Stream File Reader properties are:

Property	Control Type: Values
None	The Windows Waveform Audio Stream File Reader has no configurable properties other than Name and Description.

Table 6-14: Windows Waveform Audio Stream File Reader Properties

File Writers

Select this folder to edit file write preferences and properties. Available file writer types and their editable properties are shown in the following tables. For more information on writing data of various types, see [Chapter 2, “Importing and Exporting Data”](#).

ASCII text

The ASCII text File Writer properties are:

Property	Control Type: Values
Separator	Enter a value. Default = None
Use default format	Boolean: Use default format? Choose True or False . Default = True
Format string	Number: Enter a number to change the value. Default = G9 . 2

Table 6-15: ASCII Text File Writer Properties

Binary data

The Binary data File Writer properties are:

Property	Control Type: Values
Byte ordering	String List: Byte ordering type. Select from the list. Choose between these values: • Native • Little endian • Big endian Default = Native

Table 6-16: Binary Data File Writer Properties

Encapsulated Postscript

The Encapsulated Postscript File Writer properties are:

Property	Control Type: Values
Graphics format	Bitmap or Vector: Render graphics using bitmap or vector output Note - Only a Window or View can be exported to EPS.
Color model	RGB or CMYK
ISOLatin1	Boolean: Use ISOLatin1 encoding for fonts that support this encoding? (ISOLatin1 encoding allows access to many commonly-used foreign characters.) Choose True or False . Default = True

Table 6-17: Encapsulated Postscript File Writer Properties

Graphics Interchange Format

The Graphics Interchange Format (GIF) File Writer properties are:

Property	Control Type: Values
None	The Graphics Interchange Format File Writer has no configurable properties other than Name and Description.

Table 6-18: GIF File Writer Properties

iTools State

The iTools State File Writer properties are:

Property	Control Type: Values
None	The iTool State File Writer has no configurable properties other than Name and Description.

Table 6-19: iTools State File Writer Properties

Joint Photographic Experts Group

The Joint Photographic Experts Group File Writer properties are:

Property	Control Type: Values
Color	String List: Select a depth from the list. Choose between these values: • TrueColor • Grayscale Default = TrueColor
Quality	Number: Factor from 0 - 100 determining the level of quality. Move slider to change the level. Default = 75

Table 6-20: Joint Photographic Experts Group File Writer Properties

JPEG2000

The JPEG2000 File Writer properties are:

Property	Control Type: Values
Reversible	Boolean: Use reversible (lossless) compression.
Wavelet levels	Number: The number of wavelet decomposition levels, or stages, in the range of 0...15. Higher values take longer to store and read, but may give better compression. The default is 5.
Quality layers	Number: A positive integer specifying the number of quality layers. Each layer contains the information required to represent the image at a higher quality, given the information from all the previous layers. A larger number of layers takes longer to encode and produces a larger file, but provides more flexibility when decoding.

Table 6-21: JPEG2000 File Writer Properties

Macintosh PICT

The Macintosh PICT File Writer properties are:

Property	Control Type: Values
None	The Macintosh PICT File Writer has no configurable properties other than Name and Description.

Table 6-22: Macintosh PICT File Writer Properties

Portable Network Graphics

The Portable Network Graphics File Writer properties are:

Property	Control Type: Values
Bit depth	String List : Bit depth in bits. Select a depth from the list. Choose between these values: • Automatic • 8 bit • 24 bit Default = Automatic

Table 6-23: Portable Network Graphics File Writer Properties

Tag Image File Format

The Tag Image File Format File Writer properties are:

Property	Control Type: Values
Bit depth	String List: Bit depth in bits. Select a depth from the list. Choose between these values: • Automatic • 8 bit • 24 bit Default = Automatic
Compression	String List: Compression type. Select a type from the list. Choose between these values: • None • Packbits • JPEG Default = None

Table 6-24: Tag Image File Format File Writer Properties

Windows Bitmap

The Windows Bitmap File Writer properties are:

Property	Control Type: Values
Bit depth	String List: Bit depth in bits. Select a depth from the list. Choose between these values: • Automatic • 8 bit • 24 bit Default = Automatic

Table 6-25: Windows Bitmap File Writer Properties

Windows Enhanced Metafile

The Windows Enhanced Metafile File Writer properties are:

Property	Control Type: Values
Graphics format	Bitmap or Vector: Render graphics using bitmap or vector output Note - Only a Window or View can be exported to EMF.

Table 6-26: Windows Enhanced Metafile File Writer Properties



Chapter 7

Common Operations

This chapter describes the following common tasks that can be performed with all of the IDL Intelligent Tools:

Introduction	112	Morphing	127
File Operations	113	Additional Operations	128
Rotation	115	Rendering Translucent Objects	132
Transformations	119	Operations on Regions of Interest	133
Filtering	122	Printing	134

Introduction

The Standard IDL iTools supplied in the IDL distribution (iPlot, iSurface, iImage, iContour, iVolume, iMap, and iVector) each have many common operations. This chapter discusses the use of these common operations.

Note

This chapter describes only the Standard IDL iTools, those iTools supplied in the IDL distribution. Other iTools written by users and third-party developers share a common interface with the ITT Visual Information Solutions iTools because the iTools framework is used to create all iTools. However, the specific functionality of such iTools may be different from the functionality of the iTools described here.

File Operations

File operations are provided in the iTools to allow you to open files, save files, import variables and files, export variables, or export the contents of the iTool window as an image file.

Opening Files

Data files, text files, and previously saved iTools State (*.isv) files can be opened with **File** → **Open**. For more information on opening files, see [“Using File Open”](#) on page 32.

Importing Variables and Files

IDL variables and files can be imported into the current iTool with **File** → **Import**. The IDL Data Import Wizard offers you the choice of importing a variable or a file, and then asks you to identify the location of the data source and the type of visualization to be created with the data.

Import a Variable

The Data Import Wizard can import an IDL variable created at the IDL command line or exported from an iTool session into the current iTool. For more information on importing variables, see [“Importing Data from the IDL Session”](#) on page 41.

Import a File

The Data Import Wizard can import text files, data files, or image files into the current iTool. For more information on importing files, see [“Importing ASCII Data”](#) on page 34, [“Importing Binary Data”](#) on page 35, or [“Importing Image Data”](#) on page 34.

Saving Files

The current state of the iTool can be saved as an iTools State (*.isv) file. Whenever you close an iTool window, you will be prompted to save the current state as an *.isv file so that you can return to the current state of the data later when you open the *.isv file. Other IDL users running IDL 7.0 for Windows, UNIX or Mac OS X can open *.isv files.

Save

File → **Save** saves the state of the current iTool to a file. If the file has already been saved, it will be saved under the same filename it was previously saved under. If the state has not been previously saved and has no filename, enter a filename. The saved file can be opened by IDL on either the Windows or the UNIX platform.

Save As...

File → **Save As** also saves the state of the current iTool to a file, but it prompts you to enter a filename even if the file has been saved previously. Use **Save As** to save an existing iTools State file under a different name.

Exporting Variables and Files

Data items created within the current iTool can be exported as IDL Variables, and the contents of the current iTool window can be exported as an image file. Select **File** → **Export**, and follow the instructions in the IDL Data Export Wizard.

Export as a Variable

Data from the currently selected object can be exported as a variable from the IDL Data Export Wizard to the main IDL program.

For more information, see [“Exporting Data to the IDL Session”](#) on page 48.

Export as a File

The contents of the current window can be exported from the IDL Data Export Wizard as an image file.

For more information, see [“Exporting Data to a File”](#) on page 45.

Exiting the iTool

Clicking the Close button  on the iTool window will close the selected window.

File → **Exit** also closes the iTool window. You will be prompted to save any changes to the current state (see **File** → **Save** above for details). All visualizations and views within the window are removed from memory.

Rotation

The iTools provide a number of ways to rotate graphical objects. Objects that are 3-D can be rotated freely or along an axis using the mouse. In addition, both 2-D and 3-D objects can be rotated left or right in 90-degree increments, or they can be rotated by a specified number of degrees. These tools rotate the entire data space.

Note

Special consideration should be given when attempting to rotate a graphic image object within iImage. See for more details.

Mouse Rotation

To rotate a 3-D object with the mouse:

1. Select the object in the iTool window.
2. Click Rotate  on the toolbar to enter Rotate mode. The rotation sphere, consisting of circular x-, y-, and z-dimension axes, is displayed around the object, as illustrated in [Figure 7-1](#) and [Figure 7-2](#):

3. 3-D objects can be constrained to rotate only along one of the three displayed axes, or they can be rotated freely.
 - To rotate an object along an axis, position the mouse pointer on the axis. The constrained rotation pointer  is displayed. Drag in the desired direction to rotate the object along the selected axis.




Figure 7-1: Rotating a 3-D Object

- To rotate an object freely, position the mouse pointer anywhere on the object. The free rotation pointer  is displayed. Drag in any direction to rotate the object in that direction.




Figure 7-2: Free Rotation

4. Click  or select **Edit** → **Undo** to undo the rotation, or click  to leave rotate mode.

Rotate Left and Rotate Right

To rotate a selected 2-D or 3-D object 90° left or right, select **Operations** → **Rotate** → **Rotate Left** or **Operations** → **Rotate** → **Rotate Right**.

Note

For three-dimensional objects, the rotation is about the Z axis.

Rotate by Specified Angle

To rotate a selected 2-D or 3-D object a specific number of degrees, select **Operations** → **Rotate** → **Rotate by Angle**, specify the number of degrees in the Rotate Angle dialog, and click **OK**.




Figure 7-3: Rotate Angle Dialog

Note

For two-dimensional objects (such as plots, images, annotations, contours, and so on) the angle is absolute. The rotation angle is remembered and displayed in the **Rotate By Angle** dialog. So for example, you can set the angle to zero degrees to make your visualization angle rotate back to zero. For 3D visualizations, Rotate by Angle is relative and does not remember the current rotation angle.

Transformations

Three types of transforms are common to all iTools: Resample, Rotate Data, and Scale Data.

Resample

The **Resample** transform resamples the selected data. Resampling operation properties include factors for each dimension of the data, as well as the interpolation method to be used.




Figure 7-4: Resample Dialog

For example, if the X, Y, or Z value of a visualization needs to be different from the original data value, you can resample the data to adjust the X, Y, or Z value by the specified resample factor. Or, if the default interpolation method produces undesirable artifacts in the visualization of the data, you can resample the data with a different interpolation method.

To resample data:

1. Select one or more objects in the iTool window for resampling.
2. Select **Operation** → **Transform** → **Resample**.
3. Use the property sheet that appears to specify the resampling factor in each dimension, along with the interpolation method. See [“Resample Properties”](#) on page 406 for details.
4. Click **OK** to resample the data, or **Cancel** to abort the operation.

Note

For more information on the iTool's Operations Browser, see [Appendix C, “Operations Properties”](#).

Rotate Data

The Rotate Data transform makes it possible to rotate the data within the visualization by a specified number of degrees without affecting the rest of the data space (graphical objects and axes).

To rotate data:

1. Select the visualization.
2. Select **Operation** → **Transform** → **Rotate Data**. The Rotate Data dialog is displayed.




Figure 7-5: Rotate Data Dialog

3. Specify the number of degrees to rotate by clicking the up-down control, or by editing the text.
4. Click OK.

Scale Data

The Scale Data transform makes it possible to scale the data within an object by a specified scale factor.

To scale data:

1. Select one or more objects which contain the data to be scaled.
2. Select **Operations** → **Scale Data**. The Scale Data dialog appears.




Figure 7-6: Scale Data Dialog

3. Change the scale factor, if necessary, by editing the number in the Scale Factor field, and click **OK** to scale the selected object(s) or **Cancel** to close the Scale Data dialog without scaling the object(s).

Filtering

Four types of filters are common to all iTools: Smooth filtering, Median Filtering, Convolution, and Unsharp Masking.

Smooth Filter

To remove unwanted noise from data, apply the Smooth filter to the data.

To apply the Smooth filter:

1. Select the data that you want to smooth.
2. Select **Operations** → **Filter** → **Smooth**.
3. The smooth filter editor appears (as shown in the following figure) and desired settings can be edited.




Figure 7-7: The Smooth Filter Editor

4. Click **OK** and the filter is applied.

Median Filter

Median smoothing replaces each point with the *median* (a value in an ordered set of values with an equal number of values above and below it) of the one- or two-dimensional neighborhood of a given width. It is similar to smoothing with a boxcar or average filter, but does not blur edges larger than the neighborhood. Median filtering is effective in removing “salt and pepper” noise (isolated high or low values).

To apply the Median filter:

1. Select the data that you want to smooth.
2. Select **Operations** → **Filter** → **Median**.
3. The median filter editor appears (as shown in the following figure) and desired settings can be edited.



Figure 7-8: The Median Filter Editor

4. Click **OK** and the filter is applied.

Convolution Filter

To convolve data:

1. Select the data to be convolved.
2. Select **Operations** → **Filter** → **Convolution**. The **Convolution Kernel Editor** dialog is displayed.




Figure 7-9: Convolution Kernel Editor

The dialog displays an image preview for two-dimensional data only. The **View 1D slice** option is always disabled when you use the editor with existing data. You have access to the option when you open the editor through the Operations Browser (see “[Convolution Properties](#)” on page 398).

3. Change **Convolution Kernel Editor** settings as necessary by modifying any of the following items in the property sheet:
 - **Filter** — select a filter type from the list. The default filter is **Tent**.
 - **Number of Columns (Rows)** — edit if necessary.
 - **Center** — position is centered by default. Select **False** to turn centering off.
 - **Auto normalize** — scaling is automatic by default. To use a different scale factor, select **False** and enter a value in the **Scale factor** property field. You can also set **Bias offset** to add an offset that will be added to the results after **Scale factor**.
 - **Edge values** — edges wrap around by default. To choose a different edge format, select **Zero result**, **Repeat last value**, or **Zero pad** from the list.
 - **Use invalid value** — filtering missing data is off by default. To filter missing data using an invalid value, select **True** and enter the value in the **Invalid value** property field. You can also set **Replacement value** to give IDL a value that will replace missing results.
4. Click **OK** to apply the filter with the current settings and close the Convolution Kernel Editor window, or click **Cancel** to close the window without applying the filter.

Unsharp Mask Filter

An unsharp-mask filter can be applied to any two-dimensional array or a TrueColor image. The unsharp mask enhances the contrast between neighboring pixels in an image, and is widely used for astronomical images and for digital photographs.

To apply the Unsharp Mask filter:

1. Select the data that you want to unsharp mask.
2. Select **Operations** → **Filter** → **Unsharp Mask**.
3. The unsharp mask filter editor appears (as shown in the following figure) and desired settings can be edited.




Figure 7-10: The Unsharp Mask Filter Editor

4. Click **OK** and the filter is applied.

Morphing

Mathematical morphology is a method of processing digital images on the basis of shape. Morphing is available when working with images, surfaces, and contours. Six morphing options are available for use in iTools: dilate, erode, morph open, morph close, morph gradient, and morph tophat.

Morphing Option	Description
Dilate	Dilate is commonly known as “fill”, “expand”, or “grow.” It can be used to fill “holes” of a size equal to or smaller than the structuring element.
Erode	Erode does to the background what dilation does to the foreground. Given an image and a structuring element, erode can be used to remove islands smaller than the structuring element.
Morph open	Morph open is simply an erosion operation followed by a dilation operation. Applying morph open more than once produces no further effect.
Morph close	Morph close is simply a dilation operation followed by an erosion operation. Applying morph close more than once produces no further effect.
Morph gradient	Morph gradient is the subtraction of an eroded version of the original image from a dilated version of the original image.
Morph tophat	Morph tophat is implemented by first applying the opening operator to the original image, then subtracting the result from the original image. Applying tophat shows the bright peaks within the image.

Table 7-1: Morph Menu Options

To apply a morphology option:

1. Select the object to be morphed.
2. Select **Operations** → **Morph** → <option>.

Additional Operations

The Histogram, Statistics, and Console tools display additional information about data displayed in the iTool windows, and about operations performed with the iTools.

Plotting a Histogram

Histogram displays a histogram plot of the data currently selected in the iTool window. The Histogram plot appears in a separate iPlot window.




Figure 7-11: Histogram Plot

To display a histogram plot:

1. Select an object or group of objects in the iTool window.
2. Select **Operations** → **Histogram**.

Displaying Statistics

The Statistics dialog displays all available statistical information pertaining to the object or objects currently selected in the iTool window.

To display the Statistics dialog:

1. Select an object or a group of objects in the iTools window.
2. Select **Operations** → **Statistics**. The Statistics window is displayed.




Figure 7-12: The iTools Statistics Window

The information displayed in the Statistics window varies depending upon the type of objects selected.

- For scalars, the name of the variable and its value are displayed in the Statistics window.
- For arrays, the following information is displayed:
 - Name
 - Maximum and location
 - Dimensions
 - Standard deviation
 - Mean
 - Variance
 - Absolute deviation
 - Total
 - Skewness
 - Minimum & location
 - Kurtosis - 3

The information in the Statistics window can be edited (by selecting **Edit**), printed, or saved as a file.

- On Windows platforms, the standard Windows editing context menu containing Cut, Copy, Paste and Delete commands can be displayed by right-clicking anywhere in the Statistics window.
- On UNIX platforms, use the left or right mouse buttons to cut, copy or paste.

To save the text as an ASCII file:

1. Select **File** → **Save As**.
2. Enter a filename. If the filename already exists, you will be asked if you want to replace the file.
3. Select **Cancel** to return to the Statistics window without saving the file.

To print the text, select **File** → **Print**. The standard Windows or Motif printer dialog is displayed.

To close the Statistics window, select **File** → **Close**.

Resetting Dataspace Ranges

You can reset the ranges of your data space to accommodate all your contained visualizations. When you reset your ranges, the following properties of the data space are reset to a value of True:

- Automatic X range updates
- Automatic Y range updates
- Automatic Z range updates

To reset the ranges of your data space, select **Window → Reset Dataspace Range**.

Rendering Translucent Objects

Within iTools, you can set the transparency of an object to make it appear totally opaque, transparent, or translucent. Isosurface objects are just such a case. Text objects can also be made partially transparent so that you can see through the labels on a complex plot and still see both the labels and the data. In the majority of scenarios where you will utilize opaque data objects and translucent text labeling, this translucent rendering works very well.

It is important to know, however, that translucent rendering does not always work well in more complex situations. This is because translucent objects must be strictly rendered from the back (far from the viewer) towards the front (closer to the viewer). IDL accomplishes translucent rendering by blending the pixels already drawn on the device with the pixels that are drawn to represent a translucent object. Therefore, it is important that the objects that are positioned behind the translucent object be rendered before the translucent object. If the ordering is not correct, then you will not be able to see the objects behind the translucent object.

For most cases in iTools, ordering is not a problem. If you encounter it as a problem, the **Bring to Front** (and related) operation can help you improve the appearance of your translucent objects. In some cases, however, the ordering is not easily accomplished. For example, a complex isosurface rendered as a translucent object does not always appear correct from all angles.

An isosurface is composed of a large number of triangles stored in an IDLgrPolygon object. The triangles are always drawn in the same order, the order in which they are stored in the object. Thus, as the viewing angle changes, the apparent back-to-front ordering of the triangles also changes. In some cases, the triangles closest to the viewer draw first and end up blocking the view of other triangles drawn later and behind them that should be visible through the translucent triangles drawn first.

For all these reasons, transparency should be used with care in dealing with objects like a complex isosurface. The rendering of these objects ultimately may not appear correct.

Note

For more detailed information on alpha channel support in IDL Object Graphics, see [“Controlling Object Transparency”](#) (Chapter 2, *Object Programming*).

Operations on Regions of Interest

A *region of interest* (or ROI) is an area that contains data you wish to identify. An ROI can be drawn anywhere within your image and can be selected from rectangular, elliptical, polygonal, and freehand region of interest buttons on the iImage Image Panel. You can also apply operations to image data contained within an ROI area.

Some operations applied to ROIs affect the ROI data while others affect the ROI vertices.

Operations Modifying ROI Data

If the operation acts on the pixel values of the underlying data, the pixels that are contained within the ROI are changed as a result of the operation. Pixel values outside of the ROI area remain unchanged but pixel values within the ROI are set to correspond with the pixel result of the chosen operation.

Examples of operations acting upon the ROI data are:

- Filter operations including Convolution, Median, Smooth, Roberts, and Sobel
- Morphological operations
- Transform operations including scaling and inverting data

Operations Modifying ROI Vertices

If the operation acts on the vertices of the ROI itself, the vertices are changed as a result of the operation. If the entire image is selected for an operation, the ROI will follow the behavior of the entire image as the operation acts upon it. If only the ROI is selected, then only the ROI will respond to the operation.

Examples of operations acting upon the ROI vertices are:

- Rotate right, left, or by a specified angle
- Flip horizontal or vertical
- Region grow

Printing

File → **Print** sends the current view of the contents of the graphics window to the specified printer via the standard Windows or Motif printer dialog. If the contents have been modified in the current view, they will appear modified in the printer output.

To print the contents of the graphics window:

1. Select **File** → **Print**. The standard Windows or Motif printer dialog appears.
2. Select the desired printer and printer properties from the printer dialog.
3. Click **Print**. The current view of the contents of the graphics window is sent to the chosen printer, with the chosen options.

Print Preview

The **Print Preview** dialog in iTools allows you to view and manipulate your iTool window content before sending it to the printer.

To open the **Print Preview** dialog, select **File** → **Print Preview...**

You can reposition your content in the Print Preview window by clicking it and dragging it to a new location. If you move your content in such a way that part of it is no longer visible in the **Print Preview** dialog, this same part will not be shown when printed.

Note

If your **Print Preview** dialog shows the red border, it will not appear on paper when printed.

You can resize your content by clicking and dragging the small black rectangle at the upper right corner of the window area. The aspect ratio of the content cannot be changed. If **Center** is unchecked then the content will be resized while keeping the location of the lower left corner static. If **Center** is checked then resizing will take place while keeping the content centered.

The **Print Preview** dialog and its functions are shown here:





Figure 7-13: The **Print Preview** Dialog

Component	Function
X Margin	Sets the left margin to your desired value. Values can be manually entered.
Y Margin	Sets the bottom margin to your desired value. Values can be manually entered.
Width	Select your desired printout width. Values can be manually entered. Only positive values are accepted. The aspect ratio of the content is kept constant so a change in width will also change the height.
Height	Select your desired printout height. Values can be manually entered. Only positive values are accepted. The aspect ratio of the content is kept constant so a change in height will also change the width.
Units	Set width and height units in inches or centimeters . Default is inches .
Reset	Resets all settings to the original value when the Print Preview dialog was first opened. The margins, units, center, and border settings will be reset to defaults and the size is reset based on the size of the tool window.
Help	This invokes the IDL help for print and print preview procedures.
Orientation	Select Portrait or Landscape . Changing the orientation will reset the X and Y margins and the width and height, unless the Center check box is checked, in which case the width and height will be reset but the image will remain centered. Default is Portrait .
Center	Click to center your content on the page. When center is checked the X and Y margin text boxes are no longer available and the ability to drag the image with the mouse is removed. Default is off.

Table 7-2: Print Preview Functions

Component	Function
Border	Click to show or hide the content border as a red outline. The border does not print and is included only to indicate the boundary of the contents. The border setting is not saved. Default is on.
Setup	Select to edit printer information. If the Print button is pressed while in the setup dialog, the contents of the Print Preview dialog will be printed and the dialog will be dismissed.
Print	Prints the contents of the Print Preview dialog to the currently selected printer and closes the dialog.
Close	Closes the Print Preview dialog and saves the current settings without printing.

Table 7-2: Print Preview Functions



Chapter 8

Working with Macros

This chapter describes how to use the iTool macros.

Introduction	140	Using the Macro Editor	153
What Are Macros?	141	Understanding Items in the Macro Editor	164
Recording Macros	143	Making Selection and Tool Changes	179
Running Macros	146	Importing and Exporting Macros	186

Introduction

The macros in IDL iTools provide a shortcut mechanism that lets you quickly and automatically repeat a sequence of operations. You can record a series of actions in one iTool or several iTools, save the series as a macro, and then apply it to a new set of data to save you from having to repeat the actions manually.

This chapter discusses the following areas:

- More information about macros (see [“What Are Macros?”](#) on page 141)
- Recording macros (see [“Recording Macros”](#) on page 143)
- Running macros (see [“Running Macros”](#) on page 146)
- Editing macros (see [“Using the Macro Editor”](#) on page 153)
- Making selection and tool changes within a macro (see [“Making Selection and Tool Changes”](#) on page 179)
- Importing and exporting macros (see [“Importing and Exporting Macros”](#) on page 186)

What Are Macros?

In the context of the iTools, a *macro* is a collection of operations and property values that can be applied to an existing visualization or visualizations. There are two kinds of macros, depending on what you have selected when you start recording. For more information, see [“Macro Type Based on Recording Selection”](#) on page 179.

Macros are not linked to the objects or visualizations to which they are applied. When you run a macro, the operations or property settings apply to the objects currently selected. (The macro system does include functionality to change selections and tools during the execution of a macro. For more information, see [“Making Selection and Tool Changes”](#) on page 179.) This means that property settings can be applied to multiple visualization types, unlike property settings in styles.

Note

Property settings in macros apply to the selection, but are not tied to visualization type, whereas in styles they are tied to visualization type and might or might not apply to selection.

The following figure shows part of the display of the Macro Editor, covered in detail in [“Using the Macro Editor”](#) on page 153:




Figure 8-1: A Macro in the iTools Macro Editor

This figure shows an example macro called New Macro, composed of several operations and property settings. Operations in this macro change the selection and

apply the smooth operation. Property settings change the color and minor ticks properties.

Macro information is stored in one or more macro files located on your system. Macros are stored in IDL SAVE files. Macros are stored in a subdirectory of the user's `.idl` directory. When you create a new macro within an iTool, it will automatically be saved in the specified location.

Note

Macro information is never stored along with an iTool.

Recording Macros

You can create macros in two ways:

- Using the recording functionality in the iTools **Operations** → **Macros** menu, described in this section
- Using the Macro Editor, described in [“Using the Macro Editor”](#) on page 153

To record a macro:

1. Start an iTool.
2. Select **Operations** → **Macros** → **Start Recording**.
3. If the **Start Recording** dialog appears (as it does if the **Show dialog** property is True), select whether to record manipulator steps and press **OK**, which puts the iTools system into recording mode.



Figure 8-2: The Start Recording Dialog

Note

For more information on recording manipulator steps, see [“Capturing Intermediate Manipulations”](#) on page 144.

4. Select operations or set properties as desired to create the macro.
5. Select **Operations** → **Macros** → **Stop Recording** to complete the recording.

Putting the iTools system into recording mode creates a new macro folder in the macro registry, using a unique name based on ‘New Macro’ (as shown in the macro tree; see [“The Macro Tree”](#) on page 156). If the New Macro folder already exists, then the new name is New Macro (1) and so on until the system finds a uniquely numbered name. You can change the macro’s name when macro recording finishes.

At the end of recording, IDL saves the completed macro, and the Macro Editor opens. Note that using the **Stop Recording** menu command is the only way to stop recording without exiting the iTools system. Changing tools or closing the tool does not stop recording, and a recording started in one iTool will continue to other iTools. You can select the **Stop Recording** command in any active iTool.

Note

What you select in the iTools system before starting recording dictates what happens when you run the completed macro. For more information, see [“Macro Type Based on Recording Selection”](#) on page 179.

Capturing Intermediate Manipulations

A manipulation such as Translate typically consists of a series of transformations based on the screen position of the mouse. They start with a mouse-down operation and end with a mouse-up operation, but each mouse motion while the mouse button is down generates a transformation. Typically, when a manipulation such as Translate or Rotate is recorded, a single macro item is created that contains the overall translation from mouse-down to mouse-up. This applies to the history item that is created whether recording or not. When this macro item is processed during macro playback, the complete transformation is applied, but the individual transformations based on the individual mouse motions are not available.

A different mode of recording has been added which allows a recording of a manipulation to save the individual steps based on each mouse movement. This is useful if the purpose of the macro is to demonstrate the transformation such as a smooth 3D rotation of a surface. This new mode records each step of the manipulation while the mouse is down, based on the original motion events from the operating system.

A new property, **Record manipulator steps**, has been added to the **Start Recording** operation. This Boolean property lets you specify whether to record the individual

movements of a manipulation. The default value is False, meaning that the macro recording captures only the overall transformation rather than individual steps.

This property applies to the following manipulators when they are used within a recording:

- Rotate
- Translate (includes Image Plane translation)
- Scale
- View Pan
- View Zoom

While they are distinctly different properties, the value of **Record manipulator steps** is used to set the default value for the **Display intermediate steps** property of the macro itself. If **Record manipulator steps** is set to True when starting a recording, it is most likely that the user wants to see the intermediate steps during playback, so **Display intermediate steps** is set to True to provide that display.

Note that this property applies only to the macro item generated during recording. The history item generated for a transformation always consists of the single overall transformation, regardless of the setting of **Record manipulator steps** if recording as well as if not recording.

There are a number of other manipulators that are not affected by the **Record manipulator steps** property. For these manipulators, their primary purpose is to specify an overall movement with the mouse to specify how a succeeding operation will be applied. Therefore, an overall movement is always used to create a single macro item. These other manipulators are the following:

- Crop Box
- Range Box
- Range Pan
- Range Zoom
- Line Profile
- Surface Contour

Running Macros

When you run a macro, its operations apply to the item or items selected in the active iTool.

Note

For more information on a macro's application to the current selection, see [“Macro Type Based on Recording Selection”](#) on page 179.

To run a macro, do one of the following:

- From an iTool window, select **Operations** → **Macros** → **Run Macro**
- From the Macro Editor, select the macro to run and then select **Run** → **Run Macro**
- At the IDL command line, use the `MACRO_NAMES` keyword with an iTool command

Macro items are processed sequentially, each item either applying an operation or applying property values. Macros can contain operations that change the selection so that subsequent operations or property settings apply to different visualization objects in one or more iTools. For more information, see [“Making Selection and Tool Changes”](#) on page 179.

While the macro is running, you have access to the **Macro Controls** dialog, which lets you pause, step, and stop the macro. You can also hide or show intermediate steps in the macro, set the step delay, and hide or show the macro items. For more information, see [“Using the Macro Controls Dialog”](#) on page 149.

After running a macro, you can use the **Undo/Redo** operation, which treats the actions performed by a macro as a single event. This means that if you run a macro and then select **Undo**, all of the operations and properties changed by the macro revert to their pre-macro values.

Running from the Operations Menu

You can run a macro by selecting **Operations** → **Macros** → **Run Macros** from any open iTool. This selection opens the **Run Macro** dialog, as shown in [Figure 8-3](#).




Figure 8-3: The Run Macro Dialog

This dialog lets you select the macro to run. The macro names are obtained from all saved macros. Macros that have been created in the macro editor, but not saved are not available. By default, the first item in the list is selected, and the description of that first macro appears in the **Macro Description** field. After you select a macro name from the list, the **Macro Description** field is updated with the description of the selected macro.

The **Display intermediate steps** option is set based on the value of the macro property of the same name. Set it to display each step of the macro as it runs, or clear it to prevent any updates of the display until the macro is complete. The **Step delay** field displays the number of seconds IDL delays between each step of the macro. You can change the delay by entering a floating-point value in the field. The minimum delay is 0.0 seconds; the maximum delay is 60.0 seconds. IDL truncates the delay value to fall within that range after you click **OK**.

The values of both of these properties are retrieved from the specified macro when you select it in the list. Changes made to these properties with this dialog affect the

succeeding invocation of the macro specified, but are not applied to the macro itself. This lets the macro properties maintain default values while the settings of the dialog can be modified for a single invocation. To make a permanent change to these properties, edit them in the Macro Editor and save your changes. For more information on these properties, see [“The Macro Property Sheet”](#) on page 156.

To run a macro from this dialog, either:

- Double-click its name in the list
- Select its name in the list and click **OK**

Running from the Macro Editor

You can run macros from within the Macro Editor by doing the following:

1. In the macro-tree panel (top left), select the macro to run.
2. Select **Run** → **Run Macro**.

The macro runs on the selected visualization or visualizations in the active iTool.

For more information, see [“Using the Macro Editor”](#) on page 153.

Running from the Command Line

You can also apply macros in a non-interactive situation by running them from the IDL command line.

The iTools routines (such as `IPLOT`) have a `MACRO_NAMES` keyword that you can set when calling them. For example, you can enter the following at the command line, if you have a macro named ‘plotmacro’ already defined:

```
IPLOT, RANDOMU(1, 20), MACRO_NAMES='plotmacro'
```

This command creates a simple two-dimensional plot of 20 randomly generated data points and then applies the ‘plotmacro’ macro to it.

The keyword can take either a single string, as in the example above, or an array of strings. In the latter case, the macro names are retrieved and run sequentially at the conclusion of the iTool’s actions. This action follows the creation of the iTool and, if applicable, any visualization created by the command.

Note

For more information on the `MACRO_NAMES` keyword, see the iTools routine commands in the *IDL Reference Guide*.

Using the Macro Controls Dialog

The **Macro Controls** dialog is a floating dialog that, when launched, appears in the bottom-right corner of the iTool window containing the running macro. You cannot resize or close it, but you can move it to a different location. It appears initially in its small or collapsed form, as shown in [Figure 8-4](#).



Figure 8-4: The Macro Controls Dialog (Collapsed) While Running

The **Macro Controls** dialog lets you:

- Pause and continue the currently running macro
- Step through the macro one item at a time
- Stop the macro
- Hide or show the macro's intermediate steps
- Set the step delay
- Hide or show the macro items

These actions are described in more detail below.

Continue / Pause

If the macro is running, the button label is the pause symbol. Click this button to pause the macro. [Figure 8-4](#) shows the **Macro Controls** dialog while running.

If the macro is paused, the button label is the continue symbol. Click this button to resume macro execution. [Figure 8-5](#) shows the **Macro Controls** dialog while paused.



Figure 8-5: The Macro Controls Dialog (Collapsed) While Paused

Note

Under Microsoft Windows systems, you can invoke either action by pressing **F5**.

Step

When a macro is paused, you can click the button with the step symbol to execute the next macro item. When a macro is running, this button is desensitized.

Note

Under Microsoft Windows systems, you can invoke this action by pressing the right arrow key.

The macro step delay (if nonzero) is not applied when you click the **Step** button. In addition, the discrete delay from a Delay or Step Delay Change operation is not applied. For more information, see [“Delay Operation Item”](#) on page 175 or [“Step Delay Change Operation Item”](#) on page 176.

Stop

You can use the button with the stop symbol to stop execution of the macro. The remaining macro items are skipped, and the **Macro Controls** dialog is dismissed. You can use the **Stop** button while the macro is paused or running.

Hide Steps / Show Steps

If the intermediate steps of the macro are being displayed, the button label is the closed-eye image, for **Hide Steps**. Click this button to turn off the display of intermediate steps.

If the intermediate steps of the macro are not being displayed, the button label is the open-eye image, for **Show Steps**. Click this button to turn on the display of intermediate steps.

Using these controls lets you interactively toggle whether the display of the iTool window is updated after the execution of each macro item. This ability has several useful applications. If the list of macro items is displayed (see [“Show Macro Items / Hide Macro Items”](#) on page 151), you can monitor what the macro is doing and interactively turn on the display of intermediate steps for a particular part of the macro. You can also interactively test a macro playback when planning to insert Step Display Change operations into the macro. Inserting these operations might be useful when a macro recording contains many intermediate steps, but the author of the macro wants to show only a subset of the steps. For more information on this operation, see [“Step Display Change Operation Item”](#) on page 177.

Set Step Delay

You can use the button with the hourglass symbol to set the step delay. This action pops up a floating dialog, shown in [Figure 8-6](#), that allows setting the step delay in seconds. The **Set Step Delay** button is active while the macro is paused and while it is running. You cannot resize the **Step Delay** window, but you can move and close it.



Figure 8-6: The Step Delay Window of the Macro Controls Dialog

You can set the step delay to a floating-point value by either:

- Using the **Step Delay** window's slider
- Typing a value in the window's field

The minimum value is 0.0 seconds, the maximum value is 60.0 seconds, and the default step is 0.01 seconds. You can set the step delay value while the macro is paused or running.

Modifying the step delay value does not set the macro's step delay property. Setting the step delay through the **Macro Controls** dialog applies a temporary override value that remains in effect until the end of the macro execution, until the value is modified again with the dialog, or until a Step Delay Change operation is encountered in the macro items (see [“Step Delay Change Operation Item”](#) on page 176).

Show Macro Items / Hide Macro Items

If the **Macro Controls** dialog is collapsed, you can use the button with the down arrow (shown in [Figure 8-5](#)) to expand the dialog and show the macro items. During macro execution, the current macro item is selected in the tree view. When the macro is paused, the tree view shows the macro item to be executed next when you click either **Step** or **Continue**.




Figure 8-7: The Macro Controls Dialog (Expanded)

If the **Macro Controls** dialog is expanded, as shown in [Figure 8-7](#), you can use the button with the up arrow to collapse the dialog so that macro items are not displayed.

Using the Macro Editor

You can use the Macro Editor to modify existing macros and create new macros. The Macro Editor is launched automatically after you record a macro interactively. You can also launch the Macro Editor at any time by selecting **Operations** → **Macros** → **Macro Editor** from any iTool.

The Macro Editor is a system-wide dialog, shared by all current iTools. Closing all current iTools does not close the Macro Editor.




Figure 8-8: The Macro Editor

Figure 8-8 shows the Macro Editor with the History folder expanded to show the history items that were generated while the iImage tool was open (that is, all iImage operations, whether recorded in a macro or not). The Macros folder in the upper-right panel shows a macro with its SetProperty item selected.

Understanding the Macro Editor

The Macro Editor consists of four panels and two sets of add/remove buttons. The four panels consist of the two macro panels on the top and the two source panels on the bottom. You use the add/remove buttons to move operations and settings from the source panels to the macro panels.

The Menu Bar

The following menus appear on the Macro Editor menu bar:

- File
- Edit
- Run
- Help

You can use the **Edit** and **Run** operations in a right-click context menu on items in the macro and source trees.

The **File** menu, shown in [Table 8-1](#), contains tools for creating, importing, exporting, and saving macros.

Menu Selection	Function
New	Creates a new macro in the macro tree, with a name based on ‘New Macro.’ If New Macro already exists, then the new name is New Macro (1) and so on until the system finds a uniquely numbered name.
Import...	Imports a macro from an external file. See “Importing and Exporting Macros” on page 186 for details.
Export...	Exports the selected macro to an external file. See “Importing and Exporting Macros” on page 186 for details.
Save	Saves all macros to external IDL SAVE files with names based on the macro names.
Close	Closes the Macro Editor, prompting you to save any unsaved macro changes.

Table 8-1: The File Menu

The **Edit** menu, shown in [Table 8-2](#), contains tools for editing, deleting, duplicating, and moving items within the macro and source trees.

Menu Selection	Function
Cut	Copies the selected item to an internal clipboard and removes the item from the tree.
Copy	Copies the selected item to an internal clipboard.
Paste	Pastes the contents of the internal clipboard into the tree.
Delete	Deletes the selected item without making a copy. If the selected item is a SetProperty item and the last selection was in the macro property sheet, this action deletes selected properties from the SetProperty item. If the last selection was in the macro tree, the whole SetProperty item is deleted.
Duplicate	Duplicates the selected item.
Move Item Up	Moves the selected item up one position in the tree.
Move Item Down	Moves the selected item down one position in the tree.

Table 8-2: The Edit Menu

The **Run** menu contains only one operation: Run Macro, which runs the selected macro. See [“Running from the Macro Editor”](#) on page 148 for details.

The **Help** menu opens the online help for the Macro Editor.

The Macro Tree

The macro tree (top left) contains folders for existing macros, as shown in [Figure 8-9](#). Macros are indicated by the gears folder icon. Macro items are indicated by their own object icons or by the SetProperty icon.




Figure 8-9: The Macro Editor's Macro Tree

Clicking on an item in the tree selects the item and displays its property sheet to the right of the tree panel. Right-clicking within the tree brings up the context menu of available actions (see [“The Menu Bar”](#) on page 154). If you right-click on a tree item, then that item is selected.

For more information on these items, see [“Macro Items”](#) on page 164.

The Macro Property Sheet

The macro property sheet (top right) lets you set properties of macro folders and items.

To see a macro's properties, click on its folder in the macro tree. The macro's properties appear in the macro property sheet, as shown in [Figure 8-10](#). To change any of the properties, click on it in the sheet and make the modification you want.




Figure 8-10: The Macro Editor's Macro Property Sheet: Macro Properties

Macros have several properties, described in [Table 8-3](#).

Property	Value
Name	Used to select the desired macro from the Run Macro dialog (for more information, see “Running from the Operations Menu” on page 147). Also serves as the basis for the filename of a saved macro.
Description	Used to describe the behavior or purpose of the macro. Its value appears in the Run Macro dialog's Description field when you select a macro from the list.

Table 8-3: Macro Property Values


Property	Value
Display intermediate steps	Typically set to False so that the display updates only on completion of the macro. Set this property to True to display each step of the macro, which might be useful when using a macro to animate a series of actions.
Step delay (seconds)	Used to specify the time in seconds to delay between each step of the macro. The default value is 0.0. The minimum value is 0.0, and the maximum value is 60.0. Note - You can also add the Delay operation to a macro to create a single specific delay (see “ Delay Operation Item ” on page 175).

Table 8-3: Macro Property Values (Continued)

Note _____

If **Display intermediate steps** is set to False (the default value), updates to the display are suppressed while a macro is being run. Operations that typically update the display, such as the Volume Render operation, do not change the display if **Display intermediate steps** is set to False.

To see an individual macro item's properties, click on the item in the macro tree. The properties appear in the macro property sheet, as shown in [Figure 8-11](#). To change any of the properties, click on a property in the sheet and make the modification you want.



	Rotate
Name	Rotate
Description	Rotate
X Rotation	0
Y Rotation	0
Z Rotation	90

Figure 8-11: The Macro Editor's Macro Property Sheet: Macro Item

You can modify any properties of a macro item except for user-defined properties, which are not available for modification.

The Source Tree

The source tree (bottom left), as shown in [Figure 8-12](#), contains the following items that you can use for macro creation:

- History items, grouped by tool (see [“History Items”](#) on page 166)
- Visualizations (see [“Visualization Items”](#) on page 169)
- Annotations (see [“Annotation Items”](#) on page 170)
- Macro tool items (see [“Macro Tools Items”](#) on page 171)
- Tool menu items (see [“Tool Menus Items”](#) on page 178)





Figure 8-12: The Macro Editor's Source Tree

You can use these property settings and operations as a source for macro items. Selecting one of these items displays its properties in the source property sheet next to the tree panel. While the visualizations and annotations cannot be used directly in macros, you can use their properties as the source for macro property settings. The source tree also contains operations for the current tool, in the **Tool Menus** → **Operations** subfolder, which you can use as a source for macro operations.

Clicking on an item in the tree selects the item and displays its property sheet to the right of the tree panel. You cannot multi-select within the tree. Right-clicking within the tree brings up the context menu of available actions (see “[The Menu Bar](#)” on page 154). If you right-click on a tree item, then that item is selected.

The Source Property Sheet

The source property sheet (bottom right) displays the properties of items in the source tree to its left. As described above, properties can be used as source items for macros.



Line	
Name	Line
Description	Line Annotation
Show	True
Transparency	0
Color	(0,0,0)
Line style	
Thickness	1
Arrow style	-----
Arrowhead size	0.05

Figure 8-13: The Macro Editor's Source Property Sheet

Figure 8-13 shows the properties for the Line operation, found in the source tree's Annotations folder. You can multi-select properties in the sheet. Selected properties may be moved to a macro property setting item. Although all properties in the source property sheet are grayed out (desensitized), you can select them for creation of SetProperty macro items (for more information, see [“SetProperty Settings”](#) on page 165).

Note

User-defined properties are available only if they are part of a macro recording; they will apply like any other property during playback. You cannot otherwise use a user-defined property (moving, copying, modifying, etc.) in the macros system.

The Add and Remove Buttons

There are two sets of Add and Remove buttons, one for the source and macro trees and one for the source and macro property sheets. Both sets have similar behavior.

The Item Add Button

The item Add button (in the left pair) copies items from the History and operations folders up into macros. If a macro folder is selected in the macro tree then the new item is placed at the end of existing items. If a macro item is currently selected in the macro tree, then the new item is added to the macro folder, immediately following the selected macro item. If the top-level Macros folder is selected, then a new macro is created, and the item is placed within it.

With a visualization selected, the Add button adds a ‘Visualization...’ operation to the macro. This item will make a running macro present the Insert Visualization dialog to let you define parameters and insert a new visualization. Note that the **Show Dialog** property is set to True because you must define the parameters interactively, unlike with an Insert Visualization operation that has been recorded or copied from history.

You can select annotations in the source tree to select their properties, but you cannot move the annotations directly up into macros because they require initialization with data. The exception is annotations in the History folder (for more information, see [“Annotation Items”](#) on page 170).

The Item Remove Button

The item Remove button (in the left pair) removes the selected item or folder from the macro tree.

The Property Add Button

The property Add button (in the right pair) moves selected properties up into a new or existing SetProperty operation in a macro. Running a macro with a SetProperty operation applies the property setting to the selected visualization, letting you set the specified property on any applicable object.

Note

Once a property setting is added to a macro, it is no longer tied to a particular visualization type.

If you add a desensitized property to a macro item, the property will be sensitized (not grayed out) in the macro property sheet.

If you select an existing SetProperty item in the macro tree, IDL adds properties to it instead of creating a new SetProperty item.




Figure 8-14: An Example Using the Property Add Button

Figure 8-14 shows a SetProperty macro item created by selecting the Plot visualization in the source tree and three properties (Color, Line Style, and Thickness) in the source property sheet. The property Add button copied the desired property settings up into a SetProperty macro item containing all three properties.

The Property Remove Button

The property Remove button (in the right pair) removes any selected properties from SetProperty items. It is not enabled for other types of macro items.

Understanding Items in the Macro Editor

In the Macro Editor, you work with two main groups of items: those that make up a macro (items in the macro tree) and those that you use to create a macro (items in the source tree).

Macro Items

Macro items are the elements that make up a macro, namely operations and property settings. You insert them into a macro either during recording or, in the Macro Editor, by moving them from the source tree up into the macro tree. The properties of a selected macro item appear in the macro property sheet.




Figure 8-15: Macro Items in the Macro Editor

Figure 8-15 shows the macro items in the Sample Macro macro, both operations (Selection Change and Smooth) and property settings (SetProperty: Color, SetProperty: Minor ticks). The first SetProperty item is selected to show the property value (Color) that it will set on the selected object during playback.

Operations

Operations are the actions that you want the macro to perform on the selected object or objects, such as inserting a plot legend or applying a convolution filter. You can modify an operation's properties to customize it.

Some operations have the **Show dialog** property set to False by default when the operation is added to a macro, either by recording or in the editor. This setting lets the

operation run without displaying its dialog when the macro is run. In this case, any operation properties will be obtained from the saved macro item and used during playback. You can alter the value of this property to allow customization of operation properties during playback. If the **Show dialog** property of the macro item is set to True, then during macro playback the operation's dialog will be displayed, letting you alter any operation properties. Once the dialog is closed, the execution of the macro will continue.

SetProperty Settings

SetProperty settings contain only the properties being modified, which will apply to the currently active object during macro playback. They do not contain the **Name** and **Description** properties typically displayed for an object because the property can apply to whatever object is selected (that is, these fields are no longer tied to a certain type). However, if the name and description properties are selected in the editor or modified in a recording, the SetProperty item will display these properties as expected.

You can modify properties in the Macro Editor to customize your macros.

Source Items

This group consists of history items and four folders of operation items that you can use in macro creation: Visualizations, Annotations, Macro Tools, and Tool Menus. The items in all five groups are also available as a source for property settings to be added to a SetProperty macro item.

History Items

The History folder in the source tree, shown in [Figure 8-16](#), contains history items. The properties of a selected history item appear in the source property sheet.




Figure 8-16: The Macro Editor's History Folder

The History folder records actions that occur in an iTool. The history items are grouped into folders for each tool in current or past use, with each folder named by its tool identifier (e.g., 'PLOT TOOL' for an open iPlot tool). History items will continue to be added to history folders for the duration of the iTools session. This sequence of history items thus represents an audit trail for actions taken in a tool. It also serves as a source for the creation of macros.

Note

The History folder is cleared at the end of an iTools session (through the `itreset` command or by exiting IDL).

When you change a property value in an iTool, IDL creates a corresponding history item. The name of the property being changed is appended to the name of that item (e.g., 'SetProperty: Color' instead of simply 'SetProperty'). When you select or deselect an object in an iTool, the name of the object selected or deselected is concatenated to the name of that item (e.g., 'Selection Change: Axes'). In both cases, this additional information in the audit trail can show which properties were changed or which objects were selected or deselected.

Note

The object name is specified on history items but not on macro items, because when you run the macro, it might be operating on different objects based on the current selection. For more information, see [“Selection Changes”](#) on page 180.

Items from Closed Tools

When a tool is closed, the name and identifier of the history folder changes to indicate that the tool has been closed. The string ‘(Closed-N)’ is appended to the name of the history folder, where *N* is an integer starting at 1 and is incremented each time the tool with the same identifier is closed. After a tool is closed and the History folder renamed, creation of another tool of the same type causes the creation of a new tool with the name of the tool identifier. Actions in this tool would be recorded in a history folder named by the simple tool identifier.

For example, the following sequence creates the History folder items shown in [Figure 8-17](#):

1. Start iImage, open an image, and apply the Smooth operation.
2. Close iImage.
3. Start iImage, open an image, and apply the Median operation.
4. Close iImage.
5. Start iImage, open an image, and apply the Convolution operation.
6. Keep iImage open, start a new iImage tool, open an image in the new iImage, and apply the Dilate operation to it.
7. Close the second (newer) iImage.
8. Open the Macro Editor from the existing iImage tool.




Figure 8-17: A History Example with Open and Closed Tools

Run Macro Items

The Run Macro operation is itself an operation that will show up in the history and can be added to a macro. Using the Run Macro macro item lets you nest macros for grouping of common tasks.

If a macro has been run, you can copy a Run Macro item to a macro from the History folder. You can also add it from the **Tool Menus** → **Operations** → **Macros** subfolder in the source tree. The item contains a **Macro name** property to allow specifying the name of the macro to run. If you copy the item from history, this property is set to the name of the macro that was run, but you can set it to the name of any macro. If you add the item from the **Tool Menus** → **Operations** → **Macros** subfolder, the macro name property will be blank and should be set to the name of the desired macro to run. If you try to run a macro containing a nested Run Macro operation, you will get an error dialog if the macro name is invalid or the macro cannot be found.

Visualization Items

The Visualizations folder, shown in [Figure 8-18](#), contains the visualizations that you can use in the iTools.




Figure 8-18: The Macro Editor's Visualizations Folder

Visualizations require data for their creation, and so you cannot copy default items from this folder directly into a macro. When you add a visualization to a macro from the Visualizations folder, using the item Add button, the ‘Visualization...’ operation appears as a macro item with the **Show dialog** property set to True because you must define the visualization parameters interactively to define the data. If you want to add a visualization without having to show the **Insert Visualization** dialog, add an Insert Visualization operation from the History folder because that visualization already contains data.

You can select visualization items in the source tree to select their properties and add them to a macro (e.g., while editing a recorded macro, you could add a SetProperty item that changes the isovalue of an isosurface).

Annotation Items

The Annotations folder, shown in [Figure 8-19](#), contains the operations that create text, line (including geometric shapes), and legend annotations in a tool.




Figure 8-19: The Macro Editor's Annotations Folder

Annotations require data for their creation, and so default items from those folders cannot be copied directly to a macro. You can select annotations in the source tree to select their properties and add them to a macro (e.g., a SetProperty item that changes the caption of a text annotation), but you cannot move these items directly up into macros because they require initialization with data. If you want to add an annotation directly, you can only add an **Insert Annotation** operation from the History folder because that annotation already contains data.

Macro Tools Items

The Macro Tools folder, shown in [Figure 8-20](#), contains operations that are not in the standard menu system. You can use these items to build macros.




Figure 8-20: The Macro Editor's Macro Tools Folder

The operations in this folder deal with selection changes, tool changes, and the Scale, Translate, View Pan, Rotate, View Zoom, Range Change, Delay, Step Delay, and Step Display Change manipulations.

For information on selection and tool changes, see [“Making Selection and Tool Changes”](#) on page 179.

Scale Operation Item

The Scale operation stores the scaling factors from an interactive scale manipulation. [Table 8-4](#) shows the Scale operation's properties and values.

Property	Value
Description	Operation description, set by default to Scale
X Scale	Factor to scale the selected object's data in the x direction

Table 8-4: The Scale Operation's Property Values

Property	Value
Y Scale	Factor to scale the selected object's data in the y direction
Z Scale	Factor to scale the selected object's data in the z direction

Table 8-4: The Scale Operation's Property Values (Continued)

Note that you could have unpredictable behavior if you modify those properties in the Macro Editor and then run the macro containing the modified operation (e.g., an object scaled further than desired and thus obscuring important details). Be careful with estimating these values.

Translate Operation Item

The Translate operation stores the translation in pixels in the x and y directions from an interactive translate manipulation. This operation lets the macro system record and play back movements made with the Translate manipulator from the iTools toolbar (the Arrow icon).

Table 8-5 shows the Translate operation's properties.

Property	Value
Description	Operation description, set by default to Translate
X Translation	Number of pixels to move the selected object in the x direction
Y Translation	Number of pixels to move the selected object in the y direction

Table 8-5: The Translate Operation's Property Values

Because the [x, y] translation is relative to the selected object's current position, not absolute within an iTool view, you could have unpredictable behavior if you modify those properties in the Macro Editor and then run the macro containing the modified operation (e.g., an object moving out of view). Be careful with estimating these values.

View Pan Operation Item

The View Pan operation stores the movement in pixels in the x and y directions from an interactive view pan manipulation. This operation lets the macro system record and play back movements made with the View Pan manipulator from the iTools toolbar (the Hand icon).

Table 8-6 shows the View Pan operation's properties and values.

Property	Value
Description	Operation description, set by default to View Pan
X Pan	Number of pixels to pan the view in the x direction
Y Pan	Number of pixels to pan the view in the y direction

Table 8-6: The View Pan Operation's Property Values

Note that you could have unpredictable behavior if you modify those properties in the Macro Editor and then run the macro containing the modified operation (e.g., a view panned further than desired and thus obscuring important details). Be careful with estimating these values.

Rotate Operation Item

The Rotate operation stores the rotation angles from an interactive rotate manipulation. This operation lets the macro system record and play back movements made with the Rotate manipulator from the iTools toolbar.

Table 8-7 shows the Rotate operation's properties and values.

Property	Value
Description	Operation description, set by default to Rotate
X Rotation	Angle to rotate the selected object about the x-axis
Y Rotation	Angle to rotate to move the selected object about the y-axis
Z Rotation	Angle to rotate to move the selected object about the z-axis

Table 8-7: The Rotate Operation's Property Values

Because the [x, y, z] rotation is relative to the selected object's current position, not absolute within an iTool view, you could have unpredictable behavior if you modify those properties in the Macro Editor and then run the macro containing the modified operation (e.g., an object rotating further than desired and thus obscuring important details). Be careful with estimating these values.

View Zoom Operation Item

The View Zoom operation stores the zoom percentage from an interactive zoom manipulation. This operation lets the macro system record and play back movements made with the View Zoom manipulator from the iTools toolbar.

Table 8-8 shows the View Zoom operation's properties and values.

Property	Value
Description	Operation description, set by default to Zoom
Zoom Percentage	Zoom percentage on the selected object

Table 8-8: The View Zoom Operation's Property Values

Because the zoom percentage is relative to the selected object's current position, not absolute within an iTool view, you could have unpredictable behavior if you modify this property in the Macro Editor and then run the macro containing the modified operation (e.g., an object zooming further in than desired). Be careful with estimating this value.

Range Change Operation Item

The Range Change operation stores the changes to the dataspace range from interactive range zoom, range pan and range box manipulators. This operation lets the macro system record and play back changes made with the Data Range manipulator from the iTools toolbar (the graph icon).

Table 8-9 shows the Range Change operation's properties and values.

Property	Value
Description	Operation description, set by default to Range Change
X Minimum	Minimum value for the x coordinate of the data set
X Maximum	Maximum value for the x coordinate of the data set
Y Minimum	Minimum value for the y coordinate of the data set
Y Maximum	Maximum value for the y coordinate of the data set

Table 8-9: The Range Change Operation's Property Values

Property	Value
Z Minimum	Minimum value for the z coordinate of the data set
Z Maximum	Maximum value for the z coordinate of the data set

Table 8-9: The Range Change Operation's Property Values (Continued)

Note that you could have unpredictable behavior if you modify those properties in the Macro Editor and then run the macro containing the modified operation (e.g., the data range scaled up or down further than desired and thus obscuring important details). Be careful with estimating these values.

Delay Operation Item

The Delay operation can be added to a macro to cause a discrete delay at a particular place in a macro. The **Delay (seconds)** property of the operation allows setting a value in seconds to delay macro execution. This specific delay allows for a custom delay at a specified location in a macro, in contrast to the macro's **Step delay** property, which causes a delay between each step of the macro (see [“The Macro Property Sheet”](#) on page 156).

Note

When you are using the **Macro Controls** dialog to step manually through a macro, the delay is not applied. For more information on this dialog operation, see [“Step”](#) on page 150.

[Table 8-10](#) shows the Delay operation's properties and values.

Property	Value
Description	Operation description, set by default to Delay.
Delay (seconds)	Value, in seconds, to delay. The default value is 0.0. The minimum value is 0.0. There is no maximum value or step.

Table 8-10: The Delay Operation's Property Values

Step Delay Change Operation Item

The Step Delay Change operation can be added to a macro to change the step delay during macro execution. The Step Delay property of the operation allows setting a value in seconds to delay between macro items.

This step delay remains in place until the end of macro execution or until another Step Delay Change operation is encountered. The Step Delay value from this operation is not saved in the Step Delay property of the macro containing this operation. The step delay of the Step Delay Change operation is a temporary override of the macro's Step Delay property.

This delay allows setting the step delay for part of a macro. You can use several Step Delay Change operations within a macro to make different parts of a macro have delays of different length. If you want a discrete delay in a single location, use the Delay operation. For more information, see [“Delay Operation Item”](#) on page 175.

Note

When you are using the **Macro Controls** dialog to step manually through a macro, the step delay is not applied. For more information on this dialog operation, see [“Step”](#) on page 150.

[Table 8-11](#) shows the Step Delay Change operation's properties and values.

Property	Value
Description	Operation description, set by default to “Change the macro step delay.”
Delay mode	Indicates which delay to use. If Delay mode is set to “Use specified delay,” the Step delay (seconds) value becomes the current step delay. If Delay mode is set to “Use macro folder delay,” the step delay is retrieved from the macro applied to the current step delay.
Step delay (seconds)	Value, in seconds, to delay. The minimum value is 0.0, the maximum value is 60.0, and the default step is 0.01.

Table 8-11: The Step Delay Change Operation's Property Values

Step Display Change Operation Item

The Step Display Change operation can be added to a macro to toggle the visibility of intermediate steps during macro execution.

The setting for the **Display intermediate steps** property remain in place until the end of macro execution or until another Step Display Change operation is encountered. The **Display intermediate steps** value from this operation is not saved in the corresponding property of the macro containing this operation. The setting is instead a temporary override of the macro's **Display intermediate steps** property.

This property allows setting the visibility of intermediate steps for part of a macro. You can use several Step Display Change operations within a macro to make different parts of a macro show intermediate steps while other parts do not update the display.

Note

An update of the display is always done at the completion of macro execution.

Table 8-12 shows the Step Display Change operation's properties and values.

Property	Value
Description	Operation description, set by default to "Change the macro step display"
Display intermediate steps	Indicates whether to display intermediate steps, set by default to False (do not display intermediate steps)

Table 8-12: The Step Display Change Operation's Property Values

Tool Menu Items

The Tool Menu folder, shown in [Figure 8-21](#), contains the operations from the iTools' menu.




Figure 8-21: The Macro Editor's Tool Menu Folder

You can use items from the Tool Menu folder as a source for property settings or as a direct source for macro items. When you add one of these operations to a macro (e.g., to change the view layout of an iTool), you can modify the resulting macro item's property values to customize the actions taken by the operation when the macro runs.

Note

These operations are for the current tool. Therefore, this folder is no longer available if all tools are closed.

Making Selection and Tool Changes

You can change the selection of objects and even iTools in the course of a macro, to let you apply macro items to different objects within and across iTools. You can add these operations during macro recording or by using the Macro Editor, where you can find the selection change operations in the Macro Tools folder of the source tree.

Macro Type Based on Recording Selection

What you have selected when you start recording a macro gives rise to two general types of macros, where one of the following states is true:

- A visualization or annotation selected
- No visualization or annotation selected (e.g., a view selected instead)

In the first case, the macro's first item is a Selection Change operation with the **Selection type** property set to Existing Selection. This item represents the selection active when recording starts. When you play back the macro, it begins to apply its items (operations, property settings, or both) to the object that is selected when playback begins.

In the second case, the macro's first item is a Selection Change operation with the **Selection type** property set to No Items (De-Select All). When you play back the macro, the current selection is cleared before additional macro items are processed. You can create this type of macro if you want it to work on only specific objects or selections. The macro would typically clear the selection and then select the particular objects and then operate on them.

About Containers

The following discussion on the creation of these change operations and the properties of the operation introduces the concept of a container and position in the container. These concepts apply to both selection and tool changes, with some differences in the details.

For both changes, the term *container* is a generic term for one of the iTools objects that contains other objects. In relation to selection changes, the commonly referenced containers are the Data Space, the Annotation Layer, and the Window.

The Data Space contains visualizations that can be referenced by their position in the container. If you use the Visualization Browser to look at the visualization hierarchy, you can see that the order of the visualizations within the tree view represents their

positions in the container. This arrangement is also true of annotations within the Annotation Layer.

You can see the Window in the Visualization Browser as well. The Window is a container that holds Views, and the order of Views within the Window folder of the Visualization Browser is equivalent to the Views' positions in the container.

In relation to tool changes, the container is the current iTools session, containing all the tools. The tools container contains the individual tools, which can be referenced by their zero-based position in the container. The order of the tools is determined by their order of creation.

Selection Changes

The Selection Change operation is a macro item that can alter the current selection so that subsequent macro items are applied to different objects. During the recording of a macro, the selection change operations are added to the macro when the selection is changed interactively. In addition, when you start recording a macro, a Selection Change operation is added to reflect the current state of the selection (for more information, see [“Macro Type Based on Recording Selection”](#) on page 179).

Adding a Selection Change Operation

You can add a Selection Change operation either when you start recording a macro or during recording.

A Selection Change operation is inserted during recording if the selection is changed interactively. In this case, the type of the selection change operation is set to Position in Container. The values of the Container and Item Identifier properties are set. The value of the Selection Mode property is set to the applicable value of ['New Selection', 'Add to selection', 'Remove from selection'].

As with other operations, you can modify and delete the Selection Change operation by using the Macro Editor. You can also add the operation from the Macro Tools folder in the source tree.

Selection Change Operation Properties

Figure 8-22 shows a Selection Change operation's property sheet.

Selection Change	
Description	Selection Change
Selection type	Existing Selection
Selection mode	New Selection
Container	
Item identifier	
Position in container	0

Figure 8-22: The Selection Change Operation's Property Sheet

The **Description** property is set by default to Selection Change.

The **Selection type** property indicates the selection upon which the macro will act when you run it. This property can have the following values:

Property Value	Description
Existing Selection	Applies macro to the current selection.
Position in Container	Applies macro to the object indicated by the Position in Container property.
All in Container	Applies macro to all objects in the container.

Table 8-13: The Selection Type Property Values

Property Value	Description
Next in Container	Applies macro to the next object in the container based on the currently selected object or objects in the container. If multiple objects in the container are selected, the object with the highest position index is used as the starting point from which to determine the next in container. If the currently selected object is the last in the container, this operation wraps to the beginning when selecting the next in container.
Previous in Container	Applies macro to the previous object in the container based on the currently selected object or objects in the container. If multiple objects in the container are selected, the object with the lowest position index is used as the starting point from which to determine the previous in container. If the currently selected object is the first in the container, this operation wraps to the end when selecting the previous in container.
By Identifier	Applies macro to the object indicated by the Item Identifier property.
All Items	Applies macro to all items in all containers.
No Items (De-select All)	Applies macro to no items (requires a Selection Change operation in the macro to select an object).

Table 8-13: The Selection Type Property Values (Continued)

As [Table 8-13](#) indicates, several Selection Change properties deal with containers (for more information, see [“About Containers”](#) on page 179). For example, if the **Container** property is set to Data Space, a Selection Change operation with a Selection Type property of All in Container selects all visualizations.

The **Selection mode** property indicates the selection upon which the macro will act when you run it. This property can have the following values ([Table 8-14](#)):

Property Value	Description
New Selection	Makes the current object the selection

Table 8-14: The Selection Mode Property Values

Property Value	Description
Add to Selection	Adds the current object to the selection
Remove from Selection	Removes the current object from the selection

Table 8-14: The Selection Mode Property Values (Continued)

The **Container** property defines the container within which the Selection Change operation will act (e.g., Window/View_1/Visualization Layer/Data Space for the first View's data space).

The **Item identifier** property names the object upon which the Selection Change operation will act (e.g., View_1 for the first View in the Window).

The **Position in container** property identifies the selected object's position by number (e.g., 0 for the first item in the Visualization Layer).

Tool Changes

The Tool Change operation represents a macro item that sets the current tool so that subsequent macro items are applied in a different tool. During macro recording, a Tool Change operation is added when the currently selected tool is changed interactively. Note that when the tool selection changes because of an operation such as Histogram rather than changing interactively, a Tool Change operation is not added because it would be redundant (that is, the tool change is part of such an operation).

Adding a Tool Change Operation

You can add a Tool Change operation either when you record a macro or by adding the operation from the Macro Editor's source tree, in the Macro Tools folder.

If the operation is added during recording, the **Change type** property is set to By Identifier, and the identifier and position values are set. If it is added through the Macro Editor, only the **Change type** and **Position in container** properties are set (to By Identifier and 0, respectively).

As with other operations, you can modify and delete the Tool Change operation by using the Macro Editor.

Tool Change Operation Properties

Figure 8-23 shows a Tool Change operation's property sheet.

Tool Change	
Description	Tool Change
Change type	By Identifier
Tool identifier	
Position in container	0

Figure 8-23: The Tool Change Operation's Property Sheet

The **Description** property is set by default to Tool Change.

The **Change type** property indicates the kind of tool change that the macro will perform when you run it. This property can have the following values ([Table 8-15](#)):

Property Value	Description
By Identifier	Change selection to the tool indicated by the Tool Identifier property
Position in Container	Change selection to the tool indicated by the Position in Container property

Table 8-15: The Change Type Property Values

Property Value	Description
Next in Container	Change selection to the next tool in the container. If the current tool is the last in the container, the search for the next tool will wrap to the beginning of the container, and the first tool in the container will become the current tool
Previous in Container	Change selection to the previous tool in the container. If the current tool is the first in the container, the search for the next tool will wrap to the end of the container, and the last tool in the container will become the current tool

Table 8-15: The Change Type Property Values (Continued)

Recall that in terms of tool changes, the container means simply the current iTools session, encompassing all tools. For more information, see [“About Containers”](#) on page 179.

The **Tool identifier** property names the tool to which the Tool Change operation will change (e.g., ‘IMAGE TOOL’ for an iImage tool). This property is used only if the value of the Change Type property is By Identifier; otherwise, it is ignored.

The **Position in container** property identifies the tool to which the Tool Change operation will change by number (e.g., 0 for the first tool in the session). This property is used only if the value of the **Change type** property is Position in Container; otherwise, it is ignored.

Importing and Exporting Macros

You can import a macro from a file by selecting **File** → **Import** from the Macro Editor, which opens a dialog that lets you select one or more macro files to import. Macro files are IDL SAVE files created by exporting an existing macro.

Note

Macros created in future versions of IDL might contain features not present in the current release and might not behave as designed. Users will be warned if they are importing macros from a future version of IDL.

You can export a macro to a file by selecting **File** → **Export** from the Macro Editor. The filename that you specify will be used to create an IDL SAVE file containing the macro. The macro to be saved is specified by either the macro folder selected explicitly or the macro folder containing the selected macro item.

Note

If a Run Macro operation is in the macro being exported, you must export the macro to which that operation refers as well, to ensure proper playback behavior of the original exported macro.



Chapter 9

Working with Styles

This chapter introduces IDL iTool styles and discusses the following related-tasks:

What Are Styles?	188	Editing Styles	202
Creating Styles	190	Setting the Default Style	205
Applying Styles	196	Importing and Exporting Styles	206
Editing Styles	202		

What Are Styles?

iTool *styles* provide a convenient way to store and apply a set of properties to items in your iTool. While modifying individual property items within a style has the same effect as creating a new style that sets the same properties, a new style can be created, customized, and applied in a current session or in later sessions. Styles provide a shortcut mechanism that allows you to quickly apply groups of properties to your visualization, and to automatically alter the properties of newly-created visualizations. Styles are available across all iTools. For example, a style created in the iPlot tool will also appear as a Style selection when working in the iImage tool. However, only relevant style properties are applied to a selected visualization. Property settings for absent visualization items in the style are ignored.

Nearly all properties can be stored in styles. The only exception to this are user-defined properties (such as the color look-up table associated with an image). Individual property styles are never global, that is, the color property associated with a plot object applies only to a plot, and does not affect the color property of a surface. Nevertheless, a style can easily be created to set the color property for these individual visualization types.

When applied, styles are not permanently linked to a visualization. In other words, the visualization is exactly the same as it would be if individual properties had been set instead of the style being applied. Changes to the style are not automatically updated in the visualization unless the style is re-applied to the visualization. All of these characteristics ensure that when an iTool is saved and then shared with any other users, it will display identically. There is no need to send an associated style file.

Note

You can share styles with other users. See [“Importing and Exporting Styles”](#) on page 206 for details.

Type of Styles

Style information is stored in one or more style files located on your system. The two classes of style files are System Styles and Personal Styles:

- **System Styles** — IDL System Styles are pre-loaded in your IDL distribution. IDL's supplied System Styles are:
 - **IDL Classic** - This System Style contains IDL Direct Graphics' common black background with white text and white linestyle.
 - **IDL Standard** - This System Style is the iTools default and contains a white background with black text and black lines.
- **Personal Styles** — IDL Personal Styles are styles which you create. These are stored inside your `.idl` directory. When you create a new style within an iTool, it is automatically saved in this location.

Note

Style information is stored independently of any iTool. Styles are never automatically saved by simply making style changes in an iTool. They must always be saved explicitly.

Applying a Style

As mentioned, System Styles exist in your IDL distribution and are ready to use immediately (creating your own new Personal Styles is discussed at-length in the [Creating Styles](#) section). From an iTool window, in order to apply a style, select **Edit → Style → Apply Style...** or **Edit → Style → Style Editor...**

For more in-depth information on style application, see [“Applying Styles”](#) on page 196.

Creating Styles

There are two ways a new Personal Style can be created. You can use the iTool's Style Editor or you can select one or more visualizations within your iTool view (or the view itself) and create a new style. Both of these options are discussed here.

Creating a Style from the Current Visualization

You can create a new style by selecting one or more visualization objects within the view (or by selecting the entire view). A new style created in this manner will contain all property settings of the selected objects (or all objects in the view if nothing was selected).

Creating a Style From All Items in a View

The following example shows how to create a new style from all items in a view:

1. From the IDL Command Line, plot a simple line graph within iPlot:

```
iPlot, RANDOMU(seed, 30)
```

2. From the iPlot window, select one or more visualization objects or the entire view within the window. Then select: **Edit** → **Style** → **Create Style from Selection...**
3. Enter a name for your new style (in this example it is named **MyNewStyle1**) in the **Create Style from Selection** dialog shown in the following figure.



Figure 9-1: Create Style from Selection Dialog (MyNewStyle1 Style)

4. Now you can select between creating the new style using the selected items or using all items in the view. In this instance, choose **Create using all items in view**.

5. Select **OK** and the **iTools Style Editor** appears.
6. You can now expand the newly named style to view its properties. Under **MyNewStyle1**, select **Plot** and change the **Color** to your preference as shown here:




Figure 9-2: Selecting Background Color

7. Change the **Symbol** to **Asterisk**.
8. Now, from the Style Editor window, select the **Axis** object and change the color.
9. Select **File** → **Save** to save changes to **MyNewStyle1**.
10. Next, from the iPlot window, select **Edit** → **Style** → **Apply Style** and select **MyNewStyle1** from the **Apply Style** dialog that appears. Your new style, which contains changes to your line style color, plot symbol type (asterisks) and color of plot axes, is applied to the plot object.

Note

If multiple items of the same class are within a container (e.g. the axes container), the first one within the container will be used when creating the style.

Creating a Style From Selected Items

The following example shows how to create a new style from selected items within an iTool view:

1. From your existing iPlot window, select the text annotation tool (the letter A on the top of the window on the annotation toolbar).
2. Click anywhere in the window you wish to add a title for your plot. Type in “My Plot”.
3. Double-click on your new text annotation, and the Visualization Browser appears. Here you can edit the properties of your annotation. Change the text font, size, and color.
4. With your text annotation “My Plot” is selected (a box appears around the title when selected), select **Edit** → **Style** → **Create Style from Selection...**
5. Enter a name for your new style in the **Create Style from Selection** dialog shown in the following figure.




Figure 9-3: Create Style from Selection Dialog (NewTextStyle1 Style)

6. Name your new style **NewTextStyle1**. Now you can select between creating the new style using the selected items or using all items in the view. In this instance, choose **Create using selected items**.
7. Select **OK** and the **iTools Style Editor** appears.
8. Since we have already set our text options as we want them to appear, you can close the **Style Editor**.

9. Now open a new iPlot window and add a new title (for example, “My New Plot”) using the text annotation tool.
10. Select **Edit** → **Style** → **ApplyStyle** and select to apply **NewTextStyle1**. This applies the personal text style to the new annotation.

For details on applying a style to selected items or to all items within a view, or when launching an iTool, see “[Applying Styles](#)” on page 196. For information on modifying existing styles, see “[Editing Styles](#)” on page 202.

Note

If nothing is currently selected, then the Visualization Layer within the current view will be used when creating the style.

Creating a Style from Multiple Selected Items

Within an iTool view, you can select one or more visualization objects or annotations (or a combination of the two) to be included in a new Personal Style. To select one object or annotation simply click on the item. To select multiple items, select the first and then, holding down the **Ctrl** key, click on the other items.

Changes to the properties of the object or annotation can be made prior to creating a new style (by double-clicking on the item and altering the properties in the Visualization browser) or after creating a new style (within the iTools Style Editor).

Note

If multiply items of the same class are selected (say two axes), the first one selected will be used when creating the style.

Creating a New Style from the Style Editor

The Style Editor can be used to manually create a new style and specify the values of individual properties. Options are available in the Style Editor to duplicate existing styles, or to copy items from one style to another.

The following example shows how to create a new style using the iTool’s Style Editor:

1. First, open any iTool window and import some data.
2. From the iTool window, select **Edit** → **Style** → **Style Editor...** The iTools Style Editor window appears.

3. You will see *My Styles*, *System Styles*, and *Current Style* listed. Select *Current Style* and right-click and select **Duplicate**. A **Copy of Current Style** appears under *My Styles* and is named **Copy of Current Style**.

Note

From the iTool window you can also select **File** → **New Style**.

4. Select the **Copy of Current Style** and rename it to your desired name in the right-hand side of the Editor.

Note

To avoid confusion, styles should be given unique names. You may not name a style the same name as an IDL system style.

5. You are now able to make any changes within the new style by expanding the new style's object tree and making changes to the properties of individual visualization objects.
6. When finished, select **File** → **Save**.




Figure 9-4: The iTool's Style Editor

Note

For more information on how to populate the new style with properties, see [“Editing Styles”](#) on page 202.

Working with the Current Style

The Current Style contains the properties that will be used to create new visualizations in the current tool. The Current Style can be found in the iTools Style Editor. The Current Style can be modified by:

- Changing individual property values. These changes can be copied into another style, or applied to a visualization when the Current Style item is selected.
- Updating the Current Style when applying style modifications. See [“Applying Styles”](#) on page 196 for details.
- Updating the Current Style from a style in the Style Editor. Select a Personal or System style and select **Update Current Tool Style** from the context menu or **Apply** menu.

Note

The Current Style is not saved between IDL sessions or between iTools. Because of this, one use of the Current Style can be as a practice area to define new styles. Changes can be made to the Current Style and then used to create your desired style. You can then save this new style under a new name. The new style can be set as the “Default style” in the Preferences. For more information on setting a default style, see [“Setting the Default Style”](#) on page 205.

Copying an Existing Style

Any existing style can be copied within the Style Editor. This is useful when you want to change only a few style properties while maintaining the majority of a style’s existing properties. Simply click on the style name and choose **Edit** → **Copy** or **Edit** → **Duplicate**. Alternately, you can right-click on the style and choose **Duplicate** (or **Copy** and then **Paste**). A style named “Copy of *style name*” is then added in the My Styles folder of the Style Editor.

Note

Styles may be named and renamed as you wish.

Applying Styles

Styles can be applied to a single item or all items within a view. When a new visualization is added to an existing tool, the style of any previous visualization will not be automatically applied unless the preferred style is set as the default style (as described in “[Setting the Default Style](#)” on page 205) or unless the `STYLE_NAME` keyword is used. `STYLE_NAME` allows you to specify the name of a user-defined or system style to be applied to the created visualizations.

Changes to style properties are not automatically reflected in your visualization. To update a visualization with a modified style, you must reapply the style.

When the **Update current tool style** checkbox is selected on the **Apply Style** dialog, the Current Style is updated. Any properties set in the style you have just applied are also changed in the Current Style. Other properties are left unchanged. Any new visualizations added from that point on will have the updated style applied.

Applying a style modifies only applicable items. If the style does not contain any properties that are relevant to the selected item or visualization, no changes are made to the visualization.

Note

Selecting **Edit** → **Undo/Redo** will completely undo the application of a style. If a style is applied and **Undo** is selected, all properties changed by the style revert to their pre-application values.

Applying a Style to a Selected Item

You can apply a style to selected items in a visualization. For example:

1. From the IDL Command Line, visualize the following simple line graph:

```
iPlot, RANDOMU(seed, 30)
```
2. Highlight and select the plot line by clicking on the line.
3. Select **Edit** → **Style** → **Apply Style...**

The **Apply Style** dialog appears (as shown in the following figure). Here you can select your preferred style to be applied to the plot item.




Figure 9-5: The Apply Style Dialog

4. After selecting your preferred style (here **MyNewStyle1** has been selected), choose **Apply to selected items** so that the style changes will only be made to the selected item. **MyNewStyle1** was created to contain properties to change line color, plot symbol type, and axis color. Because **Apply to selected items** is selected and not **Apply to all items in view**, you can expect that the axes will remain their original color (black).

Note

If a particular existing style does not contain style information for an item that you have selected (for instance, if a style does not contain text information and you have selected a text item), no changes will be made to that item when the style is applied.

5. Click **OK** and your style changes will be visualized (as shown in the following figure).




Figure 9-6: iPlot Window Before (background) and After (foreground) Style Selection Application Changes Line Color and Plot Symbol Only

Note

If nothing is currently selected, then style will be applied to the Visualization Layer within the current view.

Applying a Style to All Items

You can also apply a style to all items within a view. For example:

1. Visualize a surface from the IDL Command Line by typing:

```
iSurface, dist(20)
```
2. Next add a text annotation to your image reading: **New Surface**.
3. Now select **Edit** → **Style** → **Apply Style...**
4. The **Apply Style** dialog appears (as shown in the following figure), here you can select your preferred style to be applied to the text item.




Figure 9-7: The Apply Style Dialog

5. After selecting your preferred style (here **IDL Classic** has been selected), select **Apply to all items in current view** so that the style changes will be made to all the items in the view.

Note

Selecting **Apply to all items in all views** applies the style changes to every item in every view available in the current iTool (e.g., an iPlot tool subdivided into four views using the VIEW_GRID keyword from the command line).

6. Click **OK** and the style is applied to the entire visualization.




Figure 9-8: iSurface Window Before (left) and After (right) Entire Style Application

Note

Applying a style to all items will ignore items that have the **Show** property is set to `False` (i.e. hidden items).

Applying a Style When Launching an iTool

The `STYLE_NAME` keyword allows you to apply a style to a visualization when an iTool is launched from the command line. This keyword can be used with any of the iTool routines (`ICONTOUR`, `IIMAGE`, `IMAP`, `IPLOT`, `ISURFACE`, `IVECTOR`, and `IVOLUME`).

Several system styles are included in your IDL distribution. For more information on setting a system style or created style, see [“Setting the Default Style”](#) on page 205.

Note

Styles specified in the `STYLE_NAME` string override the default style.

Editing Styles

The iTools Style Editor makes it possible to edit your existing personal styles as well as copies of IDL System Styles. The Style Editor is shown in the following figure.




Figure 9-9: The iTools Style Editor

It is important to note that IDL's System Styles cannot be edited. These can, however, be copied as a new style and then edited. For information on copying styles, see [“Copying an Existing Style”](#) on page 195. The following section describes various editing tasks related to styles.

Copying Properties Within Styles

You can copy properties from the Current Style, My Styles, and System Styles within the iTools Style Editor and paste these into any new or existing personal style. For example:

1. Select a style by clicking on it.
2. Select the style visualization object whose properties you wish to copy. The properties appear in the right panel of the editor.

3. Select a property by clicking on the property name and selecting **Edit** → **Copy** or right-clicking and selecting **Copy**.
4. Select the style name of the style in which you wish to add the copied property. The properties will be copied to corresponding visualization object within that style.
5. Select **Edit** → **Paste** or right click to select **Paste**. Your selected property is added to your selected style.

Cutting and Deleting Properties within Styles

You can cut or delete properties from your personal styles but not from the Current Style or from the System Styles. For example:

1. From the iTools Style Editor, select a personal style and select a visualization object property you wish to delete.
2. Select **Edit** → **Cut** or **Edit** → **Delete**. Alternately, you can right-click on the property and select **Cut** or **Delete**.

Note

Deleting a property from a personal style cannot be undone. Cutting a property places the property on the clipboard and the property may then be pasted within another style.

Selecting Multiple Properties for Editing

Multiple properties may be copied and pasted (for all styles), and cut or deleted (only for personal styles) as shown for individual properties in the previous sections. To select multiple properties for these operations:

1. Select a style by clicking on it.
2. Select the style visualization object whose properties you wish to copy. The properties appear in the right panel of the editor.
3. Click on the property name and then, for the selection of multiple discontinuous items, hold down the **Ctrl** key while clicking on any other properties you wish to select. For continuous selection, hold down the **Shift** key while clicking on the final property you wish to select in your group. All selected property names should appear depressed.

4. With your cursor over one of the property names and all desired properties selected, right-click and select **Copy**. Alternately, with all properties selected, you can select **Edit** → **Copy**.




Figure 9-10: The iTools Style Editor with Multiple Properties Selected to Copy

5. You can now select the style name of the style in which you wish to add the copied properties and find and highlight the corresponding visualization object within that style.
6. Select **Edit** → **Paste** or right click to select **Paste**. Your selected properties are added to your selected style.

Setting the Default Style

The default iTools style for your system can be set via the Preferences Browser. The Preferences Browser contains default property values used by all iTools. You can assign a personal style or any of the System Styles as the default iTools style preference. The default setting is none. To set a default style:

1. Select **File** → **Preferences**.
2. Select **General Settings**.
3. Select the desired style from the **Default Style** field drop-down list.




Figure 9-11: Selecting the Default Style

Once a default style is set, when a new iTool is started, the Current Style will contain a set of default values. That is, the default style is read into the Current Style.

Note

Because a default style is applied over the IDL system default settings, a default style does not need to include properties for all visualization types.

Importing and Exporting Styles

You can use the Styles import/export functionality to share style files between yourself and other users.

Exporting a File to Share


You can save (export) a style file to a place on your system to then share with other users. To do this:

1. From the Style Editor, select **File** → **Export...** and name the file, then save it into a directory as a style file (.sav).
2. This file can then be saved to a disk or sent via E-mail, FTP, etc. to another user.

Importing a Received File

You can import a saved style file. To do this:

1. From the Style Editor, select **File** → **Import...** and locate the desired file.
2. Click **Open**.
3. The style should now appear in your style listing in the iTools Style Editor.



Chapter 10

Working with Images

This chapter describes how to use the Image iTool.

Introduction	208	Filtering an Image	220
Displaying Images	209	Applying a Morphological Operator	222
Using the Image Panel	213	Contouring an Image	223
Image Properties	216	Surfacing an Image	225
Adding a Colorbar	217	Manipulating the Image Display	226
Adding Axes	218	iImage Tool Operations	231
Resampling an Image	219		

Introduction

The IDL `iImage` tool displays your data in image form. The `iImage` tool then allows you great flexibility in manipulating and visualizing image data. To use `iImage`, from the IDL Command Line, type `iImage`. An empty `iImage` tool appears. You can then import image data using any of several data import methods. For more information importing image data see [Chapter 2, “Importing and Exporting Data”](#).

Note

For more information on accepted arguments and keywords, see [“IIMAGE”](#) (*IDL Reference Guide*).

The `iImage` tool can be launched in many different ways:

- At the IDL Command Line without arguments or keywords
- At the IDL Command Line with arguments or keywords
- Through the **File** → **New** → **Visualization** → **iImage** menu option in the IDL Workbench
- Through the **File** → **New** → **iImage** menu option in an `iTool`

Common image file formats accepted are listed in [“Importing Image Data”](#) on page 34.

Displaying Images

The iImage tool's primary design is to visualize image data, though the tool is capable of much more once the data is displayed. The iImage tool also allows you to manipulate and edit the displays. The first task is to display the image data.

Your options for invoking the iImage tool are:

- At the IDL Command Line without arguments or keywords
- At the IDL Command Line with arguments or keywords

For more information on accepted arguments and keywords, see “**IIMAGE**” (*IDL Reference Guide*).

- Through the **File** → **New** → **Visualization** → **iImage** menu option in the IDL Workbench
- Through the **File** → **New** → **iImage** menu option in an iTool

To visualize image data in the iImage tool:

1. Image data can be loaded into the data manager. Image data of any supported type can also be directly visualized into the iImage tool using **File** → **Open** or the File Open icon  at the top left of your iImage window, and the File Open Dialog appears.
2. Select the desired image file from your directory structure. For example here we will visualize an `examples/data` file named `afrpolitsm.png`. Select the file name and click **Open**.




Figure 10-1: A JPEG File Visualized Using the `image` Tool

Note

The `examples/data` subdirectory of your IDL distribution contains a text file named `index.txt`. This file lists all data files available in the example directory and also lists their dimensions and values.

Displaying Multiple Images

You can use the window layout dialog to provide for multiple image display within your window. To add another image to the window containing the image you just visualized:

1. From the iImage window displaying the political map of Africa JPEG image, select **Window** → **Layout**.




Figure 10-2: The Window Layout Dialog

The Window Layout dialog contains these items:

- **Dimensions** — Allows you to enter specific window dimensions.
- **Layout** — Allows you to pick from a scroll-down list of layout options and grids.
- **Preview** — Gives you a visual preview of the selected layout.

For more information on working with window layouts, see [“Window Layouts”](#) on page 73.

2. Select a layout, in this case select **Gridded** and then enter 2 and 1 for **Columns** and **Rows** and then **OK**.

3. The window now displays a two by two arrangement of views. You will notice the original political map of Africa image is shifted to the top-left view. Select and highlight the top-right view.
4. Select **File** → **Open** or the File Open icon  at the top left of your iImage window, and from the **File Open** Dialog select the `examples/data` image named `africavlc.png` and click **Open**.
5. The second image of the African continent now appears in the top-right view.




Figure 10-3: Displaying Multiple Images in iImage

Using the Image Panel

The image panel appears to the right of the visualization window of the iImage tool. This panel allows you to view and manipulate various image properties such as pixel location and values and color properties. You can also draw ROIs within your visualization. The components and functions of the image panel are discussed in the following figure and list.




Figure 10-4: The Image Panel

- **ROIs** — The ROI buttons on the image panel allow you to draw regions of interest within your visualization. For more information on ROIs, see [Image ROIs](#) in the following section.
- **Pixel Location** — If your pointer/cursor is held over the visualization, the precise pixel location will be shown in this area.

- **Pixel Value** — Pixel color values are shown in this area.

Note

If the byte scaled pixel value (used for display) is different from the image data value at that pixel, it will be displayed in parentheses.

- **Pixel Scale** — Pixel scale data is shown in this area.
- **Edit Palette** — This button is enabled for indexed binary and greyscale color images. For more information on the Palette Editor, see [The Palette Editor](#) in the following section.
- **Window Level Control** — The window level control allows you to adjust and manipulate the image brightness and contrast by changing the RGBA or indexed channel values. For more information on the window level control, see [Window Level Control](#) in the following section.

Image ROIs

The ROI buttons (shown in the Image Panel in the preceding figure) allow you to draw regions of interest within your visualization. You can select from rectangular, elliptical, polygonal, and freehand region of interest buttons. Once you have created your ROI, you can also apply operations to image data contained within an ROI area.

Note

The ROI tools are not available for images that have an associated map projection.

Select the desired button and then hold your cursor over the area in the visualization where you wish your ROI to appear. Click the left mouse button and drag until the ROI is the desired shape and location. ROIs can be selected and moved or deleted after they are drawn.

Note

For more information on operations and regions of interest, see [“Operations on Regions of Interest”](#) on page 133.

The Palette Editor

RGB images contain their own color information while color information for indexed images is separate from the image itself. Color information can be modified for indexed and greyscale images.

The easiest way to modify color attributes for a selected indexed, binary, or greyscale image is to click on the **Edit Palette...** button on the image panel to the right of your visualization.

The various components and functions of the Palette Editor are discussed in [“CW_PALETTE_EDITOR”](#) (*IDL Reference Guide*).

Note

You can also access the palette editor by selecting the image visualization (clicking once on the visualization and then double-clicking on it to bring up the Visualization Browser) and selecting **Image Palette** → **Edit Color Table** → **Edit**.

Window Level Control

The Window Level Control on the iImage tool allows you to adjust and manipulate the image brightness and contrast for each channel of the currently selected image. The **Channel** droplist allows you to select the channel to be adjusted. The **Link All** checkbox may be selected to cause all channels to be adjusted simultaneously. A small plot window shows the histogram for the currently selected channel. For indexed color images, Channel 0 represents the image data values. For RGBA images, Channel 0 represents the red values, Channel 1 represents the green values, Channel 2 the blue values, and Channel 3 the alpha values (if present). Within the plot area is a red bar representing minimum values and a green bar representing maximum values. You can click on each bar to manipulate these values. The dotted black bar represents the level; you can click and drag this bar to move both the minimum and maximum values simultaneously.

Image Properties

The iImage tool is a self-contained image display and manipulation tool. You can import, export, modify, and manipulate image data. For more information on the basic iImage interface and its layout, see [Appendix A, “iTools Interface Reference”](#).

Modifying Properties

By selecting **Edit** → **Properties** from the iImage tool, you may modify your image properties. You may modify your image’s name, description, transparency, interpolation, pixel dimensions, pixel origin, and so on. For more information on editing properties in the iTools, see [Appendix D, “Visualization Properties”](#).

Adding a Colorbar

You can add a colorbar to your visualized image which will show on a color scale the minimum to maximum pixel values. To add a colorbar, click on the image and then from the **Image** window, select **Insert** → **Colorbar**. A colorbar will be placed in the visualization window. This colorbar can be resized and moved around the window. You can also double-click on the colorbar to invoke the Visualization Browser, which will allow you to change properties for the colorbar.




Figure 10-5: Image With Inserted Colorbar

Adding Axes

You can add X and Y axes to your image data by selecting **Insert** → **Axis** from the iTool window. From here you can select **X Axis** or **Y Axis**. You can modify axis properties by opening the Visualization Browser and selecting **Axes** and then changing the **Style** property from **None** to the desired style. Another option is to double-clicking on the axis itself within the visualization and modify its properties.




Figure 10-6: Image in iImage with Axes Inserted and Placed

Resampling an Image

Resampling re-imports the selected image data using parameters specified in the Resample properties. Resampling parameters include factors for adjusting the X, Y, or Z dimensions of the data, as well as the interpolation method to be used.

To resample image data:

1. Select one or more images in the iImage window for resampling.
2. If necessary, use the Operations Browser to set the desired parameters through the Resample properties. See [“Resample Properties”](#) on page 406 for details.
3. Select **Operation** → **Transform** → **Resample**.

Filtering an Image

There are six types of filters available in the iImage tool.

Convolving an Image

To convolve an image:

1. Select the image to be convolved.
2. Select **Operations** → **Filter** → **Convolution**.
3. The convolution filter editor appears and desired settings can be edited.
4. Click **OK** and the filter is applied.

For more details on the convolution filter, see [“Convolution Filter”](#) on page 124.

Applying a Median Filter

The median filter replaces each pixel with the *median* (a value in an ordered set of values with an equal number of values above and below it) of the two-dimensional neighborhood of a given width.

To apply the median filter to an image:

1. Select the image.
2. Select **Operations** → **Filter** → **Median**.

For more details on the median filter, see [“Median Filter”](#) on page 123.

Smoothing an Image

The smooth filter removes unwanted noise from an image using a weighted average.

To apply the smooth filter to an image:

1. Select the image.
2. Select **Operations** → **Filter** → **Smooth**.

For more details on the smooth filter, see [“Smooth Filter”](#) on page 122.

Applying a Roberts Filter

The Roberts filter uses the Roberts edge enhancement operator to detect edges within the image.

To apply the Roberts filter to an image:

1. Select the image.
2. Select **Operations** → **Filter** → **Roberts**.
3. The Roberts filter is applied.

Applying a Sobel Filter

The Sobel filter uses the Sobel edge enhancement operator to detect edges within the image.

To apply the Sobel filter to an image:

1. Select the image.
2. Select **Operations** → **Filter** → **Sobel**.
3. The Sobel filter is applied.

Applying an Unsharp Mask

The unsharp mask enhances the contrast between neighboring pixels in an image.

To apply the Unsharp Mask filter:

1. Select the data that you want to unsharp mask.
2. Select **Operations** → **Filter** → **Unsharp Mask**.

For more details on the unsharp mask filter, see [“Unsharp Mask Filter”](#) on page 125.

Applying a Morphological Operator

Mathematical morphology is a method of processing digital images on the basis of shape. Six morphing options are available for use in iImage: dilate, erode, morph open, morph close, morph gradient, and morph tophat. For more information on morphing, see [“Morphing”](#) on page 127. To morph your image, select **Operations** → **Morph** → *<option>*.

Contouring an Image

You can also insert a contoured representation of your image data into your visualization. To do this:

1. From the iImage window containing a visualized image, select **Operations** → **Contour**.
2. The Contour dialog appears (shown below) allowing you to adjust contour setting, including:
 - **Number of levels:** Set the number of contouring levels
 - **Value:** Set the contour value to use
 - **Projection:** Choose the contour type (Planar or 3D)




Figure 10-7: The Contour Dialog

3. After making any contour property changes, select **OK** to contour your image data.

The following figure shows contouring added to the image of a meteor surface.




Figure 10-8: A Contoured Image in iImage

You can highlight and double-click your contoured image data, invoking the Visualization Browser which allows you to edit Contour Level properties and Contour Level color table data. For more information on these edit options, see [“Contour”](#) on page 453.

Surfacing an Image

You can also insert a surface representation of your image data into your visualization by selecting **Operations** → **Surface**. This causes the display to become three-dimensional. The following figure shows a surface added to the image of the African political map.




Figure 10-9: Image Data Shown as a Surface

You can highlight and double-click your new surface, invoking the Visualization Browser which allows you to edit surface properties. For more information on these edit options, see “[Surface](#)” on page 448.

Manipulating the Image Display

The iImage tool allows you many options to manipulate your existing image displays. Once you have visualized your image, you may rotate, flip, translate, scale, and zoom as well as modify image properties, scroll, and select image ROIs. The following options are available for manipulating images.

For more information on manipulation tasks which are common to iImage as well as other iTools, see [Chapter 4, “Manipulating the Display”](#).

Rotating an Image

The rotate operation makes it possible to rotate the image within the visualization by a specified number of degrees. To rotate your selected image, select **Operations** → **Transform** → **Rotate Data**. For more information about rotating, see [“Rotation”](#) on page 115.

Scaling an Image and Byte Scaling an Image

It is possible to scale the pixel values within an image by a specified scale factor. To scale your image, select **Operations** → **Transform** → **Scale Data**. For more information on scaling data, see [“Scaling”](#) on page 65.

Note

When working with byte data, the default byte scale range is always 0-255. Therefore, even if data ranges from 0-100, it will display using 0-255. This may cause visualized data to appear darker.

Inverting an Image

You can also invert the data associated with your image, or with each channel of an RGB or RGBA image. If the data is byte data, the inversion occurs relative to the maximum byte value (255). Otherwise, the inversion occurs relative to the maximum data value per channel. To invert your image, select **Operations** → **Transform** → **Invert Image**.

Flipping an Image

You can flip your image within the data space either horizontally or vertically. These operations flip the actual data associated with the image. To flip your data, select **Operations** → **Flip** → **Flip Horizontal** or **Operations** → **Flip** → **Flip Vertical**.

View Zoom

View Zoom allows you to zoom in or out on a specific area of the image display area. To zoom in or out in View Zoom mode click Zoom  on the toolbar or select a percentage value from the View Zoom droplist. For more information on working with View Zoom, see “[Zooming](#)” on page 70.

Canvas Zoom

Canvas Zoom allows you to increase or decrease the magnification of the entire display canvas (which may contain multiple views, depending on the layout) by a specified percentage. Canvas Zoom is available by selecting a percentage from the **Window** → **Canvas Zoom** menu. For more information on working with Canvas Zoom, see “[Zooming](#)” on page 70.

Pixel Scaling

The pixel scale represents the number of window pixels used to display a single image pixel (horizontally and vertically). Pixel scaling is shown on the image panel (which appears on the right side of the iImage tool) and can be manipulated via the View Zoom manipulator on the iImage window toolbar and using its accompanying pull-down menu.

When an image is first loaded into iImage, the X and Y pixel scales are by default set to 100% (one window pixel is used to display one image pixel horizontally).

Typically, when iImage first displays an image, the view zoom factor matches the X pixel scale. Changing the view zoom factor also updates the pixel scale labels.

If the currently selected image has been rotated, or if the visualization has switched to 3D (for example, because a surface was inserted), then the pixel scale labels are set to an empty string.

Region Growing

The iImage region growing operation lets you apply a region growing algorithm to the currently selected ROI. A new ROI is then created and displayed. To apply region growing to your ROI, select **Operations** → **Region Grow**. You can then select the region grow method (by threshold or by standard deviation).

Adding Annotations

Annotations can be added to label or describe image visualizations displayed in the iImage tool.

The following types of annotations can be added to iImage displays:

Image Annotation Type	Description
Text	Single lines or multiple lines of text can be added to a visualization to provide a label or description
Line	Straight line annotations can be added to a visualization to link labels to objects or to identify an object
Rectangle	Rectangular annotations can be added to a visualization to identify rectangular areas
Oval	Oval annotations can be added to a visualization to identify circular areas
Polygon	Polygon annotations can be added to a visualization to identify areas bounded by a multi-sided polygon
Freehand	Freehand annotations can be added to a visualization to identify an area

Table 10-1: Types of Image Annotations

For more information on creating and using annotations, see [Chapter 5, “Adding Annotations”](#).

Line Profiles

You can plot image pixel values along a selected line. These values are extracted as a line profile of part of your image visualization and displayed in a new iPlot window:

1. From an iImage window with a visualized image, click on the **Line Profile** icon on the toolbar.
2. Use the mouse to position the jagged-edge line profile tool over the place which you wish your line profile to begin and click.
3. Drag to the ending point of your line profile and release.

4. A new plot window appears showing a plot of the image pixel values that fall along that line.

Once a line profile has been drawn, it will remain until deleted. The line may be translated (or its endpoints moved individually). If it is translated or edited, the profile plot will automatically update.

If you dismiss your Plot Profile window and wish to have it back again, from your iImage window, with the line selected, choose **Operations** → **Plot Profile** and the Plot Profile window will reappear.

Note

Line profiles on map projections always connect points using the image coordinates (either degrees or meters). See “[Registering an Image](#)” on page 335 for more information on image coordinates.

View Panning

To pan an image, select the View Pan tool button  on the toolbar and then click on the image and drag until it is in the desired location. Panning causes the extents of the visible portion of the view to be shifted.

Cropping an Image

The iImage crop manipulator button allows you to crop your image to your specified size and dimension. It also allows you to translate and resize the crop box, and then apply the crop to the currently selected image or images. The button appears in the toolbar as shown in the following figure.



Crop Manipulator Button

Figure 10-10: The Crop Manipulator Button on the Toolbar

The crop box will appear only if information has been set and is applicable to the currently-selected image. If the crop box information has not been set for the crop operation, or does not fit within your image, then no crop box appears. For more information see [“Cropping Images”](#) on page 231

If no crop box visual is present, you can click using the mouse anywhere on an image and drag to create a crop box.

Note

All portions of the image that fall outside of the crop box are grayed out.

Once a crop box is present, it may be translated (by clicking and dragging anywhere within the crop box, or along its edges) or scaled (by clicking and dragging on one of the scale handles). A new crop box can also be created by clicking anywhere within the gray area outside of the current crop box.

The arrow keys can also be used to translate the crop box (when the mouse location is anywhere within the crop box or along its edges).

When your crop box is correctly sized and positioned, you can crop the image by:

- Double-clicking anywhere within the defined crop box
- Right clicking to invoke the context menu, and then selecting Crop
- Selecting **Operations** → **Crop** from the iImage tool.

iImage Tool Operations

The iImage tool provides the following operations:

Viewing a Histogram

A histogram is a density plot showing a distribution of data values. To view a histogram of image data, use the iTool's histogram feature by selecting **Operations** → **Histogram**. For information on histogram creation, see [“Plotting a Histogram”](#) on page 128.

Viewing Image Statistics

To view statistics for image data or for ROIs, use the iTool's statistics feature by selecting **Operations** → **Statistics**. For information on viewing statistics, see [“Displaying Statistics”](#) on page 129.

Cropping Images

The iImage cropping operation allows you to crop one or more selected images at a specified location and specified dimensions. To activate the cropping operation, select **Operations** → **Crop**. The Crop manipulator is automatically activated.




Figure 10-11: The Crop Operation Dialog

Note

The appearance of this dialog can be disabled for future uses of the crop operation by setting the Show dialog property to False.

The X, Y and Width, Height properties in the dialog represent the location and dimensions of the crop box to be applied. If these values have never been set, they are by default initialized to match the full extent of your first selected image. If these values have previously been set, they are constrained to fit within the first selected image. You can enter new values manually, or the mouse can be used to define, resize, and/or translate the crop box.

The Units property can be set to indicate the units of measure to be used for reporting crop box coordinates. The default is data units. This property will automatically reset to data units (and become de-sensitized) if multiple images are selected and their pixel origins or pixel sizes differ.


Once your crop dialog is present on your image, you can crop by doing the following:

- Double-clicking anywhere within your defined crop box (in the primary visualization window).
- Pressing the Crop button within the crop operation dialog.

Once your image is cropped, the original image is replaced by the new, cropped image data. You can only retrieve your original data by selecting **Edit** → **Undo crop**, or by reloading the original image data as a separate visualization.

Note

If your original image contains any ROIs, those that do not lie completely within the crop box will be lost in the new image.



Chapter 11

Working with Surfaces

This chapter describes how to work with surfaces in the iSurface tool.

Introduction	234	Contouring a Surface	244
Displaying Surfaces	235	Resampling a Surface	246
Surface Properties	237	Filtering a Surface	247
Adding a Colorbar	239	Adding a Texture Map	248
Adding a Light	240	Manipulating Surface Displays	249
Adding a Legend	241	iSurface Tool Operations	254
Adding Axes	242		

Introduction

The IDL iSurface tool provides interactive access to surface data. You can visualize surfaces and then modify and manipulate those surfaces in the ways that you need. The following sections describe how surfaces can be displayed, modified, and manipulated in iSurface.

To use iSurface from the IDL Command Line, type `iSurface`. An empty iSurface tool appears. You can then import surface data using any of several data import methods. For more information on importing surface data, see [Chapter 2, “Importing and Exporting Data”](#).

Note

For more information on accepted arguments, see [“ISURFACE”](#) (*IDL Reference Guide*).

The iSurface tool can be launched in the following ways:

- At the IDL Command Line without arguments or keywords
- At the IDL Command Line with arguments and keywords
- Through the **File** → **New** → **Visualization** → **iSurface** menu option in the IDL Workbench
- Through the **File** → **New** → **iSurface** menu option in an existing iTool

Displaying Surfaces

Three-dimensional visualizations of surfaces can be displayed in the iSurface window.

To open an iSurface window, do one of the following:

- At the IDL command line, enter `ISURFACE`
- From an iTool window, select **File** → **New** and select **iSurface**

Surface data can be displayed by specifying data parameters at the IDL command line, or by importing a binary or ASCII text file containing surface data.

To import a file containing surface data into the iSurface tool:

1. Select **File** → **Open** from the iSurface tool and locate the file to open. For example, from your IDL `examples/data` directory, select `idemosurf.dat`.
2. Double-click the filename or select the filename and click **Open** to open the surface data file. You will be prompted to enter information regarding your file type (for example, ASCII or binary). For more information on entering this information and on importing data, see [Chapter 2, “Importing and Exporting Data”](#). In this example, enter *demosurface* for your template name and then select **New Field** and specify *demosurface* as the **Field Name** and specify it as a two-dimensional 200 by 200 Floating type.
3. Then select **OK** and **OK** to dismiss and visualize.




Figure 11-1: Surface Data Visualized in iSurface

Surface Properties

Surfaces have attributes or *properties* that can be modified to change their characteristics. These properties are organized into *property sheets* for each operation and visualization type. For example, the skin of a surface visualization has a gold color by default. To change this color, modify the surface color property in the surface visualization property sheet.

To display the property sheet for a surface, do one of the following:

- Double-click the surface in the iTool window
- Select the surface, and select **Edit** → **Properties**
- Display the Visualization Browser, and double-click the entry for the surface

For more information, see [Chapter 6, “Property Sheets and Browsers”](#).

The Visualization Browser

The Visualization Browser provides a nested list of all visualizations displayed in the iSurface window. From the Visualization Browser, you can select visualizations and display property sheets for those visualizations.

To display the Visualization Browser:

1. Select **Window** → **Visualization Browser**.
2. Do either of the following:
 - Click an item to select it in the Visualization Browser
 - Double-click an item in the iTool window to display its property sheet

For more information, see [Chapter 6, “Property Sheets and Browsers”](#) and [Appendix D, “Visualization Properties”](#).

The Operations Browser

The Operations Browser provides a nested list of all operations available from the iSurface Operations menu. From the Operations Browser, you can display property sheets for each of the items in the iSurface Operations menu.

To display the Operations Browser:

1. Select **Operations** → **Operations Browser**
2. Click an item to display its property sheet

For more information, see [Chapter 6, “Property Sheets and Browsers”](#) and [Appendix C, “Operations Properties”](#).

Adding a Colorbar

If you have added vertex coloring or texture to your surface visualization, you can add a colorbar that will show on a color scale the minimum to maximum values of data in the visualization. To add a colorbar, click on the surface data and then from the iSurface window, select **Insert** → **Colorbar**. A colorbar will be placed in the visualization window. This colorbar can be resized and moved around the data space. You can also double-click on the colorbar to invoke the Visualization Browser which will allow you to change the values for the colorbar. For more information on the colorbar, see [“Colorbar”](#) on page 477.

Adding a Light

Adding a light to your surface display allows you to highlight various parts of the surface. To add a light to your surface display, select **Insert** → **Light**. you can click on the light bulb which appears and drag it around the display area to manipulate the lighting. You can also adjust the lighting settings using the Visualization Browser by double-clicking on the light bulb.




Figure 11-2: Inserting Light into a Surface Display

Adding a Legend

Legends identify the visualizations displayed in the iTool window. Legends can be displayed in the iSurface window to identify surfaces and contours on those surfaces.

To insert a legend for a surface or contour:

1. Select specific items to include in the legend, or click in an empty area of the iSurface dataspace to deselect and include all dataspace items in the legend.
2. Select **Insert** → **New Legend**.

To add to a legend:

1. Select the visualization item or items to add to the legend.
2. If there are multiple legends, add the desired legend to the selection by shift-clicking the legend border.
3. Select **Insert** → **Legend Item**.

Note

Only a single legend item may exist for a given visualization. If you are inserting multiple visualization items into an existing legend, only legend items for those visualizations not already represented will be added to the legend.

For more information, see “[Legends](#)” on page 77.

Adding Axes

By default, surfaces are displayed with X, Y and Z axes. The display of these axes is controlled by property sheets for the axes container and for individual axes (see [“Axes”](#) on page 485). Additional X, Y or Z axes can be added to a surface visualization to make it easier to identify surface characteristics.

To add an axis to your surface visualization:

1. Select the surface.
2. Select **Insert** → **Axis**.
3. Choose from the following options:
 - **X axis**
 - **Y axis**
 - **Z axis**

Use the mouse to position the new axis, and double-click the axis to display the axis property sheet.

For more information on adding axes, see [“Additional Axes”](#) on page 84.

Imaging a Surface

You can insert an image of your surface data by using **Operations** → **Image**. An image visualization of your original surface data is then displayed with your original surface visualization.

For example at the IDL command line,

1. Enter `iSurface, DIST (10)`
2. Now select **Operations** → **Image**.




Figure 11-3: Surface Visualization with Image Added

Contouring a Surface

Contour lines can be drawn directly on a surface to provide information about the levels of the surface, such as elevation. Two types of contours can be applied: multiple-level contour operations that apply to the surface in general, and single-level contour objects applied at a specific location on the surface.

To add contour lines to a surface:

1. Select the surface in the iTools window. For example, select the `isurfdemo.dat` surface data previously visualized.
2. Select **Operations** → **Contour**.
3. The Contour dialog appears (shown below) allowing you to adjust contour setting, including:
 - **N_LEVELS**: Set the number of contouring levels
 - **Value**: Set the contour value to use
 - **Projection**: Choose the contour type (Planar or 3D)




Figure 11-4: The Contour Dialog

4. After making any contour property changes, select **OK** to contour your surface.
5. Contour lines are applied to the surface at the interval specified in the contour dialog.




Figure 11-5: Surface with Contours Added

6. To adjust the properties of the contour, double-click the contour in the iTool window or in the Visualization Browser to display the Contour property sheet. For information on the contour properties, see “[Contour](#)” on page 453.

To insert a contour object at a specific location on a surface:

1. Select a surface in the iSurface window.
2. Click the Surface Contour button  in the Manipulator toolbar.
3. Click the level on the surface at which you would like the contour to appear. Contour lines are displayed on the surface at that level.
4. To adjust the properties of the contour object, double-click the contour object in the iTool window or in the Visualization Browser to display the Contour property sheet. For information on the contour properties, see “[Contour](#)” on page 453.

Resampling a Surface

Once surface data has been imported into the iSurface window, that data can be re-imported using different import parameters by *resampling* the data. See [“Resample”](#) on page 119 for details.

To resample a surface:

1. Select a surface in the iSurface window. For example, select the `isurfdemo.dat` surfaced data.
2. Select **Operations** → **Transform** → **Resample**.




Figure 11-6: Resampled Surface in iSurface

Filtering a Surface

Three types of filters are available in the iSurface tool: smooth filtering and convolution filtering.

Convolving a Surface

To convolve a surface:

1. Select the surface to be convolved.
2. Select **Operations** → **Filter** → **Convolution**.

For details on using the convolution filter, see [“Convolution Filter”](#) on page 124.

Median a Surface

The median filter replaces each point with the *median* (a value in an ordered set of values with an equal number of values above and below it) of the one- or two-dimensional neighborhood of a given width.

to median a surface:

1. Select the surface.
2. Select **Operations** → **Filter** → **Median**.

For details about using the median filter, see [“Median Filter”](#) on page 123.

Smoothing a Surface

The smooth filter removes unwanted noise from a surface.

To apply the smooth filter to a surface:

1. Select the surface.
2. Select **Operations** → **Filter** → **Smooth**.

For details on using the smooth filter, see [“Smooth Filter”](#) on page 122.

Adding a Texture Map

An image file can be imported into a surface visualization to serve as a *texture map*: an image projected onto the surface skin in place of the default red skin.

To add a texture map to a surface:

1. Select the surface.
2. Select **Edit** → **Parameters** to open the Parameter Editor.
3. Click **Import File** to import the image file to be used as a texture map into the Data Manager.
4. Find the image file in the list of files in the Data Manager tree and select either a specific image channel to import, or select **Image Planes** to import all channels of the image.
5. Click the **Assign Data** button  under TEXTURE. The name of the data to import appears in the TEXTURE field.




Figure 11-7: TEXTURE Field in Parameter Editor

6. Click **OK**. The Parameter Editor window closes, and the texture map appears on the surface.

Manipulating Surface Displays

The iSurface tool provides options for manipulating surface data. You can rotate as well as scale surfaces. These manipulations are described in the following sections.

Rotating a Surface

Rotation tools are provided in the iSurface tool to make it easier to see all aspects of a 3-D surface visualization. Surfaces can be rotated freely or along an axis with the mouse, and they can be rotated in fixed or arbitrary increments from the Operations menu.

To rotate a surface freely or along an axis with the mouse:

1. Select the surface in the iSurface window.
2. Click Rotate  on the Manipulator toolbar. The rotation sphere is displayed around the surface.




Figure 11-8: Surface with Rotation Sphere Displayed

- To rotate the surface freely, position the mouse pointer over the surface so that it changes to a free rotation pointer . Click and drag to rotate the surface in the desired direction.
- To rotate the surface along an axis, position the mouse pointer over an axis so that it changes to an axis rotation pointer . Click and drag to rotate the surface along the axis in the desired direction.

To rotate a surface in 90° increments left or right from the Operations menu:

1. Select the surface in the iTool window.
2. Select **Operations** → **Rotate** → **Rotate Left** or **Operations** → **Rotate** → **Rotate Right**.

To rotate a surface an arbitrary number of degrees from the Operations menu:

1. Select the surface in the iTool window.
2. Select **Operations** → **Rotate** → **Rotate by Angle**.

3. In the Rotate Angle dialog, enter the desired number of degrees to rotate the surface.

For more information, see “[Rotation](#)” on page 115.

Scaling a Surface

Surfaces can be scaled freely, or scaling can be constrained to one or more dimensions.

To scale a surface freely:

1. Select the surface in the iTool window.
2. Position the mouse pointer over a side of the data set bounding box so that it changes to an unconstrained scaling pointer .
3. Click and drag to scale all points of the surface in the desired direction.

To constrain scaling of a surface:

1. Select the surface in the iTool window.
2. Position the mouse pointer over an axis “whisker” to scale along only one axis, or over a corner of the bounding box for multi-axis scaling.




Figure 11-9: Constrained Single-Axis (left) and Multi-Axis (right) Scaling

3. Click and drag to scale in the desired direction.

For more information, see “[Scaling](#)” on page 65.

Adding Annotations

Annotations can be added to label or describe surface visualizations displayed in the iSurface tool.

The following types of annotations can be added to iSurface displays:

Plot Annotation Type	Description
Text	Single lines or multiple lines of text can be added to a visualization to provide a label or description.
Line	Straight line annotations can be added to a visualization to link labels to objects or to identify an object.
Rectangle	Rectangular annotations can be added to a visualization to identify rectangular areas.
Oval	Oval annotations can be added to a visualization to identify elliptical areas.
Polygon	Polygon annotations can be added to a visualization to identify areas bounded by a polygon.
Freehand	Freehand annotations can be added to a visualization to identify an area.

Table 11-1: Types of Surface Annotations

For more information on creating and using annotations, see [Chapter 5, “Adding Annotations”](#).

View Zoom

View Zoom allows you to zoom in or out on a specific area of the surface display area. To zoom in or out in View Zoom mode click Zoom  on the toolbar. For more information on working with View Zoom, see [“Zooming”](#) on page 70.

Canvas Zoom

Canvas Zoom allows you to increase or decrease the magnification of the entire display canvas (which may contain multiple views, depending on the layout) by a specified percentage. Canvas Zoom is available by selecting the pull-down percentage list from the top of the tool just under the Help menu. For more information on working with Canvas Zoom, see “[Zooming](#)” on page 70.

Extracting a Line Profile

To extract a line profile of part of your surface visualization in an iPlot window:

1. Click on the **Line Profile** icon on the iSurface window toolbar.
2. Use the mouse to position the jagged-edge line profile tool over the place which you wish your line profile to begin.
3. Drag to the ending point of your line profile.
4. The profile plot appears in an iPlot window.

Once a line profile has been drawn, it will remain until deleted. The line may be translated (or its endpoints moved individually) by switching back to the arrows. If it is translated or edited, the profile plot will automatically update.

If you dismiss your Plot Profile window and wish to have it back again, from your iSurface window, with the line selected, choose **Operations** → **Plot Profile** and the Plot Profile window will reappear.

iSurface Tool Operations

The iSurface tool provides the following operations:

Viewing a Histogram Plot

To display a histogram plot of your surface:

1. Select the surface.
2. Select **Operations** → **Histogram**.


For more information, see [“Plotting a Histogram”](#) on page 128.

Viewing Statistics

To display the Statistics dialog:

1. Select an object or a group of objects in the iTools window.
2. Select **Operations** → **Statistics**. The Statistics window displays the statistics for the selected object(s).

For more information, see [“Displaying Statistics”](#) on page 129.



Chapter 12

Working with Contours

This chapter describes how to work with contours in the iContour tool.

Introduction	256	Adding a Colorbar	271
Displaying Contours	257	Adding a Legend	272
Contour Properties	264	Adding Axes	273
Labeling Contours	266	Filtering a Contour	274
Changing the Contour Colors	268	Manipulating the Contour Display	276
Filling Contours	269	iContour Tool Operations	279

Introduction

The IDL iContour tool allows you interactive access to contour data. You may visualize contours and then modify and manipulate those contours in the ways that you need.

The IDL iContour tool displays your data as contours and allows you great flexibility in manipulating and visualizing these contours. The iContour tool can be used for irregular or regular grid data. Irregularly-grid data arranged as three fields (three one-dimensional vectors) are gridded by a Gridding Wizard if this data is imported into the iTool. Regular grid data arranged as a two-dimensional array is directly imported.

To use iContour from the IDL Command Line, type iContour. An empty iContour tool appears. You can then import contour data using any of several data import methods. For more information on importing contour data, see [Chapter 2, “Importing and Exporting Data”](#).

Note

For more information on accepted arguments and keywords, see “**ICONTOUR**” (*IDL Reference Guide*).

The iContour tool can be launched in the following ways:

- At the IDL Command Line without arguments or keywords
- At the IDL Command Line with arguments and keywords
- Through the **File** → **New** → **Visualization** → **iContour** menu option in the IDL Workbench
- Through the **File** → **New** → **iContour** menu option in an existing iTool

Displaying Contours

The iContour tool's primary purpose is to display contours, though the tool is capable of much more once the data is displayed. The iContour tool can display regular-grid data or irregular-grid data. Gridding is the creation of uniformly-spaced planar data from data points. These points may initially be irregular.

Displaying Regular-grid Data

Regular-grid data points are presented by two-dimensional arrays. The following example shows one way of importing and displaying this type of data into the iContour tool. The 248-by-248 two-dimensional array contained within the `convec.dat` binary file in the `examples/data` directory is imported into IDL with the `READ_BINARY` function. The iContour tool then displays this data as contours.

At the IDL Command Line, enter:

```
file = FILEPATH('convec.dat', SUBDIRECTORY = ['examples', 'data'])
data = READ_BINARY(file, DATA_DIMS = [248, 248])
iContour, data
```




Figure 12-1: Earth Convection Contours in the iContour Tool

Note

The `examples/data` directory of your IDL 7.0 distribution contains a text file named `index.txt`. This file lists all data files available in the example directory and also lists their dimensions and values.

Displaying Irregular-grid Data

Irregular-grid data points are presented by three one-dimensional vectors, usually known as fields. The following example shows one way of importing and displaying this type of data into the iContour tool. The three fields contained within the `irreg_grid1.txt` ASCII file in the `examples/data` directory is imported into IDL with the **File** → **Open** option in the iContour tool. This option uses the ASCII Template wizard to import the data, which is then gridded into contour data with the Gridding Wizard. The iContour tool then displays this data as contours.

1. At the IDL Command Line, enter:

ICONTOUR

2. Select **File** → **Open** from the pulldown menus of the empty iContour tool. The Open dialog will appear.
3. Use the Open dialog to find and select the `irreg_grid1.txt` file in the `example/data` directory. The ASCII Template wizard will appear.

The `irreg_grid1` file contains three columns of data points. These columns represent the x-locations, y-locations, and the elevation (respectively) of this data. These columns are specified as three fields (vectors) of data with the ASCII Template wizard.

4. Click **Next** on the first and second step of the wizard, then click **Finish** on the third (last) step of the wizard. The **IDL iTools Create Visualization** dialog will appear.




Figure 12-2: The iTools Create Visualization Dialog

The **IDL iTools Create Visualization** dialog contains the following choices:

- Launch the gridding wizard
 - Select a visualization and specify parameters
 - Do not create a visualization
5. Select the **Launch the gridding wizard** radio button, then click **OK**. The **IDL Gridding Wizard Step 1 of 3** dialog will appear.




Figure 12-3: The IDL Gridding Wizard Step 1 of 3

The Gridding Wizard allows you to specify the method of gridding while showing you the possible results for that method. The **IDL Gridding Wizard Step 1 of 3** dialog contains the following items:

- **Number of points entered**
- **X Coordinates** — X coordinate range
- **Y Coordinates** — Y coordinate range
- **Data values** — Data values are shown here
- **Spherical data checkbox** — Check to make data spherical
- **Coordinate diagram** — Shows coordinates of grid data

- **Show points checkbox** — Select to show all points (default is checked)
 - **Help** — Obtain help on this dialog
 - **Back** — Return to previous step
 - **Next** — Proceed to Step 2 of 3
 - **Cancel** — Dismiss the Gridding Wizard
6. In the Gridding Wizard Step 1, click **Next** to accept the interpolation of data values and locations. The **IDL Gridding Wizard Step 2 of 3** dialog will appear.



Figure 12-4: The IDL Gridding Wizard Step 2 of 3

The **IDL Gridding Wizard Step 2 of 3** dialog contains the following items:

- **X Coordinates** — modify dimension, start or end
- **Y Coordinates** — modify dimension, start or end
- **Coordinate diagram** — Shows coordinates of grid data
- **Show points checkbox** — Select to show all points (default is checked)
- **Help** — Obtain help on this dialog

- **Back** — Return to previous step
 - **Next** — Proceed to Step 3 of 3
 - **Cancel** — Dismiss the Gridding Wizard
7. At Step 2, click **Next** to accept the dimensions, start and spacing. The **IDL Gridding Wizard Step 3 of 3** dialog will appear.




Figure 12-5: The IDL Gridding Wizard Step 3 of 3

The **IDL Gridding Wizard Step 3 of 3** dialog contains the following items:

- **Choose gridding method** — Choose from pull-down list of methods
- **Preview** — Click to preview selected method and data
- **Auto preview** — Checkbox to turn auto preview on (default = off)
- **Statistics tab** — Shows data statistics
- **Options tab** — Set options for missing values, smoothing, weighting, and anisotropy between axes
- **Search tab** — Set options for using search ellipse
- **Coordinate diagram** — Shows coordinates of grid data

- **Show points checkbox** — Select to show all points (default = checked)
 - **Help** — Obtain help on this dialog
 - **Back** — Return to previous step
 - **Finish** — Dismiss the Gridding Wizard with data gridded
 - **Cancel** — Dismiss the Gridding Wizard
8. At Step 3, select **Inverse Distance** as the gridding method and click **Finish** to display the surface.
 9. The resulting contours are displayed in the iContour tool.




Figure 12-6: Irregular-grid Elevation Contours in the iContour Tool

Contour Properties

The iContour window is a self-contained contour display and manipulation device. You can import and export contour data, and modify and manipulate contours. For more information on the basic iContour interface and its layout, see [Appendix A, “iTools Interface Reference”](#).

With the contour selected, the **Edit** → **Properties...** option allows access to the contour property sheet. You can change many contour properties through this sheet.




Figure 12-7: Contour Property Sheet

The following examples show how to modify some contour properties. These examples are performed on the contours imported by using the following steps:

1. At the IDL Command Line, enter:

```
ICONTOUR
```

2. Select **File** → **Open** from the pulldown menus of the empty iContour tool. The Open dialog will appear.

3. Use the Open dialog to find and select the `convect.dat` file in the `example/data` directory. The Binary Template wizard will appear.
4. In the Binary Template dialog, click **New Field**, and enter the following information in the New Field dialog:
 - **Field name:** `data` (or a name of your choosing)
 - **Type:** `byte`
 - **Number of dimensions:** 2
 - **1st dimension Size:** 248
 - **2nd dimension Size:** 248
5. Click **OK** to close the New Field dialog and the Binary Template dialog, and the contours are displayed in the tool.




Figure 12-8: Earth Convection Contours in the iContour Tool

Labeling Contours

Each contour level line has its own properties. You can access these properties through **Contour level properties** in the contour property sheet by clicking **Contour level properties**, clicking on the arrow button, and then clicking **Edit...** The Contour Levels property sheet will appear.

	All levels	Level 1	Level 2	Level 3
Value		0	10	20
Color	(0,0,0)	(0,0,0)	(0,0,0)	(0,0,0)
Line style				
Line thickness	1	1	1	1
Label	None	None	None	None
Label interval	0.4	0.4	0.4	0.4
No label gaps	False	False	False	False
Use label color	False	False	False	False
Label color	(0,0,0)	(0,0,0)	(0,0,0)	(0,0,0)
Symbol label	No symbol	No symbol	No symbol	No symbol
Symbol size	0.1	0.1	0.1	0.1
Text label				
Tick format code				
Tick format	None	None	None	None
Text font	Helvetica	Helvetica	Helvetica	Helvetica
Text style	Normal	Normal	Normal	Normal
Text font size	9	9	9	9

OK

Figure 12-9: Contour Levels Property Sheet

The first column of the Contour Levels property sheet contains the property values for all the levels. In this column, change the **Label** setting from None to Value. The value of each contour line appears as labels in the iContour display.




Figure 12-10: Labelled Contour Levels

Changing the Contour Colors

The columns after the first one are for each individual contour level. In each level column, change the Color setting from black to a different color making sure to use a different color for each level. When a level color is changed in the property sheet, that level is updated in the iContour display.

The resulting display contains a different color contour for each level.




Figure 12-11: Color Contour Levels

After changing the colors of each level, click **OK** in the Contour Levels property sheet. The Contour Labels property sheet closes.

Filling Contours

The Fill contours setting in the original contour property sheet controls whether the contour levels are filled or not. Change the **Fill contours** setting to True.

Note

You must also change the **Use palette color** setting to True as well before colors can be used. After that, you can choose or set your own color scheme from the **Levels Color Table** → **Edit color table** function.

The contour colors are now more distinctive.




Figure 12-12: Filled Contour Levels Using the Predefined Blue Waves Scheme

Even more detail can be added by increasing the number of levels in the contour display. Change the **Number of levels** from 6 to 20.

The color set for each of the original seven levels is repeated every set of seven within the 20 new levels.




Figure 12-13: 20 Filled Contour Levels Reset at 20 Levels

Adding a Colorbar

You can add a colorbar to your visualized contour which will show on a color scale the minimum to maximum values of data in the visualization. To add a colorbar, click on the contour data and then from the iContour window, select **Insert** → **Colorbar**. A colorbar will be placed in the visualization window.

Note

Be sure that the **Use palette color** setting in the Visualization Browser is `True` so that colors can be used. After that, you can choose or set your own color scheme from the **Levels Color Table** → **Edit color table** function.

This colorbar can be resized and moved around the data space. You can also double-click on the colorbar to invoke the Visualization Browser which will allow you to change the values for the colorbar and edit color tables. For more information on the colorbar, see “[Colorbar](#)” on page 477.

Adding a Legend

You can add a legend to your contour which shows the levels of the contour in their increments. To add a legend, select **Insert** → **New Legend** from the iContour tool window.




Figure 12-14: A Contour With Legend Added Showing Levels

Once you have placed a legend on your contour, you can edit the legend settings such as the title and level increments as well as the color options on the legend. Double-clicking on the legend itself will show you the Visualization Browser. For more information on the options available, see [“Legend Properties”](#) on page 524.

Adding Axes

You can also add axes to your contour as visual aids for reading contour data. Although axes are added to two- and three-dimensional contour data there are advantages to adding additional axes. For example in the figure which follows, additional axes have been added in order to create a box-style contour showing the tick marks and increments on all sides of the image. You can add X, Y and Z axes depending on your contour and needs. To insert axes, select **Insert** → **Axis** and then select **X Axis**, **Y Axis**, or **Z Axis** or from the Visualization Browser, select the **Axes** group and then set **Style** to **Box Axes**.




Figure 12-15: A Contour With Axes Added and Altered in Box-Style

Once you have placed an axis on your contour you can edit the axis settings by changing the title and increments as well as the color options on the axis. Double-clicking on the axis itself will show you the Visualization Browser.

Filtering a Contour

The iContour tool allows you to modify your contour data in the following ways:

Contour Smoothing

Within the iContour tool, contours can also be smoothed to refine edges or compensate for random noise in the data. To smooth your data from the iContour window, select **Operations** → **Filter** → **Smooth**.




Figure 12-16: Brain MRI Data (left) and Smoothed Data (right)

Note

The previous figure shows brain MRI data taken from the IDL `examples\data` directory in a file named `mr_brain.dcm`.

Note

The window's default size is three, however this can be changed via the operations browser. For more information on smoothing properties, see [“Smooth Properties”](#) on page 401.

Contour Convolution

You can also use iContour convolution feature by selecting **Operations** → **Filter** → **Convolution**. By selecting this, the **Convolution Editor** appears.

From this dialog, you can select the desired convolution type from a drop-down list or you may manipulate the columns and rows and scale factor and details manually. For more details on the convolution filter, see [“Convolution Filter”](#) on page 124.




Figure 12-17: Brain MRI Data (left) and Convolved (right) Using Gaussian Convolution

For more information on convolution properties, see [“Convolution Properties”](#) on page 398.

Manipulating the Contour Display

The iContour tool allows you many options to manipulate your existing plot displays. Once you have visualized your contours, you may rotate, flip, translate, scale, and zoom as well as modify contour properties, scroll, and select contour ROIs. The following options are available for manipulating contours.

Translating

Translation moves an object or group of objects in a specific direction. When an object is selected, a bounding box appears around the object. For information on translating objects, see [“Translation”](#) on page 64.

View Zoom

View Zoom allows you to zoom in or out on a specific area of the contour display area. To zoom in or out in View Zoom mode click Zoom  on the toolbar. For more information on working with View Zoom, see [“Zooming”](#) on page 70.

Flipping a Contour

You can flip your contour within the data space either horizontally or vertically. These operations flip the actual data associated with the contour. To flip your data, select **Operations** → **Flip** → **Flip Horizontal** or **Operations** → **Flip** → **Flip Vertical**.

Canvas Zoom

Canvas Zoom allows you to increase or decrease the magnification of the entire display canvas (which may contain multiple views, depending on the layout) by a specified percentage. Canvas Zoom is available by selecting the pull-down percentage list from the top of the tool just under the Help menu. For more information on working with Canvas Zoom, see [“Zooming”](#) on page 70.

Scaling a Contour Display

The iContour tool allows you to scale your contour data by selecting **Operations** → **Transform** → **Scale Data**. You can scale your data by a factor which you provide in the **Scale Factor** dialog.




Figure 12-18: Setting the Contour Scale Factor

Once you have set the scale factor, select **OK** and the scaling takes place.

You may zoom in and out from your plot using either the Zoom In and Zoom Out buttons on the iPlot toolbar, or by selecting **Window** → **Zoom In** or **Window** → **Zoom Out**.

Adding Annotations

The following types of annotations can be added to iContour displays:

Plot Annotation Type	Description
Text	Single lines or multiple lines of text can be added to a visualization to provide a label or description.
Line	Straight line annotations can be added to a visualization to link labels to objects or to identify an object.
Rectangle	Rectangular annotations can be added to a visualization to identify rectangular areas.
Oval	Oval annotations can be added to a visualization to identify oval areas.

Table 12-1: Types of Contour Annotations

Plot Annotation Type	Description
Polygon	Polygon annotations can be added to a visualization to identify areas bounded by a polygon.
Freehand	Freehand annotations can be added to a visualization to identify an area.

Table 12-1: Types of Contour Annotations (Continued)

For more information on creating and using annotations, see [Chapter 5, “Adding Annotations”](#).

iContour Tool Operations


The iContour tool provides the following operations:

Viewing a Histogram

A density histogram is a density plot showing the distribution of data values. The X-axis represents data values and the Y-axis represents density or frequency. Another type of histogram is a style plot histogram. To view a density histogram of contour data, use the iTool's histogram feature by selecting **Operations** → **Histogram**. For information on histogram creation, see [“Plotting a Histogram”](#) on page 128.

Viewing Statistics

To view statistics for contour data, use the iTool's statistics feature by selecting **Operations** → **Statistics**. For information on viewing statistics, see [“Displaying Statistics”](#) on page 129.



Chapter 13

Working with Plots

This chapter describes plotting tasks and the iPlot tool.

Introduction	282	Adding Legends	289
Displaying Two-Dimensional Plots	283	Adding a Colorbar	291
Displaying Three-Dimensional Plots	284	Adding Error Bars	292
Displaying Polar Plots	285	Curve Fitting	294
Overplotting	286	Filtering a Plot	297
Plot Properties	288	Manipulating the Plot Display	299
Adding Error Bars	292	iPlot Tool Operations	301

Introduction

The IDL iPlot tool displays your data in plot form. The iPlot tool then allows you great flexibility in manipulating and visualizing plot data. iPlot can be used for any type of two- or three-dimensional plot, including scatter plots, line plots, polar plots, and histogram plots. To use iPlot, from the IDL Command Line, type `iPlot`. An empty iPlot tool appears. You can then import plot data using any of several data import methods. For more information importing plot data see [Chapter 2, “Importing and Exporting Data”](#).

Note

For more information on accepted arguments, see “**IPLLOT**” (*IDL Reference Guide*).

The iPlot tool can be launched in many different ways:

- At the IDL Command Line without arguments or keywords
- At the IDL Command Line with arguments or keywords
- Through the **File** → **New** → **Visualization** → **iPlot** menu option in the IDL Workbench
- Through the **File** → **New** → **iPlot** menu option in an iTool

Displaying Two-Dimensional Plots

The iPlot tool's primary design is to display plot data, though the tool is capable of much more once the data is plotted. The iPlot tool can display multiple types of plots and allows you to manipulate and edit the displays.

The first task is to display plot data. Here is a simple example of how to display a plot.

At the IDL command line, enter:

```
iPlot, RANDOMU(seed, 20)
```




Figure 13-1: A Simple 2D Plot Using the iPlot Tool

Note

The `examples/data` directory of your IDL 7.0 distribution contains a text file named `index.txt`. This file lists all data files available in the example directory and also lists their dimensions and values.

Displaying Three-Dimensional Plots

iPlot can display multiple types of plots and allows you to manipulate and edit the displays. You can also display three-dimensional plots. Here is a simple example of how to display a 3D plot.

At the IDL command line, enter:

```
iPlot, FINDGEN(20), FINDGEN(20), RANDOMU(seed, 20)
```




Figure 13-2: A Simple 3D Plot Using the iPlot Tool

Displaying Polar Plots

iPlot can display multiple types of plots and allows you to manipulate and edit the displays. You can also display polar plots. Here is a simple example of how to display a polar plot.

At the IDL command line, enter:

```
iPlot, FINDGEN(20), FINDGEN(20), /POLAR
```




Figure 13-3: A Simple Polar Plot Using the iPlot Tool

Note

The examples/data directory of your IDL 7.0 distribution contains a text file named `index.txt`. This file lists all data files available in the example directory and also lists their dimensions and values.

Overplotting

Once you have plotted data, you may overplot new plot data in the original iPlot window. Overplotting is the process of plotting new data over the top of original data or datasets for the purpose of analyzing or comparing more than one dataset at a time.

For example, in order to overplot cosine data onto a plot of sine wave data follow these steps:

1. Create a variable named “theory” to contain sine wave data to be plotted:

```
theory = SIN(2.0*FINDGEN(200)*!PI/25.0)*EXP(-0.02*FINDGEN(200))
```

2. Plot theory using iPlot:

```
iPlot, theory
```




Figure 13-4: Sin Wave Data Plotted

3. Create a variable named “newtheory” which stores cosine data to be used for overplotting:

```
newtheory = COS(2.0*FINDGEN(200)*!PI/25.0)*EXP(-0.02*FINDGEN(200))
```

4. Now overplot the new cosine data onto your original plot:

```
iPlot, newtheory, /OVERPLOT
```




Figure 13-5: Cosine Data Overplotted on Sine Data

Plot Properties

The iPlot window is a self-contained plot display and manipulation device. You can import and export plot data, and modify and manipulate plot data. For more information on the basic iPlot interface and its layout, see [Appendix A, “iTools Interface Reference”](#).

Modifying Properties

By selecting **Edit** → **Properties** from the iPlot tool, you may modify your plot properties. You may modify your plot’s name, description, fill type and fill color, opacity as well as the show/hide properties and the line color, style and thickness. For more information on editing properties in the iTools, see [Appendix D, “Visualization Properties”](#).

Adding Legends

A legend is text that describes aspects of a visualization. For example, a legend might show the plot line or plot points. If multiple plots are present the legend may show which colors and linestyles represent which plots. An inserted legend will include items selected at the time of insertion. If no specific dataset is selected, the legend will include all datasets in the plot.

To add a legend to your plot, select **Insert** → **New Legend**.




Figure 13-6: A Simple Sine Plot with Default Legend Added

You can add new information to your existing legend, or you can also use the **Insert** → **Legend** option can be used over again to add more legends. For example, in the `theory` plot with `newtheory` overplot displayed in the previous section, you can add a legend for each plot:

1. Select the `newtheory` plot by clicking once on the line.
2. Select **Insert** → **New Legend**. A new legend appears on top of the previous legend (this new legend can be selected and repositioned).




Figure 13-7: Plot and Overplot in iPlot with Legend Added for Each

You can double-click on the legend to bring up a property sheet to alter its settings. Through the property sheet, you can also access the Visualization Browser, which can be used to navigate through other legends and objects within the visualization. In the previous example the names of the legends have been altered to reflect the data names. For more information on editing settings in the Visualization Browsers, see [“The Visualization Browser”](#) on page 427.

Adding a Colorbar

If you have added vertex coloring to your plot visualization, you can add a colorbar which will show on a color scale the minimum to maximum values of data in the visualization.

To add a colorbar,

1. Click on the plot data.
2. From the iPlot window, select **Insert** → **Colorbar**.
3. A colorbar will be placed in the visualization window.

This colorbar can be resized and moved around the data space. You can also double-click on the colorbar to invoke the Visualization Browser which will allow you to change the values for the colorbar. For more information on the colorbar, see [“Colorbar”](#) on page 477.

Adding Error Bars

Error bars are used to show uncertainty in data values. These uncertainties may be caused by measurement errors or instrument noise, and are usually specified in terms of standard deviations away from the data value.

For example, to create a 2D plot with asymmetric error bars on the X and Y axes, follow these steps:

1. To set asymmetric error bars for X and Y with X bars initially hidden, enter:

```
err = FLTARR(2,10)
err[0, *] = FINDGEN(10)/10.
err[1, *] = FLTARR(10) + 0.5
```

2. Plot the error bars in the iPlot window:

```
iPlot, FINDGEN(10), COLOR = [255, 0, 255], $
  ERRORBAR_COLOR = [255, 0, 0], $
  ERRORBAR_CAPSIZE = 0.25, X_ERRORBARS = 0, $
  XERROR = err, YERROR = err
```




Figure 13-8: 2D Plot with Error Bars

Also, to create a 3D plot with asymmetric error bars on the X, Y and Z axes:

1. To set asymmetric error bars for a 3D plot, enter:

```
nVerts = 30
x = FINDGEN(nVerts)/10.
y = (SIN(x*2) + 1.)*25.
z = x
err = FLTARR(2, nVerts)
err[0, *] = RANDOMU(seed, nVerts)
err[1, *] = RANDOMU(seed, nVerts)
```

2. Plot the error bars in the iPlot window with 3D plot and name the plot “3D Plot with Error Bars”:

```
iPlot, x, y, z, COLOR = [0, 0, 255], $
  THICK = 2, ERRORBAR_COLOR = [255, 0, 0], $
  XERROR = err/2., YERROR = err*5., ZERROR = err, $
  NAME = '3D Plot with Error Bars'
```




Figure 13-9: 3D Plot with Error Bars and Name

For more information on error-bar properties, see [“Plot”](#) on page 441.

Curve Fitting

Curve fitting is the process of finding various ways to fit a curve to a series of data points which best represents all points. More specifically, since data, such as plot data, is often given as values along a continuum, you may wish at times to give estimates at points between values. Curve fitting allows you to find intermediate estimates for these values.

Note

For both 2D and 3D plots, the curve fitting operation is performed on the X versus Y plot dimensions.

For example, to fit a curve to the damped sine plot we have already created:

1. Select **Operations** → **Filter** → **Curve Fitting**.
2. The Curve Fitting dialog appears.




Figure 13-10: The Curve Fit Dialog with Curve Fitting Model Choices

The Curve Fitting dialog contains the following fields:

- **Curve fitting model** — used to select the type of model used to try to fit a curve to the data.
- **Initial parameters and results** — used to specify the initial values of the parameters of the model used to fit a curve to the data and to display the resulting values of these parameters for the model selected in the **Curve fitting model** drop-down list. The initial values are specified in the text boxes on the left side and the results are shown in the labels on the right side.
- **Equation of the model** — shows the equation of the model used to try to fit a curve to the data. This model is selected from the **Curve fitting model**.
- **Display of resulting fit** — graphically shows how well the model specified by the **Curve fitting model** drop-down menu and the **Initial parameters** text boxes fits the data.
- **Chi-square value** — shows the resulting chi-square value, which is a measure of goodness-of-fit.

You can use this dialog to determine what type of model would best fit your data by changing the **Curve fitting model** drop-down menu setting and the **Initial parameters** text boxes values.

3. Select the desired curve fit from the **Curve fitting model** drop-down list. You can also set initial parameters if desired.




Figure 13-11: A Quintic Curve Fit to a Sin Wave Plot

The new curve created by the curve fitting operation is added to the Data Manager.

Filtering a Plot

The iPlot tool allows you to modify your plot data in the following ways:

Plot Smoothing

Within the iPlot tool, plots can also be smoothed to soften edges or compensate for random noise in the plot. To smooth your plot from the iPlot window, select **Operations → Filter → Smooth**.




Figure 13-12: Damped Sine Plotted Data (left) and Smoothed Data (right)

Note

The example shown in the previous figures is taken from example data available in the `examples\data` directory of your IDL installation. The data is contained in a file called `damp_sn.dat`.

Note

The window's default size is three, however this can be changed via the operations browser. For more information on smoothing properties, see [“Smooth Properties”](#) on page 401.

Plot Convolution

You can also use the iPlot convolution feature by selecting **Operations** → **Filter** → **Convolution**. By selecting this, the **Convolution Editor** appears. From this dialog, you can select the desired convolution type from a drop-down list or you can manually manipulate the columns, rows, scale factor, and details.

For more information on convolution properties, see “[Convolution Properties](#)” on page 398.

Plot Median

The median filter replaces each point with the *median* (a value in an ordered set of values with an equal number of values above and below it) of the one- or two-dimensional neighborhood of a given width.

To apply the smooth filter to an image:

1. Select the plot.
2. Select **Operations** → **Filter** → **Median**.

For more details on the median filter, see “[Median Filter](#)” on page 123.

Manipulating the Plot Display

The iPlot tool allows you many options to manipulate your existing plot displays. Once you have visualized your plot data, you may rotate, flip, translate, scale, and zoom as well as modify plot properties, scroll, and select plot ROIs. The following options are available for manipulating plots.

Translating

Translation moves an object or group of objects in a specific direction. When an object is selected, a bounding box appears around the object. For information on translating objects, see [“Translation”](#) on page 64.

Adding Annotations

The following types of annotations can be added to iPlot displays:

Plot Annotation Type	Description
Text	Single lines or multiple lines of text can be added to a visualization to provide a label or description.
Line	Straight line annotations can be added to a visualization to link labels to objects or to identify an object.
Rectangle	Rectangular annotations can be added to a visualization to identify rectangular areas.
Oval	Oval annotations can be added to a visualization to identify elliptical areas.
Polygon	Polygon annotations can be added to a visualization to identify areas bounded by a multi-sided polygon.
Freehand	Freehand annotations can be added to a visualization to identify an area.

Table 13-1: Types of Plot Annotations

For more information on creating and using annotations, see [Chapter 5, “Adding Annotations”](#).

View Zoom

View Zoom allows you to zoom in or out on a specific area of the plot display area. To zoom in or out in View Zoom mode click Zoom  on the toolbar. For more information on working with View Zoom, see “[Zooming](#)” on page 70.

Canvas Zoom

Canvas Zoom allows you to increase or decrease the magnification of the entire display canvas (which may contain multiple views, depending on the layout) by a specified percentage. Canvas Zoom is available by selecting the pull-down percentage list from the top of the tool just under the Help menu. For more information on working with Canvas Zoom, see “[Zooming](#)” on page 70.

Selecting the Data Range

In a two-dimensional plot, your data range can be manipulated in several ways. First, enter into the Data Range tool mode by clicking on the Data Range button  on the toolbar. You can then manipulate your data range in the following ways:

- Clicking and dragging a selection box within the view. The selected range becomes the new data range.
- Panning in one direction or another along a single axis by clicking on the arrow manipulators.
- Zooming in or out by clicking on one of the plus or minus symbols. When isotropic scaling is in effect (the default for the iPlot tool), these symbols appear at the axis origin, and will impact both the X and Y ranges simultaneously.

Note

Plots are clipped to fit within newly selected data ranges.

iPlot Tool Operations

Many operations are available in the iPlot tool. Once you have visualized your plot data, you can scale and filter as well as creating a histogram or viewing statistics for your plot. The following operations are available for plots.

Scaling a Plot Display

iPlot allows you to scale your plotted data by selecting **Operations** → **Transform** → **Scale Data**. You can scale your data by a factor which you provide in the **Scale Factor** dialog.




Figure 13-13: Setting the Plot Scale Factor


Once you have set the scale factor, select **OK** and the scaling takes place.

Viewing a Histogram

A density histogram is a plot consisting of either horizontal or vertical bars. The widths or heights of these bars represent data values. Another type of histogram is a style plot histogram which plots different data sets side-by-side using differently styled points or bars to represent the data. To view a density histogram of plot data, use the iTool's histogram feature by selecting **Operations** → **Histogram**. For information on histogram creation, see [“Plotting a Histogram”](#) on page 128.

Viewing Statistics

To view statistics for plot data, use the iTool's statistics feature by selecting **Operations** → **Statistics**. For information on viewing statistics, see [“Displaying Statistics”](#) on page 129.



Chapter 14

Working with Volumes

This chapter describes how to use the iVolume tool.

Introduction	304	Resampling Volumes	314
Displaying Volumes	305	Showing an Image Plane	315
Using the Volume Panel	309	Extracting an IsoSurface	316
Volume Properties	311	Extracting an Interval Volume	318
Adding a Colorbar	312	Manipulating the Volume Display	320
Adding Axes	313	iVolume Tool Operations	322

Introduction

The IDL iVolume tool displays your data in volume form. The iVolume tool then allows you great flexibility in manipulating and visualizing volume data. To use iVolume, from the IDL Command Line, type `iVolume`. An empty iVolume tool appears. You can then import volume data using any of several data import methods. For more information importing volume data see [Chapter 2, “Importing and Exporting Data”](#).

Note

For more information on accepted arguments, see “[IVOLUME](#)” (*IDL Reference Guide*).

The iVolume tool can be launch in many different ways:

- At the IDL Command Line without arguments or keywords
- At the IDL Command Line with arguments or keywords
- Through the **File** → **New** → **Visualization** → **iVolume** menu option in the IDL Workbench
- Through the **File** → **New** → **iVolume** menu option in an iTool

Displaying Volumes

The iVolume tool's primary purpose is to visualize volume data, though the tool is capable of much more once the data is displayed. The iVolume tool also allows you to manipulate and edit the displays. The first task is to display the volume data.

Before displaying, volume data must be loaded into the tool. Here is a simple example of one way to load in some data.

At the IDL command line, enter:

```
file = FILEPATH('head.dat', $  
    SUBDIRECTORY = ['examples', 'data'])  
data = READ_BINARY(file, DATA_DIMS = [80, 100, 57])  
IVOLUME, data
```

Note

The `examples/data` directory of your IDL 7.0 distribution contains a text file named `index.txt`. This file lists all data files available in the example directory and also lists their dimensions and values.

Note

IDL converts and stores volume data in a BYTE array. Thus, all incoming volume data is converted to BYTE type. This could alter the volume data values if the incoming data cannot accurately be stored as BYTE data.

Multi-Channel Volumes

The data in the previous example is a single-channel volume which is volume data specified in a single parameter. This is the simplest and most common way to display volume data. The iVolume tool also supports two-channel and four-channel volume rendering. Two-channel rendering allows you to combine or blend two volume arrays together. Four-channel rendering is useful when your volume data is composed of a volume array for each of the red, green, blue, and alpha display channels. Note that the dimensions of all the volume arrays used in multi-channel volume rendering must be the same.

In the following example, the second volume array of a two-channel volume is used as a mask to cut out a portion of the volume to create a hole. With the `head.dat` data already loaded from the `examples/data` directory, a mask volume is created and displays the result:

```
mask = BYTARR(80, 100, 57, /NOZERO)
mask[*] = 255
mask[30:50, *, 20:30] = 0
IVOLUME, data, mask
```

A rectangular hole through the middle of the head is created, making portions of the inside more visible.

The following is an example of a four-channel volume:

```
red = BYTARR(20,20,20, /NOZERO)
green = BYTARR(20,20,20, /NOZERO)
blue = BYTARR(20,20,20, /NOZERO)
alpha = BYTARR(20,20,20, /NOZERO)

red[10:*,*,*]=255
green[*,10:*,*]=255
blue[*,*,10:*=255
alpha[*] = 128
IVOLUME, red, green, blue, alpha
```

Rendering Volumes

Volume data does not automatically appear in the tool window since volume rendering can be a time consuming operation. To render the volume, click the **Render** button on the tool. Auto render is available but not set by default since it can slow down your iTool session if you have simultaneous operations.

Note

Volume data is only rendered if the volume data space is selected. Thus, if you have multiple volumes in your data space, auto render must be turned on in order to render both simultaneously.

The data loaded earlier can be displayed by clicking the **Render** button.




Figure 14-1: Rendered MRI Head Volume Data

Rendering Quality

The volume can be rendered in two quality modes:

- **Low** — Done with a stack of 2D texture-mapped semi-transparent polygons. The polygons are oriented so that the flat sides face the viewer as directly as possible. On most systems, Low-quality mode renders faster than High-quality mode, but not as accurately.
- **High** — Done with the IDLgrVolume ray-casting volume renderer. This quality mode is CPU-intensive and will usually take much longer than the Low-quality mode.

Extents

Since the volume is not always rendered, iVolume draws volume extents to help you locate and select the volume. You can select the volume by selecting on the extents, without rendering the volume. By default, iVolume draws a translucent solid cube with internal extents. You can also select a wire frame, or no extents within the visualization browser.

Note

Use caution when turning off extents. If extents are turned off and auto render is also off, you may need to use the Visualization Browser to select the volume again.

Using the Volume Panel

The volume panel appears to the right of the visualization window of the iVolume tool. This panel allows you to render and manipulate rendering properties. The components and functions of the volume panel are discussed in the following figure and list.




Figure 14-2: The Volume Panel

- **Name** — The volume object's name (if any).
- **Data Channels** — The volume's data channels.
- **Render** — This button will render the volume data.
- **Auto-Render** — Select this checkbox to enable auto-rendering.
- **Quality** — Pull-down menu to select desired volume rendering quality. Select Low (textures) or High (volume).

- **Boundary** — Pull-down menu to select desired volume data space boundaries. Select none, wire frame, or solid walls.
- **Render Step** — Enter desired order for rendering here (if any).

Volume Properties

The iVolume window is a self-contained volume display and manipulation device. You can import and export volume data, and modify and manipulate volume data. For more information on the basic iVolume interface and its layout, see [Appendix A, “iTools Interface Reference”](#).

Modifying Properties

By selecting **Edit** → **Properties** from the iVolume tool, you can modify your volume properties. You may modify your volume’s name, description as well as the show/hide properties and the line color, style, and thickness. For more information on editing properties in the iTools, see [Appendix D, “Visualization Properties”](#).

Adding a Colorbar

You can add colorbars to your visualized volume which will show on a color scale the minimum to maximum values of data in the visualization. To add a colorbar, click on the volume visualization and then from the iVolume window, select **Insert** → **Colorbar**. Colorbars showing RGB values as well as opacity values will be placed in the visualization window. These colorbars can be resized and moved around the data space. You can also double-click on the colorbars to invoke the Visualization Browser which will allow you to change the properties for that colorbar.




Figure 14-3: Rendered Volume with Colorbars Added

Note

Color and opacity data can be manipulated by selecting **Window** → **Visualization Browser...** from the iVolume window and then selecting **Edit color/opacity table** under **Color & opacity table**.

Adding Axes

By default, volumes are displayed with X, Y, and Z axes. The display of these axes is controlled by property sheets for the axes container and for individual axes (see [“Axes”](#) on page 485). Additional X, Y, or Z axes can be added to a volume visualization to make it easier to identify volume characteristics.

To add an axis to your volume visualization:

1. Select the volume.
2. Select **Insert** → **Axis**.
3. Choose from the following options:
 - **X axis**
 - **Y axis**
 - **Z axis**

Use the mouse to position the new axis and double-click the axis to display the axis property sheet.

For more information on adding axes, see [“Additional Axes”](#) on page 84.

Resampling Volumes

Resampling re-imports the selected volume data using parameters specified in the Resample properties. Resampling parameters include factors for adjusting the X, Y, or Z dimensions of the data, as well as the interpolation method to be used.

To resample volume data:

1. Select one or more volumes in the iVolume window for resampling.
2. If necessary, use the Operations Browser to set the desired parameters through the Resample properties. See [“Resample Properties”](#) on page 406 for details.
3. Select **Operation** → **Transform** → **Resample**.




Figure 14-4: Resampled and Rendered Volume

Showing an Image Plane

An image plane is a visualization of a slice of the volume. An image plane can be dragged and rotated within the volume. To show an image plane for a portion of volume data, first be sure your volume is selected and then choose **Operations** → **Volume** → **Image Plane**. An image plane appears showing a cross-section of your volume data. You can change the orientation of an image plane by double-clicking on the image plane to bring up the property browser. You can also click on the edge of the plane and move it to various other points in the volume data.




Figure 14-5: Image Plane of a Rendered Volume

Viewing the Image Plane in iImage

Image plane data is available in Data Manager and can be utilized in the iImage tool for closer image analysis. The image plane image data is always a four-channel RGBA truecolor image. To view your image plane in iImage, from the iVolume tool select **Operations** → **Image Plane** → **Launch iImage**.

Extracting an IsoSurface

An isosurface is a set of polygons drawn in the volume to represent a surface that has a specific constant value (the isovalue). An isosurface cannot be translated, scaled, or rotated relative to the volume but does move with the volume.

To create an isosurface, select **Operations** → **Volume** → **IsoSurface** and iVolume displays a dialog allowing you to specify the isovalue. If the volume is multi channel, you can select a channel and set its isovalue.




Figure 14-6: Isosurface Value Selector for iVolume

You will then create an isosurface for that channel by selecting **OK**.




Figure 14-7: Isosurfaced Rendered Volume

Note

Isosurfaces often contain a large number of polygons, which may degrade iVolume's display performance. When selecting the isovalue, you can also specify a decimation percentage to reduce the number of polygons in the resulting isosurface. This decimation step requires additional time, but the resulting isosurface will contain fewer triangles and will draw faster.

Consider adding a light to improve the isosurface display. Select **Insert** → **Light** to add a light.

Extracting an Interval Volume

An interval volume is a set of tetrahedra that span a space between two isovalues within a volume. Since a tetrahedral mesh is a solid, iVolume displays the outer surface of the mesh as a set of polygons. This surface cannot be translated, scaled, or rotated relative to the volume but does move with the volume.

To create an interval volume, select **Operations** → **Volume** → **Interval Volume**, and a dialog appears allowing you to set two isovalues.




Figure 14-8: Interval Volume Value Selector for iVolume

If the volume is multi channel, you can select a channel for setting the isovalues and then create an interval volume for that channel by selecting **OK**.




Figure 14-9: Interval Volume

Note

Vertex colors are not persevered during decimation.

Note

Interval volume surfaces often contain a large number of polygons, which can degrade iVolume's display performance. When selecting isovalues, you can specify a decimation percentage to reduce the number of polygons in the resulting surface. This decimation step requires additional time, but the resulting surface will contain fewer triangles and will draw faster.

Manipulating the Volume Display

The iVolume tool allows you many options to manipulate your existing volume displays. Once you have visualized your volume data, you may rotate, translate, scroll, and zoom as well as modify volume properties. The following options are available for manipulating volumes.

Rotating a Volume

Rotating makes it possible to rotate the volume within the visualization without affecting the rest of the data space (graphical objects and axes). To rotate your volume, from the toolbar on the iVolume window, select the **Rotate** button. For more information about rotating, see “[Rotation](#)” on page 115.

Scaling a Volume

It is possible to scale the data within a volume by a specified scale factor. To scale your volume, select **Operations** → **Transform** → **Scale Data**. For more information on scaling data, see “[Scaling](#)” on page 65.

View Zoom

View Zoom allows you to zoom in or out on a specific area of the volume display area. To zoom in or out in View Zoom mode click **Zoom**  on the toolbar. For more information on working with View Zoom, see “[Zooming](#)” on page 70.

Canvas Zoom

Canvas Zoom allows you to increase or decrease the magnification of the entire display canvas (which may contain multiple views, depending on the layout) by a specified percentage. Canvas Zoom is available by selecting the pull-down percentage list from the top of the tool just under the Help menu. For more information on working with Canvas Zoom, see “[Zooming](#)” on page 70.

Adding Annotations

Annotations can be added to label or describe volume visualizations displayed in the iVolume tool.

The following types of annotations can be added to iVolume displays:

Plot Annotation Type	Description
Text	Single lines or multiple lines of text can be added to a visualization to provide a label or description.
Line	Straight line annotations can be added to a visualization to link labels to objects or to identify an object.
Rectangle	Rectangular annotations can be added to a visualization to identify rectangular areas.
Oval	Oval annotations can be added to a visualization to identify circular areas.
Polygon	Polygon annotations can be added to a visualization to identify areas bounded by a multi-sided polygon.
Freehand	Freehand annotations can be added to a visualization to identify an area.

Table 14-1: Types of Volume Annotations

For more information on creating and using annotations, see [Chapter 5, “Adding Annotations”](#).

iVolume Tool Operations

Many operations are available in the iVolume tool. Once you have visualized your volume data, you can scale and filter as well as creating a histogram or viewing statistics for your volume. The following operations are available for volumes.

Viewing a Histogram

A density histogram is a plot consisting of either horizontal or vertical bars. The widths or heights of these bars represent data values. Another type of histogram is a style plot histogram which plots different data sets side-by-side using differently styled points or bars to represent the data. To view a density histogram of volume data, use the iTool's histogram feature by selecting **Operations** → **Histogram**. For information on histogram creation, see [“Plotting a Histogram”](#) on page 128.

Viewing Statistics

To view statistics for volume data, use the iTool's statistics feature by selecting **Operations** → **Statistics**. For information on viewing statistics, see [“Displaying Statistics”](#) on page 129.

Smoothing a Volume

Within the iVolume tool, plots can also be smoothed to soften edges or compensate for random noise in the volume.

To apply the smooth filter to a volume:


1. Select the volume.
2. Select **Operations** → **Filter** → **Smooth**.

Opening an Image Stack

iVolume allows you to open a group of images as an image stack within the tool. To open images as an image stack select **File** → **Open Image Stack...** From the dialog, select the images you wish to open using either **Shift** + right click if images are consecutive or **Ctrl** + right click if nonconsecutive.

Note

Images are opened and stacked in the order they are named and not in the order of selection. In other words file names are opened alphanumerically. The only way to control the order of opening files is through the naming or renaming of files.



Chapter 15

Working with Maps

This chapter describes how to use the map iTool.

Introduction	326	Registering an Image	335
Displaying Maps	327	Displaying a Contour	342
Applying a Map Projection	328	Creating a Shape Visualization	343
Using the Map Panel	332	Inserting a Map Grid	344
Displaying an Image	334	Inserting an IDL Shapefile	345

Introduction

The IDL iMap tool displays image and contour data that are georeferenced and mapped to particular projections, as well as shapefile data. The iMap tool gives you great flexibility in manipulating and visualizing these data. To use iMap, from the IDL Command Line, type `iMap`. An empty iMap tool appears. You can then import image or contour data using any of several data import methods. For more information on importing data, see [Chapter 2, “Importing and Exporting Data”](#).

Note

For more information on accepted arguments and keywords, see “**IMAP**” (*IDL Reference Guide*).

The iMap tool can be launched in many different ways:

- At the IDL Command Line without arguments or keywords
- At the IDL Command Line with arguments or keywords
- Through the **File** → **New** → **Visualization** → **iMap** menu option in the IDL Workbench
- Through the **File** → **New** → **iMap** menu option in an iTool

Displaying Maps

The iMap tool's primary goal is to visualize map data, though the tool is capable of much more once the data is displayed. The iMap tool also allows you to manipulate and edit the displays. The first task is to display the map data.

Your options for calling the iMap tool are:

- At the IDL Command Line without arguments or keywords
- At the IDL Command Line with arguments or keywords

Note

Arguments and keywords are accepted at the IDL Command Line for the iMap tool, for more information on accepted arguments and keywords, see [“IMAP”](#) (*IDL Reference Guide*).

- Through the **File** → **New** → **Visualization** → **iMap** menu option in the IDL Workbench
- Through the **File** → **New** → **iMap** menu option in an iTool

You have two options for getting started with displaying a map. You can:

- Apply a map projection and then visualize data within it
- Visualize image or contour data and then apply a map projection to it

To get started with one of these options, see the following sections:

- [“Applying a Map Projection”](#) on page 328
- [“Displaying an Image”](#) on page 334
- [“Displaying a Contour”](#) on page 342

Applying a Map Projection

A *map projection* establishes the axis type and coordinate conversion mechanism for mapping points on the earth's surface, expressed in latitude and longitude, to points on a plane, according to one of several possible map projections.

You can apply a map projection before or after you import image or contour data into the iMap tool. To do so, select **Operations** → **Map Projection**. This command opens the Map Projection dialog, shown in [Figure 15-1](#).




Figure 15-1: The Map Projection Dialog

You can apply a map projection to another iTool as well. If you do, the tool will adapt to expose iMap functionality, including the iMap operations and the Map panel.

Table 15-1 shows the common projection properties.

Name	Description
Description	Description of the map projection
Show dialog	Show this dialog before executing the Map Projection operation
Projection	Name of the map projection
Ellipsoid (datum)	Semimajor and -minor axes that define the ellipsoid
Semimajor axis	Length of the semimajor axis, in meters, for the reference ellipsoid
Semiminor axis	Length of the semiminor axis, in meters, for the reference ellipsoid
Center longitude (degrees)	Longitude in degrees of the projection's center
Center latitude (degrees)	Latitude in degrees of the projection's center
Longitude minimum (deg)	Minimum longitude to include in the projection, in degrees
Longitude maximum (deg)	Maximum longitude to include in the projection, in degrees
Latitude minimum (deg)	Minimum latitude to include in the projection, in degrees
Latitude maximum (deg)	Maximum latitude to include in the projection, in degrees
False easting (meters)	False easting to be added to each x-coordinate, in meters
False northing (meters)	False northing to be added to each y-coordinate, in meters

Table 15-1: Common Map Projection Properties

In addition to these properties, the following properties (Table 15-2) become available depending on the selected projection:

Name	Description
Height (meters)	Height above surface, in meters, for satellite projections
Hemisphere	Hemisphere for UTM and Polar projections
HOM azimuth angle (deg)	Hotine Oblique Mercator azimuth angle (degrees) east

Table 15-2: Properties for Selected Map Projections

Name	Description
HOM latitude 1 (deg)	Hotine Oblique Mercator latitude, in degrees, of the first point
HOM latitude 2 (deg)	Hotine Oblique Mercator latitude, in degrees, of the second point
HOM longitude 1 (deg)	Hotine Oblique Mercator longitude, in degrees, of the first point
HOM longitude 2 (deg)	Hotine Oblique Mercator longitude, in degrees, of the second point
IS longitudinal zones	Integerized Sinusoidal number of longitudinal zones
IS row justify flag	Integerized Sinusoidal flag that indicates what to do with rows with an odd number of columns. The following values are allowed: • 0 — Indicates the extra column is on the right of the projection y-axis • 1 — Indicates the extra column is on the left of the projection y-axis • 2 — Calculates an even number of columns
Mercator scale	Scale factor at the central meridian (for the Transverse Mercator projection) or the center of the projection (for the Hotine Oblique Mercator projection)
NAD27 Zone name (FIPS)	NAD27 State Plane Coordinate System Zone (FIPSZone)
NAD83 Zone name (FIPS)	NAD83 State Plane Coordinate System Zone (FIPSZone)
OEA horizontal shape m	Oblated equal area horizontal (<i>m</i>) shape parameter
OEA vertical shape n	Oblated equal area vertical (<i>n</i>) shape parameter
OEA rotation angle (deg)	Oblated equal area rotation angle, in degrees
SOM end-of-path flag	Space Oblique Mercator Landsat end-of-path flag, where 0 is the start and 1 is the end
SOM inclination (deg)	Space Oblique Mercator orbit inclination angle, in degrees, of the ascending node, counter-clockwise from the equator

Table 15-2: Properties for Selected Map Projections (Continued)

Name	Description
SOM Landsat number	Space Oblique Mercator Landsat number (Worldwide Reference System)
SOM Landsat path	Space Oblique Mercator Landsat path number
SOM longitude (deg)	Space Oblique Mercator longitude, in degrees, of the ascending node
SOM period (minutes)	Space Oblique Mercator satellite period, in minutes
SOM ratio	Space Oblique Mercator Landsat ratio that compensates for confusion at the northern end of orbit
Standard parallel 1 (deg)	First standard parallel (degrees latitude) of true scale
Standard parallel 2 (deg)	Second standard parallel (degrees latitude) of true scale
Zone (1-60)	Universal Transverse Mercator (UTM) grid zone number (must be negative for zones in the southern hemisphere)

Table 15-2: Properties for Selected Map Projections (Continued)

Note

The map projection properties are normally taken from the currently selected dataspace. However, in the Operations Browser, the map projection properties are registered on the operation itself. Changing these properties in the Operations Browser will have no affect on the currently selected dataspace. If the Show Dialog property is set to False and then the Map Projection operation is activated, the projection properties will be copied directly from the Map Projection operation onto the currently selected dataspace.

Note

Each projection has default longitude and latitude limits. If you have not modified one of these limits (the longitude and latitude minimum and maximum properties), the Map Projection operation will automatically use its default limit. However, if you have modified one of these limits, the Map Projection operation will use either your desired limit or the default limit, whichever is smaller.

Using the Map Panel

The iMap tool has a Map panel (Figure 15-2) that lets you manipulate the map display. The panel also appears when you apply a map projection or shapefile into another iTool.




Figure 15-2: The Map Panel in the iMap Tool

Table 15-3 describes the items on the Map panel.

Name	Description
Location	Displays the following information: • If no map projection is applied — the cursor location in degrees longitude/latitude or meters, depending on the image units • If a map projection is applied — the cursor location in degrees longitude/latitude and the corresponding Cartesian <i>X/Y</i> (or <i>U/V</i>) coordinates in meters Sensitive only if an image or a contour is selected.
Data Value	Displays the following information: • For an image — the data value and corresponding grayscale or RGB value for the current cursor location (identical to Pixel Value on the Image panel) • For a contour — the data value for the current cursor location Sensitive only if an image or contour visualization is selected.
Longitude limits	Displays the active map projection's maximum and minimum longitude values. Enter new values to update these limits. Sensitive only if a dataspace (or a visualization within the dataspace) with a map projection is selected.
Latitude limits	Displays the active map projection's maximum and minimum latitude values. Enter new values to update these limits. Sensitive only if a dataspace (or a visualization within the dataspace) with a map projection is selected.
Edit Projection...	Opens the Map Projection dialog for the currently active dataspace. For more information, see “Applying a Map Projection” on page 328.

Table 15-3: Items on the Map Panel

Displaying an Image

You can visualize image data in the iMap tool as you would in the iImage tool. To learn more about visualizing image data, see [“Displaying Images”](#) on page 209.

Note

By default, the iMap tool creates an image visualization if given a 2D array or a Truecolor image. This image is warped internally to fit the map projection, if one is present. The actual image data itself remains unchanged.

When you open an image in the iMap tool, you need to *register* the image to define how the pixel data corresponds to points on the earth’s surface. For more information on this process, see [“Registering an Image”](#) on page 335.

Once you have image data in the iMap tool, all of the features of the iImage tool are available. For more information, see [Chapter 10, “Working with Images”](#).

You can export the mapped image by selecting **File** → **Export**. When the IDL Data Export wizard opens, choose the “To a file” option, the image visualization to save, and the output file format. The result will be the image warped to the current map projection.

Note

Depending on the map projection, the alpha channel might be used to mask out pixels outside the map boundary. In this case, you can export the image to a file format that supports four channels, such as TIFF, PNG, or JPEG2000.

Registering an Image

The Map Register Image wizard, shown in [Figure 15-3](#), registers an image's data, creating a correspondence between the image pixels and points on the earth's surface. This registration step is necessary to let the iMap tool properly display the image data in the map projection you select.

The wizard launches automatically when you import image data or open an image file for which not all necessary map information is known. To launch the wizard after the image is open and registered (e.g., if you want to change the registering properties), select **Operations** → **Map Register Image**.




Figure 15-3: The Map Register Image Wizard — Step 1

The coordinates are in either meters or degrees; which units you choose for the translation can affect how the image appears in a map projection. Selecting meters means that the image data have already been warped to a particular projection, and you need to tell IDL which projection to use in displaying the image. Selecting

degrees, on the other hand, means that the image data are not already warped, so you do not need to specify a map projection for the image. It is important that you know in which units your data are, to make the correct decision when registering the image for display.

The Map Register Image wizard reflects this difference between the units by having three steps for meters and two for degrees:

1. Select the coordinate units.
2. Set the pixel minimum, maximum, and size values.
3. (Meters only) Specify the map projection to associate with the image and, if desired, with the dataspace as well.

Once you have set these registering properties and map projection (if applicable), IDL registers the image data, and the iMap tool displays the image and the Image panel along with the Map panel.

Note

If the image being registered was originally from either a TIFF file containing GeoTIFF tags or a JPEG2000 file containing a GeoTIFF UUID box, an additional button, **Show GeoTIFF tags**, is available on the latter dialogs of the Map Register Image wizard (Steps 2 and 3 for meters, Step 2 for degrees). Pressing this button brings up a separate text window containing the GeoTIFF tags, which can be useful in determining the map registration properties.

For a list of GeoTIFF tags, see the [GEOTIFF](#) keyword in “[READ_TIFF](#)” (*IDL Reference Guide*). For more information on JPEG2000 with GeoTIFF, see <http://www.remotesensing.org/jpeg2000/>.

The rest of this section describes the two registration pathways, with meters or with degrees, in more detail.

Registering an Image in Meters

If you select Meters as the coordinate units in Step 1 and click on Next, you see the wizard's Step 2 dialog for meters, shown in [Figure 15-4](#).




Figure 15-4: The Map Register Image Wizard — Step 2 (Meters)

[Table 15-4](#) shows the properties associated with meter coordinates.

Name	Description
X (or U) minimum (meters)	Minimum position in the <i>x</i> (or <i>u</i>) direction, in meters, of the image data
X (or U) maximum (meters)	Maximum position in the <i>x</i> (or <i>u</i>) direction, in meters, of the image data

Table 15-4: Meter Coordinate Properties

Name	Description
X (or U) pixel size (meters)	Pixel size, in meters, in the <i>x</i> (or <i>u</i>) direction
Y (or V) minimum (meters)	Minimum position in the <i>y</i> (or <i>v</i>) direction, in meters, of the image data
Y (or V) maximum (meters)	Maximum position in the <i>y</i> (or <i>v</i>) direction, in meters, of the image data
Y (or V) pixel size (meters)	Pixel size, in meters, in the <i>y</i> (or <i>v</i>) direction

Table 15-4: Meter Coordinate Properties (Continued)

Note _____
The (*u.v*) coordinates refer to the *UV* plane of a cylindrical projection.

Entering the minimum value and the pixel size automatically updates the maximum value.

Figure 15-5 shows the final step in the Map Register Image wizard for the Meters option.




Figure 15-5: The Map Register Image Wizard: Step 3 (Meters)

In this step, you can select a map projection to associate with the image. You also have the option of updating the dataspace map projection to use this projection.

Registering an Image in Degrees

If you select Degrees as the coordinate units in Step 1 and click on Next, you see the wizard’s Step 2 dialog for degrees, shown in [Figure 15-6](#).




Figure 15-6: The Map Register Image Wizard: Step 2 (Degrees)

[Table 15-5](#) shows the properties associated with degree coordinates.

Name	Description
Longitude minimum (deg)	Minimum longitude position, in degrees, of the image data
Longitude maximum (deg)	Maximum longitude position, in degrees, of the image data

Table 15-5: Degree Coordinate Properties

Name	Description
Longitude pixel size (deg)	Pixel size, in degrees, in the longitude direction
Latitude minimum (deg)	Minimum latitude position, in degrees, of the image data
Latitude maximum (deg)	Maximum latitude position, in degrees, of the image data
Latitude pixel size (deg)	Pixel size, in degrees, in the latitude direction

Table 15-5: Degree Coordinate Properties (Continued)

Entering the minimum value and the pixel size automatically updates the maximum value.

Displaying a Contour

You can visualize contour data in the iMap tool as you would in the iContour tool. To learn more about visualizing contour data, see [“Displaying Contours”](#) on page 257.

Once you have contour data in the iMap tool, all of the features of the iContour tool are available. For more information, see [Chapter 12, “Working with Contours”](#).

Creating a Shape Visualization

A *shapefile* stores nontopological geometry and attribute information for the spatial features in a data set. The shapefile format was created by ESRI, and is widely used in the geographic information systems community. The iTools display a shapefile's data by creating one of three special visualization types: ShapePolygon, ShapePolyline, and ShapePoint. The type of visualization created depends on the type of data in the shapefile.

Note

For more information on the shape visualizations, see [“Visualization Type Properties”](#) on page 437.

You can create a shape visualization in one of the following ways:

- Using **File** → **Open** and selecting the shapefile
- Using **File** → **Import** to launch the Data Import Wizard, and selecting the shapefile
- Using **Insert** → **Visualization** and either selecting the appropriate shape visualization type (if you have already imported the shape data into an iTool) or selecting the shapefile whose data you want to import for a shape visualization

Note

When creating a shape visualization using **File** → **Import** or **Insert** → **Visualization**, if the shapefile contains more than one item (polygon, polyline, or point), you can choose to create a single visualization containing *all* of the included items, or to create an individual visualization for each item in the file.

Inserting a Map Grid

The **Insert** → **Map** → **Grid** operation creates a longitude-latitude grid (Figure 15-7) within the current dataspace, using the current projection. If no projection is active, then IDL uses geographic coordinates.




Figure 15-7: The Map Grid

The gridlines appear as a single MapGrid object within the current dataspace. For information on this visualization, see “Map Grid” on page 500.

Note

When you insert a map grid, the Axes container within the dataspace is automatically hidden. To display the axes, use the Visualization Browser to change the Show property of the Axes container.

Inserting an IDL Shapefile

IDL comes with several shapefiles that you can insert in the iMap tool or in another iTool that has a map projection already applied. These files originated from the ESRI Data and Maps CD-ROM data set (1999, 2000, 2002) and can be found, along with their associated database (.dbx) and index (.shx) files, in the `resource/maps/shape` directory of the IDL installation. Also see [“Overview of ESRI Shapefiles”](#) (Chapter 30, *IDL Reference Guide*) for more detailed information on shapefiles.

Inserting the Continents

The **Insert** → **Map** → **Continents** operation loads the `continents.shp` file and displays the continents as a single ShapePolygon ([Figure 15-8](#)) in the current dataspace, using the current projection. If no projection is active, then IDL uses geographic coordinates.




Figure 15-8: The Continents Shapefile

Inserting the Countries (Low Resolution)

The **Insert** → **Map** → **Countries (low res)** operation loads the `country.shp` file and displays the countries (boundaries as of 2002) as separate ShapePolygons (Figure 15-9) in the current dataspace, using the current projection. If no projection is active, then IDL uses geographic coordinates. The ShapePolygons exist in a Countries (low res) visualization container.




Figure 15-9: The Countries (Low Res) Shapefile

Inserting the Countries (High Resolution)

The **Insert** → **Map** → **Countries (high res)** operation loads the `cntry02.shp` file and displays the countries (boundaries as of 2002) as separate ShapePolygons (Figure 15-10) in the current dataspace, using the current projection. If no projection is active,

then IDL uses geographic coordinates. The ShapePolygons exist in a Countries (high res) visualization container.




Figure 15-10: The Countries (High Res) Shapefile

Inserting the Rivers

The **Insert** → **Map** → **Rivers** operation loads the `rivers.shp` file and displays the rivers as separate ShapePolylines (Figure 15-11) in the current dataspace, using the current projection. If no projection is active, then IDL uses geographic coordinates. The ShapePolylines exist in a Rivers visualization container.




Figure 15-11: The Rivers Shapefile (Continents Added for Context)

Inserting the Lakes

The **Insert** → **Map** → **Lakes** operation loads the `lakes.shp` file and displays the lakes as separate ShapePolygons (Figure 15-12) in the current dataspace, using the current projection. If no projection is active, then IDL uses geographic coordinates. The ShapePolygons exist in a Lakes visualization container.




Figure 15-12: The Lakes Shapefile (Continents Added for Context)

Inserting the United States

The **Insert** → **Map** → **United States** operation loads the `states.shp` file and displays the states as separate ShapePolygons (Figure 15-13) in the current dataspace, using the current projection. If no projection is active, then IDL uses geographic coordinates. The ShapePolygons exist in a United States visualization container.




Figure 15-13: The United States Shapefile

Inserting the Canadian Provinces

The **Insert** → **Map** → **Canadian Provinces** operation loads the `canadaprovince.shp` file and displays the provinces as separate ShapePolygons (Figure 15-14) in the current dataspace, using the current projection. If no projection is active, then IDL uses default longitude-latitude coordinates. The ShapePolygons exist in a Canadian Provinces visualization container.




Figure 15-14: The Canadian Provinces Shapefile



Chapter 16

Working with Vectors

This chapter describes vectors and the iVector tool.

Introduction	354	Manipulating the Vector Visualization ...	363
Displaying Vectors	355	iVector Tool Operations	365
Vector Properties	360	Vectors and Mapping	367

Introduction

The IDL iVector tool displays data in vector form. A vector is a line segment that has both length (magnitude) and direction. Magnitude and direction are expressed using two components, the “east-west” component (or *U*) and the “north-south” component (or *V*).

The iVector tool displays two-dimensional *vector flow fields*. Examples of data that can be visualized using vector flow fields are ocean currents, wind, and fluid flows. Data can be visualized as vectors (arrows), wind barbs, or streamlines, and can be located on a regular or irregular grid or can be georeferenced. You can control all aspects of these visualizations, including arrow style and size, coloring by magnitude, direction, or another dataset, data location, missing data, streamline particles, and subsampling.

For more information about importing vector data see [Chapter 2, “Importing and Exporting Data”](#).

Note

For more information on accepted arguments, see “[IVECTOR](#)” (*IDL Reference Guide*).

The iVector tool can be launched in the following ways:

- At the IDL Command Line without arguments or keywords
- At the IDL Command Line with arguments or keywords
- Through the **File** → **New** → **Visualization** → **iVector** menu option in the IDL Workbench
- Through the **File** → **New** → **iVector** menu option in an iTool

Displaying Vectors

The iVector tool's primary purpose is to display vector data, though the tool is capable of much more once the data is visualized. The iVector tool can display multiple types of vectors and allows you to manipulate and edit the displays.

The first task is to display vector data. The following sections are examples of how to display various types of vector data.

Vector Fields

In a *vector field*, each datum is represented by a small arrow, with a length proportional to the magnitude of the flow at that location, and pointing in the direction of the flow.

The following example shows the flow produced by vectors of the form $(-Y, X)$. To create this flow in IDL, enter the following code at the Command Line:

```
x = (y = FINDGEN(21) - 10)
u = REBIN(-TRANPOSE(y), 21, 21)
v = REBIN(x, 21, 21)
IVECTOR, u, v, x, y, AUTO_COLOR=1, $
      RGB_TABLE=39, SCALE_ISOTROPIC=1
```




Figure 16-1: Vector Field Showing Flow

Note

The setting `AUTO_COLOR=1` sets the color of each vector according to its magnitude. The `ISOTROPIC` setting ensures that the X and Y coordinates have the same scaling.

Wind Barbs

Vector data represented using *wind barbs* shows data using arrow shafts with barbs and flags. The direction of the arrow indicates the direction of the wind flow. Barbs and flags represent wind speed in knots. A short barb represents 5 knots while each

long barb represents 10 knots. Each flag represents 50 knots. Collectively, the barbs and flags indicate the magnitude on each arrow, using the following conventions:

Speed (knots)	Symbol
0 - 0.5	Dot
0.5 - 2.5	Shaft only ____
2.5 - 7.5	Short barb ` ____
7.5 - 12.5	Long barb \ ____
12.5 - 17.5	Long + short barb \ ` ____
17.5 - 22.5	Two long barbs \\ ____
47.5 - 52.5	Flag ^ ____

By convention, for geographic data (GRID_UNITS=1 or 2) the barbs and flags point in the clockwise direction in the Northern hemisphere and counterclockwise in the Southern hemisphere. For non-geographic data (GRID_UNITS=0) the barbs and flags always point in the clockwise direction.

The following example shows the wind barbs produced by a field of the form $(-Y, X)$. In this example the VECTOR_STYLE keyword sets the style to wind barbs. To create these wind barbs in IDL, enter the following code at the Command Line:

```
x = (y = 2*FINDGEN(11) - 10)
u = 9*REBIN(-TRANSPPOSE(y), 11, 11)
v = 9*REBIN(x, 11, 11)
IVECTOR, u, v, x, y, VECTOR_STYLE=1
```




Figure 16-2: Wind Barbs in iVector

Streamlines

Streamlines visualize the movement of a set of massless particles through the vector field. The points are tracked by treating the vector field as a velocity field and integrating it. Each path is tracked until the path leaves the input field or a maximum number of steps is reached. You can use keywords to set the number of particles, the integration step size, and the number of steps.

The following example shows the streamlines produced by a random vector field. To create these streamlines in IDL, enter the following code at the Command Line:

```
u = RANDOMU(1,20,20) - 0.5
v = RANDOMU(2,20,20) - 0.5
IVECTOR, u, v, /STREAMLINES, $
    X_STREAMPARTICLES=10, Y_STREAMPARTICLES=10, $
    HEAD_SIZE=0.1, STREAMLINE_NSTEPS=200
```




Figure 16-3: Streamlines in iVector

Note

For details on the streamline keywords, see [“IVECTOR” \(IDL Reference Guide\)](#). Also see [“Adding and Modifying Streamlines”](#) on page 365.

Vector Properties

The iVector window is a self-contained vector visualization and manipulation device. You can import and export vector data, and modify and manipulate vector data. For more information on the basic iVector interface and its layout, see [Appendix A, “iTools Interface Reference”](#).

Modifying Properties

By selecting **Edit** → **Properties** from the iVector tool, you may modify your vector properties. You may modify your vector visualization’s name, description, grid units, style, arrow properties, direction convention, as well as the show/hide properties. For more information on editing properties in the iTools, see [Appendix D, “Visualization Properties”](#).

Subsampling

If you have a vector dataset with a large number of vectors, and thus very high resolution, seeing individual vectors may be difficult. *Subsampling* allows you to decrease the number of displayed vectors, making it easier to view the vector dataset.

You can set subsampling using keywords to iVector from the command line or from the iVector visualization’s property sheet.

The following table shows subsampling functions and how you can invoke them.

Function	Command Line Method	Visualization Browser Method	Options
X Subsampling Factor	Set the X_SUBSAMPLE keyword to IVECTOR	Edit → Properties select X subsample factor	Set to a value (from 1 to any positive value)
Y Subsampling Factor	Set the Y_SUBSAMPLE keyword to IVECTOR	Edit → Properties select Y subsample factor	Set to a value (from 1 to any positive value)
Subsampling Method	Set the SUBSAMPLE_METHOD keyword to IVECTOR	Edit → Properties set Subsampling method	Set to Nearest neighbor or Linear

Table 16-1: iVector Subsampling

For example, a subsampling factor of 2 for both x and y indicates that every other vector will be displayed. A subsampling factor of 10 indicates that one out of every 10 vectors will be displayed.

Autosubsampling

You can also enable *autosubsampling*. Autosubsampling will automatically decrease the number of displayed vectors, based on the current view zoom factor. Zooming out (a smaller zoom percentage) will increase subsampling factors, in turn decreasing the number of displayed vectors. Zooming in (a larger zoom percentage) will decrease subsampling factors, in turn increasing the number of displayed vectors. The following table shows the two ways to enable autosubsampling.

Function	Command Line Method	Visualization Browser Method	Options
Auto-subsampling	Use the AUTO_SUBSAMPLE keyword to IVECTOR	choose Edit → Properties and set Automatic subsampling	• For Command Line, set to enable, default is disabled • For visualization browser, set to True to enable, Default is False (disabled)

Table 16-2: Enabling Autosubsampling for iVector

Coloring Vectors Using Auxiliary Data

Imagine you have global wind data and want to color each wind vector according to the surface temperature at that location. In a case like this you want to visualize your vector data using one dataset for the magnitude and direction, and another dataset for the color of each vector.

There are two ways to do this:

- Use the VECTOR_COLORS keyword from the command line — For more information about using this keyword, see “[IVECTOR](#)” (*IDL Reference Guide*).
- Attach a dataset to the Vector Colors parameter in the Parameter Editor — To do this select your dataset and then go to **Edit** → **Parameters...** to bring up the Parameter Editor.

Your auxiliary dataset can be either integer or floating-point type. For either type, the data will automatically be scaled into the 0-255 range to be used as the color indices. These color indices are then converted into actual colors as given by your current palette for the vector visualization.

If you insert a colorbar (**Insert** → **Colorbar**), the colorbar axis will have the correct (original) range for your auxiliary dataset.

Manipulating the Vector Visualization

The iVector tool gives you many options to manipulate your existing vector visualizations. Once you have visualized your vector data, you may rotate, flip, translate, scale, and zoom as well as modify vector properties. The following options are available for manipulating vectors.

Translating

Translation moves an object or group of objects in a specific direction. When an object is selected, a bounding box appears around the object. For information on translating objects, see [“Translation”](#) on page 64.

Adding Annotations

The following types of annotations can be added to iVector displays:

Vector Annotation Type	Description
Text	Single lines or multiple lines of text can be added to a visualization to provide a label or description.
Line	Straight line annotations can be added to a visualization to link labels to objects or to identify an object.
Rectangle	Rectangular annotations can be added to a visualization to identify rectangular areas.
Oval	Oval annotations can be added to a visualization to identify elliptical areas.
Polygon	Polygon annotations can be added to a visualization to identify areas bounded by a multi-sided polygon.
Freehand	Freehand annotations can be added to a visualization to identify an area.

Table 16-3: Types of Vector Annotations

For more information on creating and using annotations, see [Chapter 5, “Adding Annotations”](#).

View Zoom

View Zoom allows you to zoom in or out on a specific area of the vector display area. To zoom in or out in View Zoom mode click Zoom  on the toolbar. For more information on working with View Zoom, see “[Zooming](#)” on page 70.

Canvas Zoom

Canvas Zoom allows you to increase or decrease the magnification of the entire display canvas (which may contain multiple views, depending on the layout) by a specified percentage. Canvas Zoom is available by selecting the pull-down percentage list from the top of the tool just under the Help menu. For more information on working with Canvas Zoom, see “[Zooming](#)” on page 70.

iVector Tool Operations

Many operations are available in the iVector tool. Once you have visualized your vector data, you can add streamlines or contours. The following operations are available for vectors.

Adding and Modifying Streamlines

When a vector visualization is selected, choosing **Operations** → **Vector** → **Streamlines** will bring up the Streamlines operation dialog:




Figure 16-4: The Streamlines Operation Dialog

From this dialog you can control the number of x and y particles, and the number and size of streamline steps. The dialog only contains the properties that directly affect the current streamline data.

After making any desired streamline setting adjustments, select **OK** to insert a new streamline visualization into the existing dataspace.

The property sheet for the streamline visualization contains additional properties that affect both the streamline data and the visualization. To see the streamline properties, select (with the streamline visualization selected) **Edit** → **Properties...**




Figure 16-5: Editing Streamline Properties in the Visualization Browser

These properties and their values are described in “[Vector](#)” in Appendix D: Visualization Properties.

Adding Magnitude Contours

When a vector or streamline visualization is selected, choose **Operations** → **Vector** → **Contour Magnitude** to insert a contour visualization using the magnitudes of the vector data. To modify the contour properties, select (with the contour visualization selected) **Edit** → **Properties...**

Adding Direction Contours

When a vector or streamline visualization is selected, choose **Operations** → **Vector** → **Contour Direction** to insert a contour visualization using the directions of the vector data. To modify the contour properties, select (with the contour visualization selected) **Edit** → **Properties...**

Vectors and Mapping

If you insert a map projection into an iTool with an existing vector visualization, or if you insert a vector visualization into an iTool with an existing map projection, IDL will attempt to determine whether the vector visualization should be warped using the current map projection.


If the *X* coordinates of the vector visualization are in the range from -180 to 180 and the *Y* coordinates are in the range from -90 to 90, the locations of the vectors are assumed to represent longitude and latitude. In this case, the location of each vector is warped to the current map projection. If the *X* and *Y* coordinates are not in this range, the vector locations are not warped.

Note

The locations and directions of vectors are warped, but their magnitudes are not. The magnitude is assumed to be independent of the grid units.

You can override the default behavior by setting the **Grid units** property of the vector visualization or by specifying the value of the `GRID_UNITS` keyword to `IVECTOR`:

- Setting the value of the **Grid units** property to 1 (meters) indicates that the vector locations are already correctly located on a particular map projection (assumed to be in meters). In this case, you should then also set the dataspace map projection to match your map projection, so that any images or shapefiles are warped to the correct map projection.
- Setting the value of the **Grid units** property to 2 (degrees) indicates that the vector locations are in degrees of longitude and latitude, and that these locations should be warped to the map projection.
- Setting the value of the **Grid units** property to 0 (Not applicable) indicates that the vector grid is in arbitrary units that are not tied to a map projection.



Appendix A

iTools Interface Reference

This appendix describes the following common features of the IDL Intelligent Tools interface:

Introduction to iTools Interface Elements	370	Help Menu	382
File Menu	371	File Toolbar	383
Edit Menu	373	Edit Toolbar	384
Insert Menu	376	Manipulator Toolbar	385
Operations Menu	377	Annotation Toolbar	386
Window Menu	380	Context Menu	387

Introduction to iTools Interface Elements

The Standard IDL Intelligent Tools comprise seven distinct tools: iImage, iPlot, iSurface, iContour, iVolume, iMap, and iVector. Each tool has a specific set of functions related to the type of data it is designed to use. In addition to these specific tasks, all four tools have a number of functions in common. This appendix describes those functions that all iTools have in common; for information about the functions unique to the individual iTools, refer to the chapters describing those tools.

This appendix is an overview of these menu items and toolbar buttons that are common to all iTools:

Menu Bar Items

The following menus appear on the iTool menu bar:

- File Menu
- Edit Menu
- Insert Menu
- Operations Menu
- Window Menu
- Help Menu

Toolbar Items

The following toolbars appear at the top of each iTool window:

- The File toolbar, containing the New, Open, Save, and Print buttons.
- The Edit toolbar, containing the Undo, Redo, Cut, Copy, and Paste buttons.
- The Manipulator toolbar, containing the Select, Rotate, and View Pan buttons.
- The View Zoom button and View Zoom drop-down list.
- The Annotation toolbar, containing the Text and line buttons as well as the Line, Rectangle, Oval, Polygon, and Freehand annotation buttons.

File Menu

The File menu contains tools for creating, opening, printing and saving files, as well as tools for importing and exporting data and images. The File menu items are common to all standard iTools.

Menu Selection	Keyboard Accelerator	Function
New	Ctrl+N	Creates a new iTool of the specified type. Options: iImage, iPlot, iSurface, iContour, iVolume, iMap, and iVector.
Open...	Ctrl+O	Opens a file for import into the current iTool. If this is a data file, such as an image file, ASCII file, or binary file, a new data object will be created and, if applicable, a new visualization will be created.
Import...		Imports an IDL variable or file to the current iTool. See “Data Import Methods” on page 27 for details.
Export...		Exports the data from the currently-selected object to the IDL main program level, or exports the current window to an image file.
Save	Ctrl+S	Saves the state of the current iTool to a file. If the state has not been previously saved and has no filename, enter a filename.
Save As...		Prompts you to enter a filename and then saves the state of the current iTool.
Print Preview...		Shows a preview of the visualization to print and allows you to reorient (Portrait or Landscape) as well as center, print, close, or change printer setup.
Print...	Ctrl+P	Sends the current view of the contents of the graphics window to the specified printer via the standard Windows or Motif printer dialog.

Table A-4: The File Menu

Menu Selection	Keyboard Accelerator	Function
Preferences...		Displays the Preferences Browser. See “The Preferences Browser” on page 95 for details.
Exit	Ctrl+Q	Exits the iTool window, closing all visualizations and views within the window and removing them from memory.

Table A-4: The File Menu (Continued)

Edit Menu

The Edit menu contains tools for editing and deleting data within the tool, retracing your steps with the Undo/Redo commands, and displaying properties for selected objects. The Edit menu items are common to all standard iTools.

Menu Selection	Keyboard Accelerator	Function
Undo	Ctrl+Z	Nullifies the previous operation and restores the iTool to its state before that operation. The name of the previous operation appears after Undo. Note - Operations such as open, save, export, export variable, print, exit, and window moving and resizing cannot be undone.
Redo	Ctrl+Y	Nullifies the previous Undo command and restores the iTool to its state before the Undo command was issued. Any action that can be undone can also be redone.
Cut	Ctrl+X	Deletes the selected item(s) and places a copy on the local clipboard.
Copy	Ctrl+C	Copies the selected item to the local clipboard. If a view is copied, then a bitmap copy of that view (not the entire Window) is also put on the System clipboard. Note - You may change the magnification (resolution) of the bitmap copy using the Edit Copy property sheet.
Paste	Ctrl+V	Pastes the current local clipboard contents into the selected view. If a view is pasted, it is added to the current Window layout and becomes the currently-selected view.

Table A-5: The Edit Menu

Menu Selection	Keyboard Accelerator	Function
Paste Special		Pastes the current local clipboard contents into the selected view, and makes a reference to all contained data.
Delete	Del	Deletes the currently-selected item(s), without putting a copy on the local or system clipboards. Deletion can be reversed with Undo.
Select All		Selects all items in the current view.
Grouping		Select Group to add all selected objects to a group, Ungroup to remove them from the group.
Order		Change the display order of the selected object(s). Choose from these options: • Bring to Front: Move selected object(s) to the top display level. • Send to Back: Move selected object(s) to the bottom display level. • Bring Forward: Move selected object(s) up one display level. • Send Backward: Move selected object(s) down one display level.
Style		Selections related to iTool's styles. • Apply Style: Applies current style to your iTool visualization. • Create Style from Selection: Creates a new style from selected visualization items. • Style Editor: Brings up the Style Editor dialog.

Table A-5: The Edit Menu (Continued)

Menu Selection	Keyboard Accelerator	Function
Parameters...		Displays the Parameter Editor. See “Data Import Methods” on page 27 for details.
Properties...		Brings up the property sheet for the currently-selected item(s). If only the view is selected, the property sheet for the view layer is presented. Only one property sheet may be displayed at a time. If a different item or view is selected, the contents of the property sheet change to the properties of the new item or view. For grouped items, a single property sheet with the intersection of the properties is displayed. When the property values are not the same for the grouped items, those properties are set to undefined or default. Setting a property for a grouped item sets that property for all items in the group.

Table A-5: The Edit Menu (Continued)

Insert Menu

The Insert menu contains tools for adding visualization elements to the displayed data. Contents of the Insert menu vary from iTool to iTool.

Menu Selection	Function
Visualization	Inserts a new visualization into the current window. See “Inserting Visualizations” on page 54 for details.
View	Inserts a new view into the current window. • If the window is currently locked, this menu item will be grayed out. • If the window is not locked, the new view is added to the layout in the appropriate location, depending on the currently active layout.
Dataspace	Inserts data space. (useful when overplotting such as in iPlot)
Axis	Inserts a new axis. Choose from these options: • X: inserts an additional X axis • Y: inserts an additional Y axis • Z: inserts an additional Z axis See “Additional Axes” on page 84 for details.
New Legend	Inserts a new legend for the data set or for the selected visualization(s) into the current window. See “Legends” on page 77 for details.
Legend Item	Inserts a new item into your existing legend.
Colorbar	Inserts a colorbar for the selected item. Note - Only available for indexed color images.
{ Additional items vary depending on the iTool selected. } For example:	
Light	Inserts a new light into the current window. See “Lights” on page 494 for details.
Map	Inserts a new map into the current window.

Table A-6: The Insert Menu

Operations Menu

The Operations menu contains commands for performing operations on the selected data. Contents of the Operations menu vary from iTool to iTool.

Menu Selection	Function
Operations Browser	Displays a hierarchical nested list of all tools in the menus and toolbars. See “The Operations Browser” on page 93 for details.
Macros	Selections related to iTool’s macros. • Run Macro: Select to run a macro. • Start Recording: Select to begin recording a macro. • Stop Recording: Select to cease macro recording. • Macro Editor: Select to bring up the Macro Editor dialog.
Statistics	Computes the statistical properties of the selected item(s), and displays the results in a separate dialog. See “Displaying Statistics” on page 129 for details.
Histogram	Displays a histogram plot of the selected data. See “Plotting a Histogram” on page 128 for details.
Filter	Choose from these options: • Convolution • Median • Smooth See “Filtering” on page 122. {Additional filters vary depending on the iTool selected.}
Rotate	

Table A-7: The Operations Menu

Menu Selection	Function
Rotate Left	Rotate the selected data space left 90°.
Rotate Right	Rotate the selected data space right 90°.
Rotate by Angle	Specify the number of degrees to rotate the selected data space. Note - Rotate by Angle is absolute and always rotates relative to the original X-Y coordinate system for 2D visualizations. For 3D visualizations, Rotate by Angle is relative and does not remember the current rotation angle.
Transform	• Resample — Resample the selected data using parameters specified in Resample property settings. • Rotate Data — Rotate the data within the visualization by a specified number of degrees without affecting the rest of the data space. • Scale Data — Scale the selected object by a specified scale factor. See “Transformations” on page 119 for details. { Additional transformations vary depending on the iTool selected. }

Table A-7: The Operations Menu (Continued)

Menu Selection	Function
Morph	Choose from the following options: • Dilate is commonly known as “fill”, “expand”, or “grow.” It can be used to fill “holes” of a size equal to or smaller than the structuring element. • Erode does to the background what dilation does to the foreground. Given an image and a structuring element, erode can be used to remove islands smaller than the structuring element. • Morph open is simply an erosion operation followed by a dilation operation. Applying morph open more than once produces no further effect. • Morph close is simply a dilation operation followed by an erosion operation. Applying morph close more than once produces no further effect. • Morph gradient is the subtraction of an eroded version of the original image from a dilated version of the original image. • Morph tophat is implemented by first applying the opening operator to the original image, then subtracting the result from the original image. Applying tophat shows the bright peaks within the image. See “Morphing” on page 127 for details.
{ Additional items vary depending on the iTool selected. }	

Table A-7: The Operations Menu (Continued)

Window Menu

The Window menu contains commands for displaying the Data, Operations and Visualization browsers, for zooming in and out of the display, for modifying the window layout, and for displaying a log of system messages. The Window menu items are common to all iTools.

Menu Selection	Function
Data Manager	Displays the Data Manager for the current iTool. See “About the Data Manager” on page 24 for details.
Visualization Browser	Displays a hierarchical nested list of all visualization elements in the display area. See “The Visualization Browser” on page 90 for details.
Canvas Zoom	Set to increase or decrease magnification of the entire iTool window without moving the observer’s “eye.” • 800% • 400% • 200% • 100% • 75% • 50% • 25% Default is 100%. See “Canvas Zoom” on page 70 for more information.
Zoom on Resize	If this menu item is checked, visualizations will be resized whenever a view is resized. By default, visualizations will not be resized if the view size changes. Note - Resizing the tool window usually resizes the view as appropriate.

Table A-8: The Window Menu

Menu Selection	Function
Layout...	Displays the window layout dialog, which allows the user to change the current view layout and the window dimensions. See “Window Layouts” on page 73 for details.
Fit to View	Changes the View Zoom increment so that selected visualizations will completely fill the view.

Table A-8: The Window Menu (Continued)

Help Menu

The Help menu contains commands for displaying online help and information about the iTools. The Help menu items are common to all iTools.

Menu Selection	Function
Help on iTools	Displays help for the iTools system.
Help on the iTools Data Manager	Displays help on the Data manager.
Help on the iTools Parameter Editor	Displays help on the Parameter Editor
Help on Selected Item	Displays help for the item selected in the iTool visualization or browser window.
Help on this iTool	Displays help for the current iTool.
About iTools	Displays a dialog describing the iTools and giving the version number.

Table A-9: The Help Menu

Note _____
In the Operations and Preferences browser windows, help for the selected item is also available on the context menu.

File Toolbar

The File toolbar contains the following buttons:

Button	Tool Name	Function
	New	Creates a new iTool of the same type as the current tool with no data or visualizations.
	Open	Opens a file for import into the current iTool. If this is a data file, such as an image file, ASCII file, or binary file, a new data object will be created and, if applicable, a new visualization will be created.
	Save	Saves the state of the current iTool to a file. If the state has not been previously saved and has no filename, enter a filename. The saved file is cross-platform.
	Print	Prints the entire contents of the graphics window.

Table A-10: File Toolbar Buttons

Edit Toolbar

The Edit Toolbar contains the following buttons:

Button	Tool Name	Function
	Undo	Nullifies the previous operation and restores the iTool to its state before that operation. Note - Operations such as open, save, export, export variable, print, exit, and window moving and resizing cannot be undone.
	Redo	Nullifies the previous Undo command and restores the iTool to its state before the Undo command was issued. Any action that can be undone can also be redone.
	Cut	Deletes the selected item(s) and places a copy on the local clipboard. If the window layout is locked, you will be asked if a copy of the view should be placed on the System clipboard.
	Copy	Copies the selected item to the local clipboard. If a view is copied, then a bitmap copy of that view (not the entire Window) is also put on the System clipboard.
	Paste	Pastes the current local clipboard contents into the selected view. If a view is pasted, it is added to the current Window layout and becomes the currently-selected view.

Table A-11: Edit Toolbar Buttons

Manipulator Toolbar

The Manipulator Toolbar contains the following buttons:


Button	Tool Name	Function
	Select	Click to enter select mode. The arrow pointer is displayed, and objects can be selected in the display area. Click to select an object; a selection box appears around the current selection.
	Rotate	Click to enter rotate mode. A rotation sphere appears around the currently selected object. - Position the mouse pointer on an axis, and the axis rotation pointer is displayed. Drag in the desired direction to rotate the object along the axis. - Position the mouse pointer anywhere on the selected object, and the free rotation pointer is displayed. Drag in the desired direction to rotate the object freely.
	View Pan	Click and drag across the view to pan.
	View Zoom	Click to enter zoom mode. The zoom cursor is displayed, and dragging the mouse closer to or farther from the center of the canvas decreases or increases magnification at the initial point of clicking.
	View Zoom	Click to select a magnification percentage for the entire view.

Table A-12: Manipulator Toolbar Buttons

Annotation Toolbar

The Annotation Toolbar contains the following buttons:

Button	Tool Name	Function
	Text	Click to enter text annotation mode. The insert pointer is displayed, and text can be entered from the keyboard.
	Line	Click to enter line annotation mode. The crosshairs pointer is displayed. Click at the starting point for the line and drag in the desired direction. Release the mouse button to terminate the line.
	Rectangle	Click to enter rectangle annotation mode.
	Oval	Click to enter oval annotation mode.
	Polygon	Click to create a polygon annotation. Click to define vertices, double-click to complete polygon.
	Freehand	Click to enter freehand annotation mode. The crosshairs pointer is displayed. Click at a starting point and drag to create the desired shape. Release the mouse button to complete the polygon.

Table A-13: Annotation Toolbar Buttons

Context Menu

Right-clicking on the visualization window brings up a context menu at that location. The context menu is common to all iTools, and it contains the following menu items:

Menu Selection	Description
Cut	Deletes the selected item(s) and places a copy on the local clipboard. If the window layout is locked, you will be asked if a copy of the view should be placed on the System clipboard.
Copy	Copies the selected item to the local clipboard. If a view is copied, then a bitmap copy of that view (not the entire Window) is also put on the System clipboard.
Paste	Pastes the current local clipboard contents into the selected view. If a view is pasted, it is added to the current Window layout and becomes the currently-selected view.
Delete	Deletes the currently-selected item(s), without putting a copy on the local or system clipboards. Deletion can be reversed with Undo.
Grouping:	Grouping gives you the advantage of allowing desired items to operate together and be manipulated as a single unit.
Group	Groups the currently-selected items into a single unit.
Ungroup	If the selected item is currently a group, then it is ungrouped. Note - You cannot group items across separate visualization and annotation layers.

Table A-14: The Context Menu

Menu Selection	Description
Order: Bring To Front Send To Back Bring Forward Send Backward	Brings the selected item(s) to the front of the graphics hierarchy. Sends the selected item(s) to the back of the graphics hierarchy. Bring the selected item(s) forward one position in the graphics hierarchy. Send the selected item(s) back one position in the graphics hierarchy.
Export to IDL	Exports the currently selected item(s) to your IDL session.
Parameters...	Brings up the parameter editor for the currently selected item(s).
Properties...	Brings up the property sheet for the currently selected item(s). If only the view is selected, the property sheet for the view layer is presented. Only one property sheet may be displayed at a time. If a different item or view is selected, the contents of the property sheet change to the properties of the new item or view. For grouped items, a single property sheet with the intersection of the properties is displayed. When the property values are not the same for the grouped items, those properties are set to undefined or default. Setting a property for a grouped item sets that property for all items in the group.

Table A-14: The Context Menu (Continued)



Appendix B

Property Controls

The following user interface controls are used in iTool property sheets. The general function of these controls is described here. Refer to the individual property descriptions in [Appendix C, “Operations Properties”](#) and [Appendix D, “Visualization Properties”](#) for specific information on how to set individual property controls.




Control Type	Function
Boolean	 Click the browse button  to expand the list. Select either of the two choices (Show or Hide, True or False, etc.) from the list.
Number	If the number is editable, type in a new value. You may be restricted to whole numbers or a range of numbers. Entering a value outside of the valid range causes the number to snap to the nearest allowable value.
	 If a slider is displayed, slide the marker to select a new value.
	 If a spinner control is displayed, click, or click and hold the up or down buttons to change the value.
String	 Enter a string in the text box. If the string exceeds the length of the text box, a browse button is provided to expand the text box.

Table B-15: Controls Used in Property Sheets



Control Type	Function
Color	Select a color from the palette displayed in the color selector:  Or click Custom Color (UNIX users right-click the color bar at the bottom of the window) to specify RGB or HSL values:  Windows Color Picker  UNIX Color Picker <i>Windows users:</i> enter Hue, Sat, Lum or Red, Green, Blue values and click OK to apply the new values. Click Add to Custom Colors to save your values. <i>UNIX users:</i> drag the Red, Green, Blue or Hue, Lightness, Saturation sliders to change values, and click OK to apply the new values.

Table B-15: Controls Used in Property Sheets (Continued)




Control Type	Function	
Line Style		Select a line style from the list. To make the line invisible, select No Line .
Line Thickness		Select a line thickness from the list. Numbers indicate line thickness in pixels. Use the scroll bar to display additional items.
Symbol		Select a symbol to appear at regular intervals on the selected line from the list. To remove a symbol from a line, select No Symbol . Use the scroll bar to display additional items.
String List		Select an item from the list. Use the scroll bar to display additional items.
User Defined		Click the Edit button to display the user-defined property control.

Table B-15: Controls Used in Property Sheets (Continued)



Appendix C

Operations Properties

This appendix describes the following properties of the IDL Intelligent Tools interface found in the Operations Browser of each iTool:

The Operations Browser	394	Crop Properties	413
Macros Properties	395	Region Grow Properties	414
Statistics Properties	396	Contour Properties	416
Filter Properties	398	Image Properties	417
Rotate Properties	405	Surface Properties	418
Transform Properties	406	Vector Properties	419
Map Projection Properties	410	Volume Properties	420
Map Register Image Properties	411	Image Plane Properties	422
Morphing Properties	412		

The Operations Browser

The Operations Browser provides a hierarchical tree view of the tools and operations available from the iTool Operations menu. The Operations Browser is used to set properties for operations and tools used in the iTool window. See [“The Operations Browser”](#) on page 93 for details on how to display and use the Operations Browser.




Figure C-6: The Operations Browser

The property sheet for each operation displayed in the Operations Browser contains the Name and Description properties described in the following table. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#)

Property	Control Type: Options
Name	String : Name assigned to this statistics dialog. Edit the text to change the name.
Description	String : Description of this statistics function. Edit the text to change the description.

Table C-16: Statistics Operation Properties

Macros Properties

Macros provide a shortcut mechanism that lets you quickly and automatically repeat a sequence of interactive operations. The Macros tools appears in the Operation Browser for all iTools. See [Chapter 8, “Working with Macros”](#) for details on how to use macros.

This browser has no properties that can be configured other than Name and Description.

Statistics Properties

The Statistics tool displays statistical information relating to the currently selected object or group of objects. The Statistics tool appears in the Operation Browser for all iTools. See [“Displaying Statistics”](#) on page 129 for details on how to use the Statistics tool.

This browser has no properties that can be configured other than Name and Description.

Histogram Properties

The Histogram tool displays a histogram plot of the data selected in the iTool window. The Histogram tool appears in the Operation Browser for all iTools. See [“Plotting a Histogram”](#) on page 128 for details on how to use the Histogram tool.

Histogram has no configurable properties other than Name and Description.

Filter Properties

The following properties control the iTool filters.

Convolution Properties

Convolution smooths data by using a weighted moving average. Convolution filter properties appear on the Operations Browser for all iTools. See “Convolution Filter” on page 124 for details on applying convolution.

For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to.

Property	Control Type: Options
Show dialog	Boolean: Display the Convolution Kernel Editor dialog when the Convolution filter is selected from the Operations → Filter menu. Choose True to display the dialog, or False to apply the Convolution filter without displaying the dialog. Default = True

Table C-17: Convolution Filter Properties

Property	Control Type: Options
Filter	String List: The default filter. Select from the following list: • User defined • Tent • Boxcar • Gaussian • Edge Horizontal • Edge Vertical • Edge Diagonal Right • Edge Diagonal Left • Line Horizontal • Line Vertical • Line Diagonal Right • Line Diagonal Left • Laplacian • Emboss Default = Tent
Number of columns	Number: Width of the filter (applies only to Tent, Boxcar, and Gaussian). Default = 3
Number of rows	Number: Height of the filter (applies only to Tent, Boxcar, and Gaussian). Default = 1 for 1D data, 3 for 2D data
Kernel	User Defined: Display the Convolution Kernel Editor dialog. Click Edit to display the dialog.
Center	Boolean: Select True (centered) or False (no centering). Default = True
Auto normalize	Boolean: Select True (for automatic normalizing) or False (no automatic normalizing). Default = True
Scale factor	Number: Value to be divided into each result. Default is calculated from the kernel.

Table C-17: Convolution Filter Properties (Continued)

Property	Control Type: Options
Bias offset	Number : Value to be added to each result, after scale factor. Default is calculated from the kernel.
Edge values	Boolean : Select for edge value type: • Zero result • Wrap around • Repeat last value • Zero pad Default = Wrap around
Use invalid value	Boolean : Select True to use the invalid value to filter out missing data, or False (invalid value not used). Default = False
Invalid value	Number : Missing or invalid value that should be ignored. Default = 0
Replacement value	Number : Value used to replace missing results. Default = 0

Table C-17: Convolution Filter Properties (Continued)

Median Properties

Median smoothing replaces each point with the *median* (a value in an ordered set of values with an equal number of values above and below it) of the one- or two-dimensional neighborhood of a given width. See “[Median Filter](#)” on page 123 for details on applying the median filter.

For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Options
WIDTH	Number : Width of the smooth window. Enter a whole number between 1 (no smoothing) and the width of the data. Default = 3
Even Average	Boolean : If set to true and the Width property is set to an even number, the operation will return the average of the two middle numbers.

Table C-18: Median Filter Properties

Smooth Properties

The Smooth filter reduces noise within an image by applying low pass filters. Smooth filter properties appear on the Operations Browser for all iTools. See [“Smooth Filter”](#) on page 122 for details on applying the smooth filter.

For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Options
WIDTH	Number : Width of the smooth window. Enter a whole number between 1 (no smoothing) and the width of the data. Default = 3

Table C-19: Smooth Filter Properties

Roberts Filter Properties

Roberts filter appears on the Operations Browser for the iImage tool only. Roberts filter has no configurable properties other than Name and Description. For more information on the Roberts filter, see [“ROBERTS”](#) (*IDL Reference Guide*).

Sobel Filter Properties

Sobel filter appears on the Operations Browser for the iImage tool only. Sobel filter has no configurable properties other than Name and Description. For more information on the Sobel filter, see “[SOBEL](#)” (*IDL Reference Guide*).

Unsharp Mask Properties

An unsharp-mask filter can be applied to any two-dimensional array or a TrueColor image. The unsharp mask enhances the contrast between neighboring pixels in an image, and is widely used for astronomical images and for digital photographs. For more information on unsharp masking a plot, see “[Unsharp Mask Filter](#)” on page 125.

Property	Control Type: Options
Show dialog	Boolean: Display the Unsharp Mask Editor dialog when the Unsharp Mask filter is selected from the Operations → Filter menu. Choose True to display the dialog, or False to apply the Unsharp Mask filter without displaying the dialog. Default = True
Amount of filter (%)	Number: Click and slide to select percentage amount of filter to be applied. Default = 100%
Radius in pixels	Number: Click and slide to select filter radius in pixels. Default = 3
Clipping threshold	Number: Click and slide to select clipping threshold. Default = 0

Table C-20: Unsharp Mask Filter Properties

Curve Fitting Properties

Curve fitting properties appear on the Operations Browser for the iPlot tool only. See “Curve Fitting” on page 294 for details on applying curve fitting to a plot.

For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to Appendix B, “Property Controls”.

Property	Control Type: Options
Show dialog	Boolean: Display the Curve Fitting Editor dialog when the Curve Fitting filter is selected from the Operations → Filter menu. Choose True to display the dialog, or False to apply the Curve Fitting filter (the default curve fitting model - linear - will be used) without displaying the dialog. Default = True

Table C-21: Curve Fitting Properties

Property	Control Type: Options
Model name	String List: Model to use in curve fitting. Select a model from the list. Choose from these values: • Linear • Qaudratic • Cubic • Quartic • Quintic • Exponential • Gompertz • Logsquare • Hyperbolic • Hyperbolic trigonometric • Logistic • Geometric • Trigonometric summation • Trigonometric product • Variable sinc • Gaussian • Gaussian + constant • Gaussian + linear • Gaussian + quadratic Default = Linear
Parameter(s)	Number: Initial parameter(s) and result(s). Values may be edited here. Default = Varies

Table C-21: Curve Fitting Properties (Continued)

Rotate Properties

The following properties control the iTool Rotate tools. Rotate properties appear on the Operations Browser for all iTools (for iImage it is Rotate or Flip).

Rotate Left Properties

Rotate Left has no configurable properties other than Name and Description.

Rotate Right Properties

Rotate Right has no configurable properties other than Name and Description.

Rotate By Angle Properties

Rotate by Angle has no configurable properties other than Name and Description.

Flip Horizontal

Flip Horizontal has no configurable properties other than Name and Description.

Flip Vertical

Flip Vertical has no configurable properties other than Name and Description.

Transform Properties

The following properties control the iTool Transform tools.

Resample Properties

The Resample transform resamples the selected data using the resampling factors and method specified in these properties. Resample Transform properties appear on the Operations Browser for all iTools. See “[Resample](#)” on page 119 for details on how to resample data.

For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Options
1st dimension factor	Number : The resampling factor for the first dimension (X). Edit the number to change the value. Default = 2
2nd dimension factor	Number : The resampling factor for the second dimension (Y). Edit the number to change the value. Default = 2
3rd dimension factor	Number : The resampling factor for the third dimension (Z). Edit the number to change the value. Default = 2
Interpolation method	String List : Method of interpolation to use in resampling. Select a method from the list. Choose from these values: • Nearest neighbor: Assign the value of the nearest pixel to the pixel in the output image. Fastest method, but may cause jagged edges. • Linear: Surveys the two closest pixels, drawing a line between them and designating a value along that line as the output pixel value. • Cubic: Use cubic polynomial waveforms instead of linear waveforms. Most accurate method, but may require more processing time. Default = Nearest neighbor

Table C-22: Resample Transform Properties

Rotate Data Properties

The Rotate Data operation allows you to rotate the data within the visualization by a specified number of degrees without affecting the rest of the data space (graphical objects and axes). See [“Rotation”](#) on page 115 in for details on using the Rotate Data operation.

The following properties control the Rotate Data tool. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Options
Angle	Number: The angle of rotation in degrees clockwise. Default = 0
X center offset	Number: X subscript of the center of rotation. Default = 0
Y center offset	Number: Y subscript of the center of rotation. Default = 0
Magnification	Number: Magnification factor. Default = 1
Interpolation method	String List: Method of interpolation to use when rotating. Select a method from the list. Choose from these values: • Nearest neighbor: Assign the value of the nearest pixel to the pixel in the output image. Fastest method, but may cause jagged edges. • Linear: Surveys the two closest pixels, drawing a line between them and designating a value along that line as the output pixel value. • Cubic: Use cubic polynomial waveforms instead of linear waveforms. Most accurate method, but may require more processing time. Default = Nearest neighbor
Extrapolate missing	Boolean: Extrapolate the value of a missing pixel from the value of nearby pixels. Default = True

Table C-23: Rotate Data Properties

Property	Control Type: Options
Missing value	Number : A value to be substituted for pixels in the rotated image that fall outside the bounds of the unrotated image. This property is only used if the Extrapolate missing property is set to false. Default = 0
Pivot	Boolean : If set to true, the image will be rotated around the point defined by the X center offset and Y center offset. If set to false, the image will be rotated around its center. Default = False

Table C-23: Rotate Data Properties (Continued)

Scale Data Properties

The Scale Data operation scales the selected objects by a specified scale factor. Scale Data properties appear on the Operations Browser for all iTools. See “[Scaling](#)” on page 65 for details on using the Scale Data operation.

The following properties control the Scale Data tool. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Options
Show dialog	Boolean : Display the Scale Data Editor dialog when Scale Data is selected from the Operations → Scale Data menu. Choose True to display the dialog, or False to apply the Scale Data without displaying the dialog. Default = True
Scale Factor	Number : Scale the selected data by this factor. Edit the number to change the factor that appears in the Scale Factor dialog. Scale Factor may be positive or negative. Default = 2

Table C-24: Scale Data Properties

Invert Image Properties

Invert Image Transform properties appear on the Operations Browser for iImage only. The operation has no unique properties.

Byte Scale Properties

Byte Scale properties appear on the Operations Browser for iImage only. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Options
Automatic Min/Max	Boolean : Automatically compute minimum and maximum values? Choose True or False . Default = True
Minimum cutoff	Number : Minimum value of array to be considered. Edit the number to change the value. Default = 0
Maximum cutoff	Number : Maximum value of array to be considered. Edit the number to change the value. Default = 255
Bottom byte	Number : Minimum value of scaled result. Edit the number to change the value. Range = 0-255. Default = 0
Top byte	Number : Maximum value of scaled result. Edit the number to change the value. Range = 0-255. Default = 255

Table C-25: Byte Scale Transform Properties

Note

When working with byte data, the default bytescale range is always 0-255. Therefore, even if data is bytescaled from 0-100, it will display using 0-255. This may cause visualized data to appear darker.

Map Projection Properties

The map projection functionality displays image and contour data that are georeferenced and mapped to particular projections. See [Chapter 15, “Working with Maps”](#) for details on how to use mapping functionality.

For a comprehensive list of map projection properties, see [“Applying a Map Projection”](#) on page 328.

Map Projection has no configurable properties other than Show dialog.

Property	Control Type: Options
Show dialog	Boolean: Display the Map Projection dialog when Operations → Map Projection is chosen. Choose True to display the dialog, or False to apply the Map Projection dialog without displaying the dialog. Default = True

Table C-26: Map Projection Properties

Map Register Image Properties

The map projection functionality displays image and contour data that are georeferenced and mapped to particular projections. See [Chapter 15, “Working with Maps”](#) for details on how to use mapping functionality.

Map Register Image has the following configurable properties.

Property	Control Type: Options
Origin (x)	Number: Set the longitudinal minimum in degrees. Default = 0
End (x)	Number: Set the longitudinal maximum in degrees. Default = 0
Pixel size (x)	Number: Set the longitudinal pixel size in degrees. Default = 0
Origin (y)	Number: Set the latitudinal minimum in degrees. Default = 0
End (y)	Number: Set the latitudinal maximum in degrees. Default = 0
Pixel size (y)	Number: Set the latitudinal pixel size in degrees. Default = 0

Table C-27: Map Register Properties

Morphing Properties

Morphing is available for iImage, iSurface, and iContour.

Mathematical morphology is a method of processing digital images on the basis of shape. Six morphing options are available for use in iTools: dilate, erode, morph open, morph close, morph gradient, and morph tophat. All six options share the same properties. See “[Morphing](#)” on page 127 in for details on morphing data.

For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Options
Structure Shape	String List : The shape of the structuring element used in the morph operation. Choose from these values: • Square • Circle Default = Square
Structure Width	Number : The width of the structuring element. Default = 3

Table C-28: Morphological Filter Properties

Crop Properties

Cropping is available for the iImage tool. The iImage cropping operation allows you to crop one or more selected images at a specified location and specified dimensions.

See “[iImage Tool Operations](#)” on page 231 for details on cropping.

For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Options
X	Number : The X cropping value. Default = 0
Y	Number : The Y cropping value. Default = 0
Width	Number : The crop operation width setting. Default = <width of selected image>
Height	Number : The crop operation height setting. Default = <height of selected image>
Units	String List : • Data • Pixel Default = Data

Table C-29: Crop Properties

Region Grow Properties

Region growing expands a selected area to include nearby pixels that fall within a threshold range of the current selection. See “[REGION_GROW](#)” (*IDL Reference Guide*) for additional details. For a description of how a particular control is used, refer to [Appendix B](#), “Property Controls”.

Property	Control Type: Options
Region grow method	String List: The method used to select pixels that are similar to the current selection. Choose from these values: • By threshold: The expanded region includes neighboring pixels that fall within the range defined by the Threshold minimum and Threshold maximum values. • By standard deviation: The expanded region includes neighboring pixels that fall within the range of the mean of the region’s pixel values plus or minus the given multiplier times the sample standard deviation as follows: $\text{Mean} \pm \text{StdDevMultiplier} * \text{StdDev}$ where Mean is the mean value of the selected pixels, StdDevMultiplier is the value specified by the Standard Deviation Multiplier property, and StdDev is the standard deviation of the selected pixels. Default = By threshold
Pixel search method	String List: Specifies which pixels should be considered during region growing. Four-neighbor searching searches only the neighbors that are exactly one unit in distance from the current pixel; Eight-neighbor searching searches all neighboring pixels. Choose from these values: • 4-neighbor • 8-neighbor Default = 4-neighbor

Table C-30: Region Grow Operation Properties

Property	Control Type: Options
Threshold to use	String List: Specifies the threshold values to use. Choose from these values: • Source ROI/Image threshold: Base the threshold values on the pixel values in the currently selected region. • Explicit: Specify the threshold values using the Threshold minimum and Threshold maximum properties. Default = Source ROI/Image threshold
Threshold minimum	Number: The explicitly specified minimum threshold value. Default = 0
Threshold maximum	Number: The explicitly specified maximum threshold value. Default = 256
Standard deviation multiplier	Number: The number of standard deviations to use if the region growing method is By standard deviation. Default = 1
For an RGB(A) image use	String List: If the image has separate color channels, use the selected channel when growing the region. Choose from these values: • Luminosity: Luminosity values • Red Channel: Red values • Green Channel: Green values • Blue Channel: Blue values • Alpha Channel: Transparency values. Default = Luminosity

Table C-30: Region Grow Operation Properties (Continued)

Contour Properties

Contour Properties appear on the Operations Browser for iImage and iSurface only. The following properties control the contour operation. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Options
N_LEVELS	Number : Set the number of contour levels. Default = 5
Value	Number : Set the contour value to use. Default = 0
Projection	Boolean : Choose the contour type: • Planar • 3D Default = Planar

Table C-31: Contour Properties

Image Properties

Image Properties appear on the Operations Browser for iSurface and iContour only. Image has no configurable properties other than Name and Description.

Surface Properties

Surface Properties appear on the Operations Browser for iImage and iContour only. Surface has no configurable properties other than Name and Description.

Vector Properties

Vector Properties appear on the Operation Browser for the iVector tool.

Streamlines

For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Options
Show Dialog	Boolean: Display the Streamlines Value Selector dialog when Streamlines is selected from the Operations → Vector menu. Choose True to display the dialog, or False to apply the streamlines without displaying the dialog. Default = True
X stream particles	Number: Set number of X dimension stream particles. Default = 25
Y stream particles	Number: Set number of Y dimension stream particles Default = 25
Streamline steps	Number: Set number of streamline steps. Default = 100
Streamline step size	Number: Set streamline step size value. Default = 0.2

Table C-32: Vector Streamline Properties

Contour Magnitude

Contour Magnitude has no configurable properties.

Contour Direction

Contour Direction has no configurable properties.

Volume Properties

Volume Properties appear on the Operation Browser for the iVolume tool only.

Image Plane

Image Plane has no configurable properties other than Name and Description.

Isosurface

For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Options
Show Dialog	Boolean: Display the Isosurface Value Selector dialog when Isosurface is selected from the Operations → Volume menu. Choose True to display the dialog, or False to apply the isosurface without displaying the dialog. Default = True

Table C-33: Isosurface Properties

Render Volume

Render Volume has no configurable properties other than Name and Description.

Interval Volume

For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Options
Show Dialog	Boolean: Display the Isosurface Value Selector dialog when Isosurface is selected from the Operations → Volume menu. Choose True to display the dialog, or False to apply the isosurface without displaying the dialog. Default = True

Table C-34: Interval Volume Properties

Image Plane Properties

Image Plane Properties appear on the Operation Browser for the iVolume tool only.

Property	Control Type: Options
Show	Boolean: Display the image plane after Image Plane is selected from the Operations → Volume → Image Plane menu. Choose True to display, or False to apply the image plane without displaying. Default = True
Opacity control	Boolean: Choose opacity control type. • Use opacity table • Opaque • Opacity value Default = Use opacity table
Opacity value	Number: Set opacity value. Default = 50
Orientation	Boolean: Choose image plane orientation. • X • Y • Z Default = X
Opacity	Number: Set opacity. Default = 1
Color	Boolean: Set color. Default = White [255, 255, 255]
Bottom color	Boolean: Set bottom color. Default = White [255, 255, 255]


Table C-35: Image Plane Properties

Property	Control Type: Options
Depth offset	Number : Set depth offset value. Default = 1
Skip zero opacity	Boolean : Choose True to skip zero opacity or False to use zero opacity. Default = True
Texture interpolation	Boolean : Set texture interpolation type. • Nearest neighbor • Bilinear Default = Nearest neighbor

Table C-35: Image Plane Properties (Continued)

Launch iImage

Launch iImage has no configurable properties other than Name and Description.



Appendix D

Visualization Properties

This appendix describes the following visualization properties of the IDL Intelligent Tools interface found in the Visualization Browser of each iTool:

Introduction to Visualization Properties ..	426	Data Space Properties	433
The Visualization Browser	427	Visualization Type Properties	437
Window Properties	428	2D Annotation Layer Properties	513
View Properties	430	Legend Properties	524
Visualization Layer Properties	431		

Introduction to Visualization Properties

The IDL iTools comprise seven distinct tools: iImage, iPlot, iSurface, iContour, iVolume, iMap, and iVector. Each tool has a specific set of functions related to the type of data it is designed to use. In addition to these specific tasks, all tools have a number of functions in common.

This appendix describes those functions that all iTools have in common; for information about the functions unique to the individual iTools, refer to

- [Chapter 10, “Working with Images”](#)
- [Chapter 11, “Working with Surfaces”](#)
- [Chapter 12, “Working with Contours”](#)
- [Chapter 13, “Working with Plots”](#)
- [Chapter 14, “Working with Volumes”](#)
- [Chapter 15, “Working with Maps”](#)
- [Chapter 16, “Working with Vectors”](#)

This appendix describes the properties common to various iTool visualizations.

The Visualization Browser

The Visualization Browser provides a hierarchical tree view of all objects displayed in the iTool window. The Visualization Browser is used to select objects and to display the property sheets for selected objects. See [“The Visualization Browser”](#) on page 90 for details on how to display and use the Visualization Browser.

The Visualization Browser displays a list of the contents of the iTool window in the left pane. The property sheet for the object currently selected in the left pane can be displayed in the right pane of the Visualization Browser window by clicking on the small arrows to the top-right of the left pane and top-left of the right pane (in the middle if both are displayed). For example, to display the properties of the current window, select Window in the left pane of the Visualization Browser as shown in the following figure.

Window Properties




Figure D-7: The Visualization Browser with Window Properties Displayed

These properties control the display of the iTool window. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Values
Zoom on Resize	Boolean: Zoom visualization upon resize of window? Choose True or False . Default = False
Window Width	Number: Width of the current iTool window in pixels. Edit the number to change the value. Default = 640 Note - The minimum width of the window correlates to the width of the menubar.

Table D-36: iTool Window Properties

Property	Control Type: Values
Window Height	Number : Height of the current iTool window in pixels. Edit the number to change the value. Default = 512
Drag Quality	String : Drag quality to define the level of detail shown when a visualization is translated, scaled, zoomed, or otherwise moved by mouse. Choose High , Medium , or Low . Default = High .

Table D-36: iTool Window Properties (Continued)

All property sheets displayed in the Visualization Browser, with the exception of the Window property sheet displayed above, include the Name, Description, and Show properties described in the following table:

Property	Control Type: Values
Name	String : Name assigned to this view. Edit the text to change the name.
Description	String : Description of this view. Edit the text to change the description.
Show	Boolean : Show this view? Choose True or False . Default = True

Table D-37: Name and Description Properties

View Properties

Each iTool window contains at least one view. If multiple views have been created from the Window Layout dialog, each view will be listed separately.




Figure D-8: Visualization Browser with View Properties Displayed

These properties control the display of the view or views contained in the iTool window. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#)

Property	Control Type: Values
Zoom Factor	Number : Increase or decrease magnification of the view by this factor. Edit the number to change the value. Default = 1
Layout Position	Displays the currently selected layout view
X margin	Number : Set horizontal margin size. Valid range = 0.0 to 0.49.
Y margin	Number : Set vertical margin size. Valid range = 0.0 to 0.49.
Background color	Color : Sets the background color of the contained Visualization Layer. Default = [255, 255, 255] (white)

Table D-38: View Properties

Visualization Layer Properties

The Visualization Layer contains the data space and, for three-dimensional objects, the lights, associated with a visualization.




Figure D-9: Visualization Browser with Visualization Layer Properties Displayed

These properties control the visualization of the data space. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Values
Background Color	Color: Visualization layer background color. Transparent must be set to False . Click to choose from the default color palette, or specify RGB values. Default = [255, 255, 255] (white)
Transparent	Boolean: Make visualization layer transparent? Choose True or False . Default = True

Table D-39: Visualization Layer Properties

Property	Control Type: Values
Projection	String List: Projection method for displaying the visualization layer. Select a method from the list. Choose from these values: • Orthogonal: Orthographic projection (objects are projected onto the visualization layer along lines perpendicular to the view plane) • Perspective: Objects are projected onto the visualization layer along perspective lines that converge in the distance. Default = Orthogonal
Stretch to Fit	Boolean: Stretch visualization layer to fit window? Choose True or False. Default = False
Depth cue bright	Number: The distance of the near Z plane used for depth cueing. Objects closer than this distance will be painted in their normal color. Objects further than this distance will fade into the background.
Depth cue dim	Number: The distance of the far Z plane used for depth cueing. Objects further than this distance will be painted in the background color. Setting Depth cue bright and Depth cue dim to the same value will disable depth cueing.

Table D-39: Visualization Layer Properties (Continued)

Data Space Properties

The data space contains the data type(s) displayed within the visualization, plus the axes associated with the data. It is a transparent-walled bounding box by default. When the data space walls are not transparent, some display artifacts may be visible in certain situations. See [“Rendering Objects at Data Space Depth”](#) on page 436 for more information.




Figure D-10: Visualization Browser with Data Space Properties Displayed

These properties control the visualization of the data space. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Values
Isotropic scaling	Scaling method. Select a method from the list. Choose between these values: • Automatic: automatic scaling • Isotropic: isotropic scaling • Anisotropic: anisotropic scaling Default = Automatic Note - If this property is set to Automatic, then: 1. If any visualization within the dataspace has its Isotropic scaling property set to True, the dataspace will be automatically set to isotropic, and the Anisotropic 2D/3D scale properties will be desensitized. 2. If none of the visualizations are isotropic, the dataspace will be automatically set to anisotropic, and the appropriate Anisotropic scale property will be sensitized for either 2D or 3D data.
Anisotropic 2D scale	Presentation scale factor applied along Y axis
Anisotropic 3D scale	Presentation scale factor applied along Z axis
Map projection	Default = No projection (click to edit)
X Minimum	Number : Minimum value for X coordinate of data set.
X Maximum	Number : Maximum value for X coordinate of data set.
Y Minimum	Number : Minimum value for Y coordinate of data set.
Y Maximum	Number : Maximum value for Y coordinate of data set.
Z Minimum	Number : Minimum value for Z coordinate of 3-D data set.

Table D-40: Data Space Properties

Property	Control Type: Values
Z Maximum	Number : Maximum value for Z coordinate of 3-D data set.
Automatic X range updates	Boolean : Automatically updates the range of X values. Choose True or False . Default = True
Automatic Y range updates	Boolean : Automatically updates the range of Y values. Choose True or False . Default = True
Automatic Z range updates	Boolean : Automatically updates the range of Z values. Choose True or False . Default = True
X log	Boolean : Determines X axis type. Choose True (logarithmic) or False (linear). Default = False .
Y log	Boolean : Determines Y axis type. Choose True (logarithmic) or False (linear). Default = False .
Z log	Boolean : Determines Z axis type. Choose True (logarithmic) or False (linear). Default = False .
Color	Color : Data space bounding box border color. Border Style must not be No line . Click to choose from the default color palette, or specify RGB values. Default = [0, 0, 0] (black)
Linestyle	Line Style : Data set bounding box border line style. Select a line style from the list. Default = No line
Thickness	Line Thickness : Data set bounding box border line thickness. Select a thickness from the list. Default = 1 .
Fill Background	Boolean : Fills data space background with background color. Choose True or False . Default = True
Fill Color	Color : Data space background color. Fill Background must be set to True . Click to choose from the default color palette, or specify RGB values. Default = [255, 255, 200] (cream)
Transparency	Number : Transparency of data space background from 0% to 100%. Fill Background must be set to True . Move slider to select a new percentage. Default = 100

Table D-40: Data Space Properties (Continued)

Rendering Objects at Data Space Depth

The depth buffer is a record of the depth at which each pixel of a graphic primitive is rendered on a graphics device. This is typically used to control the visual positioning of objects in front or behind other objects. (See [“Controlling the Depth of Objects in a View”](#) (Chapter 2, *Object Programming*) for more information on depth buffers.)

Data space walls are polygon objects that are transparent by default. In unusual circumstances when the walls are not transparent, *and* when another object is drawn in the same plane, display artifacts may be visible when the objects are transformed. This results from the normal competition between z-buffer and polygon rasterization operations. To avoid any display artifacts, reposition the object so that it is not in the same plane as the data space wall, or make the wall completely transparent.

Visualization Type Properties

There are many types of visualizations that can be displayed in the six iTools. Each data type has its own property sheet, which can be displayed in the Visualization Browser. For more information, see:

- [“Image”](#) on page 438
- [“Plot”](#) on page 441
- [“Plot 3D”](#) on page 445
- [“Surface”](#) on page 448
- [“Contour”](#) on page 453
- [“Vector”](#) on page 458
- [“Volume”](#) on page 463
- [“Isosurface”](#) on page 469
- [“Interval Volume”](#) on page 471
- [“Image Plane”](#) on page 474
- [“Colorbar”](#) on page 477
- [“Histogram”](#) on page 481
- [“Axes”](#) on page 485
- [“Lights”](#) on page 494
- [“Polygonal ROI”](#) on page 497
- [“IDL Graphics Objects”](#) on page 499
- [“Map Grid”](#) on page 500
- [“ShapePolygon”](#) on page 505
- [“ShapePolyline”](#) on page 507
- [“ShapePoint”](#) on page 509
- [“Streamlines”](#) on page 510

Image




Figure D-11: Visualization Browser with Image Properties Displayed

These properties control image object visualizations. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Values
Image Palette	User Defined: By selecting Edit Color → Table Edit access the color table to manipulate color values
Interpolation	String List: Method used for interpolating the image. Select a method from the list. Choose from these values: • Nearest Neighbor: Assign the value of the nearest pixel to the pixel in the output image. Fastest method, but may cause jagged edges. • Bilinear: Create a weighted average based on the nearness and brightness of the closest four pixels, and assign that value to the pixel in the output image. Default = Nearest Neighbor
Z value	Number: Z value of plane on to which to project the image. Edit the number to change the value. Note - If the Z value is zero then the image visualization is considered to be 2D. If the Z value is nonzero, then the image visualization is considered to be 3D, and the dataspace associated with this image will be automatically switched to 3D. Default = 0
Pixel size (x)	Number: Pixel size for x value. Default = 1
Pixel size (y)	Number: Pixel size for y value. Default = 1
Origin (x)	Number: Origin point for x value. Default = 0
Origin (y)	Number: Origin point for y value. Default = 0

Table D-41: Image Properties

Property	Control Type: Values
Units	Number : Number of units. Default = None
Image transparency	Number : Transparency of the image, 0% - 100%. Move the slider to change the value. Default = 0 (no transparency) Note - The transparency is changed by adding an alpha channel to the image. If your image has an alpha channel then the Transparency property is ignored.
Row Order	String List : Select an order from the list. Choose from these values: • Bottom-to-top • Top-to-bottom Default = Bottom-to-top

Table D-41: Image Properties (Continued)

Plot




Figure D-12: Visualization Browser with Plot Properties Displayed

These properties control plot object visualizations. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).


Property	Control Type: Values
Vertex Colors Color Table	User Defined: By selecting Edit Color → Table Edit access the color table to manipulate plot color values 
Color	Color: Color for the plot line. Click to choose from the default color palette, or specify RGB values. Default = [0 , 0 , 0] (black)
Line style	Line Style: Style for the plot line. Select a style from the list. Default = ————— (solid line)
Thickness	Line Thickness: Thickness for the plot line. Select a thickness from the list. Default = 1

Table D-42: Plot Properties

Property	Control Type: Values
Minimum value	Number : Minimum value to include in the plot. Edit the number to change the value.
Maximum value	Number : Maximum value to display in the plot. Edit the number to change the value.
Histogram plot	Boolean : Display plot as a histogram? Choose True or False . Default = False
Points to average	Number : Number of points to average when drawing the plot. Edit to change the value. Default = 1
Polar plot	Boolean : Display plot as a polar plot? Choose True or False . Default = False
Fill plot	Boolean : Fill between plot lines? Choose True or False . Default = False
Fill level	Number : Level at which to begin the plot fill. Edit the number to change the value. Default = 0
Fill color	Color : Color for the plot fill. Fill transparency must be less than 100%. Click to choose from the default color palette, or specify RGB values. Default = [128, 128, 128]
Fill transparency	Number : Transparency of the plot fill from 0% to 100%. Move the slider to change the value. Default = 0
Symbol	Symbol : Symbol to appear at regular intervals on the plot line. Choose a symbol from the list. Default = No symbol
Symbol size	Number : Factor from 0 - 1 determining the size of the selected symbol. Move slider to change the size. Default = 0.2
Use default color	Boolean : Activate Symbol color property. Choose True or False . Default = False
Symbol color	Color : Color for the selected symbol. Click to choose from the default color palette, or specify RGB values. Default = [0, 0, 0] (black)

Table D-42: Plot Properties (Continued)

Property	Control Type: Values
Symbol thickness	Number : Line thickness from 1 - 9.9 for the selected symbol. Move slider to change the thickness. Default = 1.
Symbol increment	Number : Interval at which symbols will be displayed on the plot line. Influenced by Number of points to average (listed previously). Edit to change the value. Default = 1

Table D-42: Plot Properties (Continued)

Plot 3D




Figure D-13: Visualization Browser with 3D Plot Properties Displayed

These properties control three-dimensional plot object visualizations. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).


Property	Control Type: Values
Vertex color table	User Defined: By selecting Edit Color → Table Edit access the color table to manipulate plot color values. 
XY Shadow	Boolean: Show XY shadow? Choose Hide or Show. Default = Hide
YZ Shadow	Boolean: Show YZ shadow? Choose Hide or Show. Default = Hide
XZ Shadow	Boolean: Show XZ shadow? Choose Hide or Show. Default = Hide
Color	Color: Color for the plot line. Click to choose from the default color palette, or specify RGB values. Default = [0 , 0 , 0] (black)

Table D-43: Plot 3D Properties

Property	Control Type: Values
Line style	Line Style: Style for the plot line. Select a style from the list. Default =  (solid line)
Thickness	Line Thickness: Thickness for the plot line. Select a thickness from the list. Default = 1
Shading	String List: Shading method. Select a method from the list. Choose between these values: • Flat: Flat shading • Gouraud: Gouraud shading Default = Flat
Symbol	Symbol: Symbol to appear at regular intervals on the plot line. Choose a symbol from the list. Default = No symbol
Symbol size	Number: Factor from 0 - 1 determining the size of the selected symbol. Move slider to change the size. Default = 0.2
Use default color	Boolean: Activate Symbol color property. Choose True or False . Default = False
Symbol color	Color: Color for the selected symbol. Click to choose from the default color palette, or specify RGB values. Default = [0, 0, 0] (black)
Symbol thickness	Number: Line thickness from 1 - 9.9 for the selected symbol. Move slider to change the thickness. Default = 1.
Symbol increment	Number: Interval at which symbols will be displayed on the plot line. Influenced by Number of points to average (above). Edit to change the value. Default = 1

Table D-43: Plot 3D Properties (Continued)

Surface




Figure D-14: Visualization Browser with Surface Properties Displayed

These properties control surface object visualizations. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Values
Color	Color: Color of the surface visualization. Click to choose from the default color palette, or specify RGB values. Default = [255, 184, 0] (gold)
Use color on bottom	Boolean: Display a color for the bottom of the surface. Choose True or False . Default = False
Image palette	User Defined: By selecting Edit Color → Table Edit access the color table to manipulate surface color values.
Bottom color	Color: Color to be used for the bottom of the surface. Click to choose from the default color palette, or specify RGB values. Default = [255, 255, 255] (white)
Minimum value	Number: Minimum Z-Axis value of the surface plot. Edit the number to change the value.
Maximum value	Number: Maximum Z-Axis value of the surface plot. Edit the number to change the value.

Table D-44: Surface Properties

Property	Control Type: Values
Surface style	String List: Style used for rendering the surface. Select a style from the list. Choose from these values: • Points: Data points in the surface are rendered as points. • Wire mesh: Data points in the surface are connected with lines, forming a mesh. • Filled: Data points in the surface are connected with filled quadrangles or triangles, forming a solid surface. • Ruled XZ: Data points in the surface are connected with horizontal (Z-direction) lines, forming a grid. • Ruled YZ: Data points in the surface are connected with vertical (Y-direction) lines, forming a grid. • Lego: Stacked histogram-style plot in which each data value is rendered as an outline box covering the XY extent of the cell and with a height proportional to the Z value. • Lego filled: Same as Lego, but the boxes are filled. Default = Filled
Fill shading	String List: Method used for shading the surface polygons. Select a shading method from the list. Choose from these values: • Flat: Shades polygons with a uniform fill. • Gouraud: Interpolates intensities from each vertex along each edge. Then, when the polygons are converted, interpolates the shading along each scan line from the edge intensities. Results in a more natural appearance. Default = Flat
Draw method	String List: Method used for drawing the surface. Select a method from the list. Choose from these values: • Quads: Draw a surface composed of quadrangles. • Triangles: Draw a surface composed of triangles. Default = Quads

Table D-44: Surface Properties (Continued)

Property	Control Type: Values
Line style	Line Style: Style of lines used for constructing the surface. Select a style from the list. Default =  (solid line)
Line thickness	Line Thickness: Thickness of lines used for constructing the surface. Select a thickness from the list. Default = 1
Remove hidden lines	Boolean: Hide lines that show through the surface mesh or grid. Choose True or False . Default = False
Show skirt	Boolean: Display the edges of the surface as a filled skirt? Choose True or False . Default = False
Skirt bottom height	Number: Set bottom of displayed skirt to this height. Edit the number to change the value. Default = 0
Texture interpolation	String List: Method used for interpolating selected texture map. Select a method from the list. Choose from these values: • Nearest Neighbor: Assign the value of the nearest pixel to the pixel in the output image. Fastest method, but may cause jagged edges. • Bilinear: Create a weighted average based on the nearness and brightness of the closest four pixels, and assign that value to the pixel in the output image. Default = Nearest Neighbor
Texture hires	String List: Method used for tiling the selected high-resolution texture map. Select a tiling method from the list. Choose from these values: • No tiling: Do not use tiling • LOD tiling: Use level of detail tiling • Tiling: Use tiling Default = No tiling

Table D-44: Surface Properties (Continued)

Property	Control Type: Values
Skip zero opacity	Boolean: Skip zero opacity for surface? Choose True or False . Default = True
Vertex Color Scale	User Defined: Select vertex color scale bottom/top.
Texture Map Scale	User Defined: Select texture map scale bottom/top.

Table D-44: Surface Properties (Continued)

Contour




Figure D-15: Visualization Browser with Contour Properties Displayed

These properties control contour object visualizations. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Values
Contour level properties	User Defined: Click to edit individual or all contour level properties. Click  and Edit... to display the Contour Levels window. See “ Contour Levels Window ” on page 455 for details.
Use palette color	Boolean: Use palette color? Choose True or False . Default = False

Table D-45: Contour Properties

Property	Control Type: Values
Planar Z Value	Number: Z value of plane on to which to project contours. Edit the number to change the value. Note - If the Z value is zero, and the Projection is Planar, then the contour visualization is considered to be 2D. If the Z value is nonzero, then the contour visualization is considered to be 3D, and the dataspace associated with this contour will be automatically switched to 3D. Default = 0
Number of levels	Number: Number of contour levels to display. Edit the number to change the value. Default = 5
Projection	String List: Method of projection. Select a method from the list. Choose from these values: • Three-D: Project in three dimensions • Planar: Project onto a plane Default = Planar
Fill contours	Boolean: Fill space between contours? Choose True or False. Default = False
Shading	String List: Shading method. Select a method from the list. Choose between these values: • Flat: Flat shading • Gouraud: Gouraud shading Default = Flat
Minimum value	Number: Minimum value to display in the contour. Edit number to change value. No default value.
Maximum value	Number: Maximum value to display in the contour. Edit number to change value. No default value.
Downhill ticks	Boolean: Show downhill ticks? Choose Hide or Show. Default = Hide

Table D-45: Contour Properties (Continued)

Property	Control Type: Values
Downhill tick interval	Number: Distance between downhill tick marks. Edit number to change value. Default = 0 . 2
Downhill tick length	Number: Length of downhill tick marks. Edit number to change value. Default = 0 . 2

Table D-45: Contour Properties (Continued)

Contour Levels Window




Figure D-16: Contour Levels Window

The Contour Levels window contains properties that control the contour levels.

Property	Control Type: Values
Value	Number: Value of the contour level. Edit the number to change the value. Default comes from contour data.
Color	Color: Color for the contour level. Click to choose from the default color palette, or specify RGB values. Default = [0 , 0 , 0] (black)

Table D-46: Contour Levels Properties

Property	Control Type: Values
Line style	Line Style: Style for the contour level. Select a style from the list. Default =  (solid line)
Line thickness	Line Thickness: Thickness for the contour level. Select a thickness from the list. Default = 1
Label	String List: Choose the kind of label to use for each contour level. Choose from these values: • None • Value • Text • Symbol
Label interval	Number: Distance between labels on the contour level. Edit number to change value. Default = 0.4
No label gaps	Boolean: Interrupt the contour level for the label. Choose True or False . Default = False
Use label color	Boolean: Display a color for the contour level's label. Choose True or False . Default = False
Label color	Color: Color for the contour level label. Click to choose from the default color palette, or specify RGB values. Default = [0, 0, 0] (black)
Symbol label	Symbol: Symbol to appear at regular intervals on the contour level. Choose a symbol from the list. Default = No symbol
Symbol size	Number: Factor from 0 - 1 determining the size of the selected symbol. Move slider to change the size. Default = 0.2
Text label	String: Text that labels the contour object in the legend. Edit string to change value. Default = none
Tick format code	String: Text that defines the tick format. Edit string to change format. You can edit this value only if Tick Format is set to Use Tick Format Code . Default = none

Table D-46: Contour Levels Properties (Continued)

Property	Control Type: Values
Tick format	String List: Choose a format code or time interval to use for each tick interval. Choose from these values: • None • Use Tick Format Code • Filled Fixed Width Integer • Freeform Integer or Float • Float with 2 or 4 decimal places • Exponential with 2 or 4 decimal places • Date (13 formats) • Time (11 formats) Default = None
Text font	String List: Font used for label text. Select a font from the list. Choose from these values: • Helvetica • Courier • Times • Symbol • Hershey Default = Helvetica
Text style	String List: Style used for label text. Select a style from the list. Choose from these values: • Normal • Bold • Italic • Bold italic Default = Normal
Text font size	Number: Font size in points for the label text. Edit the number to change the size. Default = 9

Table D-46: Contour Levels Properties (Continued)

Vector




Figure D-17: Visualization Browser with Vector Properties Displayed

These properties control vector visualizations. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Values
Grid units	String List: Set grid units type. Choose from: • Not applicable • Meters • Degrees Default = Not applicable

Table D-47: Vector Properties

Property	Control Type: Values
Vector style	String List: Set vector style type. Choose between these values: • Arrows • Wind barbs Default = Arrows
Length scale	Number: Length. Enter value. Default = 1
Head size	Number: Head size. Enter value. Default = 1
Arrow style	String List: Set arrow style type. Choose between these values: • Lines • Filled Default = Filled
Proportional heads	Boolean: Make arrow heads proportional? Choose True or False. Default = False
Arrowhead angle	Number: Arrowhead angle value. Enter value. Default = 30
Arrowhead indentation	Number: Arrowhead indentation value. Enter value. Default = 0.4
Arrow thickness	Number: Arrow thickness level. Choose value 1 through 10. Default = 2
Line thickness	Number: Line thickness level. Choose value 1 through 10. Default = 1
Data location	Boolean: Select location along arrow for data. Choose Tail, Center, or Head. Default = Center
Automatic color	Boolean: Select color setting. Choose None, Magnitude, or Direction. Default = Magnitude

Table D-47: Vector Properties (Continued)

Property	Control Type: Values
Color	Color : Color for arrows. Click to choose from the default color palette, or specify RGB values. Default = [0, 0, 0] (black)
Color palette	Color: By selecting Edit color table → Edit access the color table to manipulate vector color values  Note - To edit the opacity only in the editor, uncheck the R, G, and B boxes in both the Modify and Display rows. Edit the remaining line by clicking on and dragging the line in the window. Click OK when finished.
Transparency	Number : Percent transparency. Move slider to change value. Default = 0
Minimum magnitude	Number : minimum magnitude. Enter value. Default = None

Table D-47: Vector Properties (Continued)

Property	Control Type: Values
Maximum magnitude	Number: maximum magnitude. Enter value. Default = None
Z value	Number: Z value of plane on to which to project the vector visualization. Edit the number to change the value. Note - If the Z value is zero then the vector visualization is considered to be 2D. If the Z value is nonzero, then the vector visualization is considered to be 3D, and the dataspace associated with this vector will be automatically switched to 3D. Default = 0
Automatic subsampling	Boolean: Automatically subsample the vector visualization? Choose True or False . Default = False
Subsampling method	String List: Set subsample type. Choose between these values: • Nearest neighbor • Linear Default = Nearest neighbor
X subsampling factor	Number: Subsample factor in the x direction. Default = 1
Y subsampling factor	Number: Subsample factor in the y direction. Default = 1
Mark missing points	Boolean: Automatically mark missing points? Choose True or False . Default = False
Direction convention	Boolean: Choose direction convention. Select Polar , Meteorological , or Wind azimuths . Default = Polar (counterclockwise from X axis)
Missing point symbol	Symbol: Symbol to be used for missing points. Choose a symbol from the list. Default = No symbol for arrow visualizations, Points for wind barb visualization.
Symbol size	Number: Factor from 0 - 1 determining the size of the selected symbol. Move slider to change the size. Default = 0.2

Table D-47: Vector Properties (Continued)

Property	Control Type: Values
Use default color	Boolean: Activate Symbol color property. Choose True or False . Default = False
Symbol color	Color: Color for the selected symbol. Click to choose from the default color palette, or specify RGB values. Default = [0,0,0] (black)

Table D-47: Vector Properties (Continued)

Volume




Figure D-18: Visualization Browser with Volume Properties Displayed

These properties control volume object visualizations. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).


Property	Control Type: Values
Display Scale	Set the display scale for the selected volume. Select Display Scale Bottom/Top → Edit 

Table D-48: Volume Properties


Property	Control Type: Values
Color & Opacity Table 0	Color: By selecting Edit Color → Table Edit access the color table to manipulate plot color values  Note - To edit the opacity only in the editor, uncheck the R, G, and B boxes in both the Modify and Display rows. Edit the remaining line by clicking on and dragging the line in the window. Click OK when finished.
Color & Opacity Table 1	Color: By selecting Edit Color → Table Edit access the color table to manipulate plot color values.

Table D-48: Volume Properties (Continued)


Property	Control Type: Values
Subvolume	String: Edit SubVolume Extents.  The image shows a dialog box titled 'SubVolume Extents Selector'. It contains three sections: 'Volume X Extents', 'Volume Y Extents', and 'Volume Z Extents'. Each section has a horizontal bar with a red vertical line on the left and a green vertical line on the right. Below each bar are two input fields: the first field contains '0' and the second field contains '79' for X, '0' and '99' for Y, and '0' and '56' for Z. At the bottom of the dialog are 'OK' and 'Cancel' buttons.
Auto render	Boolean: Automatically render the volume each time the window is redrawn? Choose True or False. Default = False
Quality	String List: Quality of the volume. Choose between these values: • Low (texture maps) • High (volume) Default = Low
Boundary	String List: Boundary around the volume. Choose between these values: • Off • Wire frame • Solid walls Default = Solid walls

Table D-48: Volume Properties (Continued)

Property	Control Type: Values
Boundary transparency	Number: Percent transparency of the boundary around the volume (wire frame or solid walls). Move slider to change value. Default = 90
Render step X	Number: Stepping factor through the voxel matrix in the x direction. Default = 1
Render step Y	Number: Stepping factor through the voxel matrix in the y direction. Default = 1
Render step Z	Number: Stepping factor through the voxel matrix in the z direction. Default = 1
Extents color	Color: Color for the volume. Click to choose from the default color palette, or specify RGB values. Default = [0 , 0 , 0] (black)
Ambient color	String: Choose from default color palette or specify RGB values. Default = [255 , 255 , 255] (white)
Composite function	String: Choose composite function. Default = Alpha Blending
Acceleration hints	Boolean: Use acceleration hints? Choose Enable or Disable. Default = Disable
Interpolation	String List: Set interpolation type. Choose between these values: • Nearest neighbor • Trilinear Default = Nearest neighbor
Use lighting	Boolean: Use lighting? Choose True or False. Default = False

Table D-48: Volume Properties (Continued)

Property	Control Type: Values
Voxel gradient	Color : Color of the volume. Click to choose from the default color palette, or specify RGB values. Default = [0 , 0 , 0] (black)
Update Z Buffer	Boolean : Update Z Buffer? Choose True or False . Default = True
Skip zero opacity	Boolean : Skip zero opacity? Choose True or False . Default = True

Table D-48: Volume Properties (Continued)

Isosurface




Figure D-19: Visualization Browser with Isosurface Properties Displayed

These properties control isosurface object visualizations. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Values
Color	Color: Color to be used for the isosurface lines in this visualization. Click to choose from the default color palette, or specify RGB values. Default = [0 , 0 , 0] (black)
Linestyle	Line Style: Style of the isosurface lines. Select a line style from the list. Default = No line
Thickness	Line Thickness: Thickness of the isosurface lines in points. Select a thickness from the list. Default = 1

Table D-49: Isosurface Properties

Property	Control Type: Values
Fill background	Boolean: Fill background? Choose True or False . Default = True
Fill color	Color: Color to fill. Click to choose from the default color palette, or specify RGB values. Default = [255, 0, 0] (red)
Transparency	Number: Level of transparency. Default = 0
Source color	String List: Choose from the following: • Isovalue selected (Volume color table) • User selected (Fill Color Property) Default = Isovalue selected (Volume color table)
Isovalue dialog	String: Edit isovalue.
Isovalue	Number: The value for the isosurface, which should be in the range [Min(volume data), Max(volume data)].
Mesh quality	Number: The percent of the isosurface mesh to retain. Default is 100.

Table D-49: Isosurface Properties (Continued)

Interval Volume




Figure D-20: Visualization Browser with Interval Volume Properties Displayed

These properties control interval volume object visualizations. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Values
Color	Color: Color to be used for the interval volume lines in this visualization. Click to choose from the default color palette, or specify RGB values. Default = [0 , 0 , 0] (black)
Linestyle	Line Style: Style of the interval volume lines. Select a line style from the list. Default = No line

Table D-50: Interval Volume Container Properties


Property	Control Type: Values
Thickness	Line Thickness: Thickness of the interval volume lines in points. Select a thickness from the list. Default = 1
Fill background	Boolean: Fill background? Choose True or False. Default = True
Fill color	Color: Color to fill. Click to choose from the default color palette, or specify RGB values. Default = [255, 0, 0] (red)
Transparency	Number: Level of transparency. Default = 0
Source Color	String List: Set source color. Choose from the following: • Isovalue selected (Volume color table) • User selected (Fill Color Property) Default = Isovalue selected (Volume color table)
Isovalue dialog	String: Edit isovalue. 
Isovalue 0	Number: The lower isovalue for the interval volume, which should be in the range [Min(volume data), Max(volume data)].

Table D-50: Interval Volume Container Properties (Continued)

Property	Control Type: Values
Isovalue 1	Number: The upper isovalue for the interval volume, which should be in the range [Min(volume data), Max(volume data)].
Mesh quality	Number: The percent of the interval volume mesh to retain. Default is 100.

Table D-50: Interval Volume Container Properties (Continued)

Image Plane




Figure D-21: Visualization Browser with Image Plane Properties Displayed

These properties control image plane object visualizations. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Values
Opacity Control	String List: Set opacity. Choose from the following: • Use Opacity Table • Opaque • Opacity Value Default = Use Opacity Table
Opacity Value	Number: Factor from 0 - 100 determining the level of opacity. Move slider to change the size. Default = 50

Table D-51: Image Plane Container Properties

Property	Control Type: Values
Orientation	Set orientation. Default = X
Location	Number : The location of the image plane along the associated dimension (either X , Y , or Z depending on orientation). The valid range is from 0 to the size of the associated volume dimension.
Color	Color : Color to be used for the image plane lines in this visualization. Click to choose from the default color palette, or specify RGB values. Default = [255, 255, 255] (white)
Bottom color	Color : Color to be used for the image plane bottom color in this visualization. Click to choose from the default color palette, or specify RGB values. Default = [255, 255, 255] (white)
Linestyle	Line Style : Style of lines used for constructing the surface. Select a style from the list. Default = _____ (solid line)
Thickness	Line Thickness : Thickness of lines used for constructing the surface. Select a thickness from the list. Default = 1
Style	Style : Style of lines used. Choose from the following: • Points • Lines • Filled Default = Filled
Depth offset	Number : Set depth offset value. Enter value. Default = 1
Remove hidden	Boolean : Remove hidden? Choose True or False . Default = False

Table D-51: Image Plane Container Properties (Continued)

Property	Control Type: Values
Skip zero opacity	Boolean: Skip zero opacity? Choose True or False . Default = True
Polygon rejection	String List: Hide polygons based on their orientation. Choose from the following: • None • Normals point away • Normals point toward Default = None Note - Polygon rejection has no effect on non-filled polygons (where Style is Points or Lines).
Shading	String List: Shading method. Select a method from the list. Choose between these values: • Flat: Flat shading • Gouraud: Gouraud shading Default = Flat
Texture interpolation	String List: Set texture interpolation type. Choose between these values: • Nearest neighbor • Bilinear Default = Nearest neighbor

Table D-51: Image Plane Container Properties (Continued)

Colorbar




Figure D-22: Visualization Browser with Colorbar Properties Displayed

These properties control colorbar object visualizations. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Values
Border	Boolean: Set border on or off. Choose True or False . Default = False
Orientation	Boolean: Set orientation of colorbar. Choose Horizontal or Vertical . Default = Horizontal
Color	Color: Color to be used for the colorbar in this visualization. Click to choose from the default color palette, or specify RGB values. Default = [0 , 0 , 0] (black)
Line style	Line Style: Style of the colorbar lines. Select a line style from the list. Default =  (solid line)
Line thickness	Line Thickness: Thickness of the colorbar lines in points. Select a thickness from the list. Default = 1
Major ticks	Number: Set number of major tick marks. Enter value. Default = 3
Minor ticks	Number: Set number of minor tick marks. Enter value. Default = 0
Major tick length	Number: Factor from 0 - 1 determining major tick length. Move slider to change the size. Default = .05
Minor tick length	Number: Factor from 0 - 1 determining minor tick length. Move slider to change the size. Default = 1
Tick interval	Number: Set tick interval. Enter value. Default = 0

Table D-52: Colorbar Container Properties

Property	Control Type: Values
Tick layout	String List: Set tick layout type. Choose between these values: • Axis plus labels • Labels only • Box style Default = Axis plus labels
Tick direction	String List: Set tick direction. Choose between these values: • Right/Above • Left/Below Default = Right/Above
Logarithmic axis	Default = false
Text show	Boolean: Set text to show or not show. Choose True or False. Default = True (show)
Text position	String List: Set text position. Choose between these values: • Below/left • Above/right Default = Below/left
Tick format code	Shows the code for the tick format selected. Default = empty
Tick format	String List: Choose a format code or time interval to use for each tick interval. Choose from these values: • None • Use Tick Format Code • Filled Fixed Width Integer • Freeform Integer or Float • Float with 2 or 4 decimal places • Exponential with 2 or 4 decimal places • Date (13 formats) • Time (11 formats) Default = None

Table D-52: Colorbar Container Properties (Continued)

Property	Control Type: Values
Title	Title: Enter title for colorbar. Default = RGB Table 0
Text color	Color: Color to be used for the legend text. Click to choose from the default color palette, or specify RGB values. Default = [0, 0, 0] (black)
Text font	String List: Font used for legend text. Select a font from the list. Choose from these values: • Helvetica • Courier • Times • Symbol • Hershey 3 Simplex In addition to the above standard fonts, you will also have available all of the other Hershey fonts as well as any TrueType fonts available to IDL. Default = Helvetica
Text style	String List: Style used for legend text. Select a style from the list. Choose from these values: • Normal • Bold • Italic • Bold italic Default = Normal
Text font size	Number: Font size in points for the legend text. Edit the number to change the size. Default = 12

Table D-52: Colorbar Container Properties (Continued)

Histogram




Figure D-23: Visualization Browser with Histogram Properties Displayed

These properties control histogram object visualizations. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).


Property	Control Type: Values
Vertex Colors Color Table	Color: By selecting Edit Color → Table Edit access the color table to manipulate plot color values 
Histogram binsize	Number: Set histogram binsize. Default = 1
Color	Color: Color to be used for the plot lines. RGB values are assigned or you may edit your color. Default = varies

Table D-53: Histogram Container Properties


Property	Control Type: Values
Line style	Line Style: Style of the colorbar lines. Select a line style from the list. Default =  (solid line)
Thickness	Line Thickness: Thickness of the colorbar lines in points. Select a thickness from the list. Default = 1
Minimum value	Number: Minimum histogram value. Enter a number. Default = varies
Maximum value	Number: Maximum histogram value. Enter a number. Default = varies
Histogram plot	Boolean: Set histogram to show or not show. Choose True or False . Default = True (show)
Number of points to average	Number: Number of points in plot to be averaged. Enter a number. Default = 1
Polar plot	Boolean: Set histogram to show or not show as a polar plot. Choose True or False . Default = False (hide)
Fill plot	Boolean: Set histogram to show or not show as a filled plot. Choose True or False . Default = False (hide)
Fill level	Number: Level to fill if fill plot is selected. Enter a number. Default = varies
Fill color	Color: Color to be used for fill plot if selected. Default = [128, 128, 128] (grey)

Table D-53: Histogram Container Properties (Continued)

Property	Control Type: Values
Fill transparency	Number: Value of transparency if fill plot is selected. Enter a number. Default = 0
Symbol	String List: Font used for legend text. Select a font from the list. Choose from the list of symbols. Default = No symbol
Symbol size	Number: Value for symbol size in points if fill symbol is selected. Enter a number. Default = 0.2
Use default color	Boolean: Set to use default color for symbols. Choose True or False . Default = True (use default color)
Symbol color	Color: Color to be used for symbols if default color is set to False. Enter a value. Default = varies
Symbol thickness	Number: Value for symbol thickness in points if symbol is selected. Enter a number. Default = 1
Symbol increment	Number: Value for symbol increments if fill symbol is selected. Enter a number. Default = 1

Table D-53: Histogram Container Properties (Continued)

Axes




Figure D-24: Visualization Browser with Axis Properties Displayed

These properties control axis object visualizations. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

The following table contains the properties that control the container for the visualization axes.

Property	Control Type: Values
Style	String List: Select display style for axes. Choose from these values: • None: Do not display axes. • At Dataspace Minimum: Display 2 axes for 2-D visualization, 3 axes for 3-D visualization. • Box Axes: Display 4 axes for 2-D visualization, 12 axes for 3-D visualization. • Crosshairs: Display crosshair style axes. Default = At Dataspace Minimum
Lock to Data	Boolean: Locks axis (axes) to data. Default = False
Transparency	Number: Adjusts transparency of axis (axes). Default = 0
Color	Color: Color to be used for the axis lines in this visualization. Click to choose from the default color palette, or specify RGB values. Default = [0 , 0 , 0] (black)
Line style	Line Style: Style of the axis tick lines. Select a line style from the list. Default =  (solid line)
Line thickness	Line Thickness: Thickness of the axis tick lines. Select a thickness from the list. Default = 1
Major ticks	Number: Set number of major tick marks. Enter value. Default = 0
Minor ticks	Number: Set number of minor tick marks. Enter value. Default = 0

Table D-54: Axes Container Properties

Property	Control Type: Values
Major Tick Length	Number : Normalized length of major tick marks for all axes from 0 (no ticks) to 1 (major tick marks span the visualization). Move the slider to change the value. Default = 0.05.
Minor tick length	Number : Relative length of minor tick marks for all axes from -1 (minor tick marks extend the length of major tick marks on left side of axes) to 1 (minor tick marks extend same length as major tick marks on right side of axes). Move the slider to change the value. Default = 0.5 (minor tick marks extend one-half the length of major tick marks on right side of axes).
Tick interval	Number : Interval between ticks. Edit the number to change the value. Default = 0
Tick layout	String List : Select layout style for major and minor tick visualization on all axes. Choose from these values: • Axis plus labels: Display tick labels and marks. • Labels only: Display tick labels only (no tick marks). • Box style: Display tick labels and marks, with labels enclosed in boxes. Default = Axis plus labels
Tick direction	String List : Select a direction for tick marks. Choose from these values: • Right/Above: Place tick marks to the right of or above the axis line. • Left/Below: Place text to the left of or below the axis line. Default = Right/Above
Text show	Boolean : Set text to show or not show. Choose True or False . Default = True (show)

Table D-54: Axes Container Properties (Continued)

Property	Control Type: Values
Text position	String List: Select a position for tick and label text. Choose from these values: • Below/left: Place text below or to the left of the axis line. • Above/right: Place text above or to the right of the axis line. Default = Below/left
Tick format code	String: A string defining the format of the tick annotation information. The format code should be enclosed in parentheses, and should conform to one of the formats described in “Format Codes” (Chapter 18, <i>Application Programming</i>). This field always displays the current format code, but is only available for editing if Use Tick Format Code is selected as the value of the Tick format property.
Tick format	String List: Choose a format code or time interval to use for each tick interval. Choose from these values: • None • Use Tick format code • Filled Fixed Width Integer • Freeform Integer or Float • Float with 2 or 4 decimal places • Exponential with 2 or 4 decimal places • Date (13 formats) • Time (11 formats) Default = None
Title	String: Title to apply to all axes for this visualization. Enter title text for the axes. No default value.
Text color	Color: Color to be used for the text. Click to choose from the default color palette, or specify RGB values. Default = [0, 0, 0] (black)

Table D-54: Axes Container Properties (Continued)

Property	Control Type: Values
Text font	String List: Font used for tick and label text. Select a font from the list. Choose from these values: • Helvetica • Courier • Times • Symbol • Hershey 3 Simplex In addition to the above standard fonts, you will also have available all of the other Hershey fonts as well as any TrueType fonts available to IDL. Default = Helvetica
Text style	String List: Style used for tick and label text. Select a style from the list. Choose from these values: • Normal • Bold • Italic • Bold italic Default = Normal
Text font size	Number: Font size in points for the tick and label text. Edit the number to change the size. Default = 12

Table D-54: Axes Container Properties (Continued)

This table contains the properties that control axis visualization X, Y, or (for three-dimensional visualizations) Z. For each property, the type of control and the values

that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Values
Color	Color: Color to be used for the axis line. Click to choose from the default color palette, or specify RGB values. Default = [0 , 0 , 0] (black)
Line style	Line Style: Style of the axis tick lines. Select a line style from the list. Default = ————— (solid line)
Line thickness	Line Thickness: Thickness of the axis tick lines in points. Select a thickness from the list. Default = 1
Major ticks	Number: Number of major ticks marks to display along the axis. Edit the number to change the value. Default = 5
Minor ticks	Number: Number of minor ticks to display between major ticks. Edit the number to change the value. Default = 3
Major tick length	Number: Normalized length of major tick marks for this axis from 0 (no ticks) to 1 (major tick marks span the visualization). Move the slider to change the value. Default = 0 . 05
Minor tick length	Number: Relative length of minor tick marks for this axis from -1 (minor tick marks extend the length of major tick marks on left side of axis) to 1 (minor tick marks extend same length as major tick marks on right side of axis). Move the slider to change the value. Default = 0 . 5 (Minor tick marks extend one-half the length of major tick marks on right side of axis).
Tick interval	Number: Interval between major tick marks. Edit the number to change the value. Default = 0 (use the default interval for the specified range)

Table D-55: Property Settings for Individual Axes

Property	Control Type: Values
Tick layout	String List: Select layout style for major and minor tick visualization. Choose from these values: • Axis plus labels: Display tick labels and marks. • Labels only: Display tick labels only (no tick marks). • Box style: Display tick labels and marks, with labels enclosed in boxes. Default = Axis plus labels
Tick direction	String List: Select a direction for tick marks. Choose from these values: • Right/Above: Place tick marks to the right of or above the axis line. • Left/Below: Place text to the left of or below the axis line. Default = Right/Above
Text show	Boolean: Show tick and label text? Choose True or False. Default = True.
Text position	String List: Select a position for tick and label text. Choose from these values: • Below/left: Place text below or to the left of the axis line. • Above/right: Place text above or to the right of the axis line. Default = Below/left
Tick format code	String: A string defining the format of the tick annotation information. The format code should be enclosed in parentheses, and should conform to one of the formats described in “Format Codes” (Chapter 18, <i>Application Programming</i>). This field always displays the current format code, but is only available for editing if Use Tick Format Code is selected as the value of the Tick format property.

Table D-55: Property Settings for Individual Axes (Continued)

Property	Control Type: Values
Tick format	String List: Choose a format code or time interval to use for each tick interval. Choose from these: • None • Use Tick format code • Filled Fixed Width Integer • Freeform Integer or Float • Float with 2 or 4 decimal places • Exponential with 2 or 4 decimal places • Date (13 formats) • Time (11 formats) Default = None
Title	String: Title to apply to this axis. Enter title text for the axes. No default value.
Text color	Color: Color to be used for the text. Click to choose from the default color palette, or specify RGB values. Default = [0 , 0 , 0] (black)
Text font	String List: Font used for tick and label text. Select a font from the list. Choose from these values: • Helvetica • Courier • Times • Symbol • Hershey Default = Helvetica

Table D-55: Property Settings for Individual Axes (Continued)

Property	Control Type: Values
Text style	String List: Style used for tick and label text. Select a style from the list. Choose from these values: • Normal • Bold • Italic • Bold italic Default = Normal
Text font size	Number: Font size in points for the tick and label text. Edit the number to change the size. Default = 12

Table D-55: Property Settings for Individual Axes (Continued)

Lights




Figure D-25: Visualization Browser with Light Properties Displayed

Lights properties control the lighting of the data space. These properties are available only for 3-D Surface and Volume visualizations.

Three types of lights can be configured through the Lights properties: Ambient Light, Light 1 (from above), and Light 2 (from below). Each type of light has the same set of properties, as described in [Table D-56](#).

For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Values
Type	String List: Type of light source for this light. Select a type of light from the list. Choose from these options: • Ambient: Universal light source with no direction or position. An ambient light illuminates every surface in the scene equally, which means that no edges are made visible by contrast. Ambient light controls the overall brightness and color of the scene. • Positional: Supplies divergent light rays so that the edges of surfaces can be made visible by contrast. A positional light source can be located anywhere in the scene. • Directional: Supplies parallel light rays from a light source located at an infinite distance from scene. • Spotlight: Illuminates only a specific area defined by the light's position, direction, and the <i>cone angle</i> (angle the spotlight covers). Default = Positional
Distance	Number: Distance of the light source from the visualization from -1 (in front of the visualization) to 1 (behind the visualization). Move the slider to change the value. Default = -1 for Ambient Light and Light 1, 1 for Light 2
Intensity	Number: Intensity of this light from 0 (no light) to 1 (bright light). Move the slider to change the value. Default = 0.5 for Ambient Light, 0.8 for Light 1 and Light 2
Color	Color: Color of this light. Click to choose from the default color palette, or specify RGB values. Default = [255, 255, 255] (white)

Table D-56: Property Settings for Lights

Property	Control Type: Values
Cone angle	Number : Angle the spotlight covers from 0° to 180°. Active only when Spotlight type is selected. Move the slider to change the value. Default = 60
Focus attenuation	Number : Floating-point value from 0 to 128 that attenuates the intensity of spotlights as the distance from the center of the cone of coverage increases. This factor is used as an exponent to the cosine of the angle between the direction of the spotlight and the direction from the light to the vertex being lighted. Active only when Spotlight type is selected. Move the slider to change the value. Default = 0

Table D-56: Property Settings for Lights (Continued)

Polygonal ROI




Figure D-26: Visualization Browser with Polygon ROI Properties Displayed

These properties control polygonal ROI object visualizations. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#)

Property	Control Type: Values
Color	Color: Color to be used for the line. Click to choose from the default color palette, or specify RGB values. Default = [0 , 0 , 0] (black)
Linestyle	Line Style: Style of the polygon lines. Select a line style from the list. Default = ————— (solid line)
Thickness	Line Thickness: Thickness of the polygon lines in points. Select a thickness from the list. Default = 1
Fill background	Boolean: Fill background? Choose True or False . Default = True

Table D-57: Property Settings for Polygonal ROI

Property	Control Type: Values
Fill color	Color: Color to fill. Click to choose from the default color palette, or specify RGB values. Default = [255,255, 255] (white)
Transparency	Number: Level of transparency. Default = 0

Table D-57: Property Settings for Polygonal ROI (Continued)

IDL Graphics Objects




Figure D-27: Visualization Browser with IDL Graphics Object Properties Displayed

You can import an IDL graphics object into an iTool and display it directly by selecting the “IDL Graphics Object” visualization type. The properties available will depend on the type of graphics object. See the properties listing for the specific graphics object in the *IDL Reference Guide* for details.

Note

The behavior of IDL graphics objects imported into an iTool may not be the same as that of the corresponding iTool visualization. While importing an existing graphics object into an iTool will often work, you will generally obtain better results using an iTool visualization type.

Tip

In order to display properties for a generic IDL graphics object in the iTool property sheet interface, the graphics object must have been created with the `REGISTER_PROPERTIES` keyword set. If no properties are registered, only the three standard iTool properties (Name, Description, and Show) will be present, as displayed in the previous figure.

Map Grid




Figure D-28: Visualization Browser with Map Grid Object Properties Displayed

These properties control map grid object visualizations. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).


Name	Description
Automatic grid	Boolean: Automatically compute the grid range and spacing. Choose True or False. Default = True Note - If a SAVE file is restored from an IDL version prior to 6.2, this property is set to False.
Longitude minimum (deg)	Number: Minimum longitude, in degrees, to include in the grid
Longitude maximum (deg)	Number: Maximum longitude, in degrees, to include in the grid
Latitude minimum (deg)	Number: Minimum latitude, in degrees, to include in the grid
Latitude maximum (deg)	Number: Maximum latitude, in degrees, to include in the grid
Longitude spacing	Number: Longitude grid spacing, in degrees
Latitude spacing	Number: Latitude grid spacing, in degrees
Longitude lines	User Defined: Click to edit individual or all longitude line properties. Click  and Edit... to display the Map Grid Lines dialog. 

Table D-58: Property Settings for Map Grid


Name	Description
Latitude lines	User Defined: Click to edit individual or all latitude line properties. Click  and Edit... to display the Map Grid Lines dialog. 
Color	Color: Color for the grid lines. Click to choose from the default color palette, or specify RGB values. Default = [0 , 0 , 0] (black)
Thickness	Line Thickness: Thickness for the grid lines. Select a thickness from the list. Default = 1
Transparency	Number: Transparency of the grid lines from 0% to 100%. Move the slider to change the value. Default = 0
Label	Boolean: Use labels on the grid lines. Choose True or False . Default = True
Label position	Number: Normalized label position. Default = 0 . 5
Use label color	Boolean: Use default color instead of Label color. Choose True or False . Default = False
Label color	Color: Color for the grid label. Click to choose from the default color palette, or specify RGB values. Default = [0 , 0 , 0] (black)

Table D-58: Property Settings for Map Grid (Continued)

Name	Description
Label fill background	String List: Choose the kind of fill background for the label. Choose from these values: • None • View color • Fill color
Label fill color	Color: Color for the label background's fill. Click to choose from the default color palette, or specify RGB values. Default = [255, 255, 255] (white)
Z value	Number: Z value of plane on to which to project the map visualization. Edit the number to change the value. Note - If the Z value is zero then the map visualization is considered to be 2D. If the Z value is nonzero, then the map visualization is considered to be 3D, and the dataspace associated with this map will be automatically switched to 3D. Default = 0
Text font	String List: Font used for label text. Select a font from the list. Choose from these values: • Helvetica • Courier • Times • Symbol • Hershey 3 Simplex In addition to the above standard fonts, you will also have available all of the other Hershey fonts as well as any TrueType fonts available to IDL. Default = Helvetica

Table D-58: Property Settings for Map Grid (Continued)

Name	Description
Text style	String List : Style used for label text. Select a style from the list. Choose from these values: • Normal • Bold • Italic • Bold italic Default = Normal
Text font size	Number : Font size in points for the label text. Edit the number to change the size. Default = 12

Table D-58: Property Settings for Map Grid (Continued)

The Map Grid Lines dialog displays a property sheet for the longitude or latitude lines, depending on which set you want to edit. This sheet includes the same properties as the overall Map Grid object, from Color to Text font size.

ShapePolygon




Figure D-29: Visualization Browser with ShapePolygon Properties Displayed

These properties control ShapePolygon visualizations. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Name	Description
Color	Color: Color for the ShapePolygon line. Click to choose from the default color palette, or specify RGB values. Default = [0 , 0 , 0] (black)
Line style	Line Style: Style for the ShapePolygon line. Select a style from the list. Default = _____ (solid line)
Thickness	Line Thickness: Thickness for the ShapePolygon line. Select a thickness from the list. Default = 1
Fill background	Boolean: Fill background? Choose True or False . Default = False

Table D-59: Property Settings for ShapePolygon

Name	Description
Fill color	Color: Color for the ShapePolygon fill. Click to choose from the default color palette, or specify RGB values. Default = [255, 255, 255] (white)
Z value	Number: Z value of plane on to which to project the shape polygon visualization. Edit the number to change the value. Note - If the Z value is zero then the shape polygon visualization is considered to be 2D. If the Z value is nonzero, then the shape polygon visualization is considered to be 3D, and the dataspace associated with this shape polygon will be automatically switched to 3D. Default = 0
Transparency	Number: Transparency of the ShapePolygon fill from 0% to 100%. Move the slider to change the value. Default = 0

Table D-59: Property Settings for ShapePolygon (Continued)

ShapePolyline




Figure D-30: Visualization Browser with ShapePolyline Properties Displayed

These properties control ShapePolyline visualizations. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Name	Description
Transparency	Number: Transparency of the ShapePolyline from 0% to 100%. Move the slider to change the value. Default = 0
Color	Color: Color for the ShapePolyline. Click to choose from the default color palette, or specify RGB values. Default = [0,0,0] (black)
Line style	Line Style: Style for the ShapePolyline. Select a style from the list. Default = _____ (solid line)

Table D-60: Property Settings for ShapePolyline

Name	Description
Thickness	Line Thickness: Thickness for the ShapePolyline. Select a thickness from the list. Default = 1
Z value	Number: Z value of plane on to which to project the shape polyline visualization. Edit the number to change the value. Note - If the Z value is zero then the shape polyline visualization is considered to be 2D. If the Z value is nonzero, then the shape polyline visualization is considered to be 3D, and the dataspace associated with this shape polyline will be automatically switched to 3D. Default = 0

Table D-60: Property Settings for ShapePolyline (Continued)

ShapePoint

These properties control ShapePoint visualizations. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Name	Description
Symbol	Symbol: Symbol to represent each ShapePoint. Choose a symbol from the list. Default = No symbol
Symbol size	Number: Factor from 0 to 1 determining the size of the selected symbol. Move slider to change the size. Default = 0.2
Symbol color	Color: Color for the selected symbol. Click to choose from the default color palette, or specify RGB values. Default = [0, 0, 0] (black)
Symbol thickness	Number: Symbol thickness from 1 to 9.9 for the selected symbol. Move slider to change the thickness. Default = 1.
Transparency	Number: Transparency of the ShapePoint fill from 0% to 100%. Move the slider to change the value. Default = 0

Table D-61: Property Settings for ShapePoint

Streamlines

These properties control Streamline visualizations. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#)

Name	Description
Grid units	String List: Set grid units type. Choose from: • Not applicable • Meters • Degrees Default = Not applicable
Head size	Number: Head size. Enter value. Default = 1
Line thickness	Number: Line thickness level. Choose value 1 through 10. Default = 1
Automatic color	String List: Select color setting. Choose None, Magnitude, or Direction. Default = None
Color	Color: Color for arrows. Click to choose from the default color palette, or specify RGB values. Default = [0 , 0 , 0] (black)

Table D-62: Property Settings for Streamlines


Name	Description
Color palette	Color: By selecting Edit color table → Edit access the color table to manipulate vector color values  Note - To edit the opacity only in the editor, uncheck the R, G, and B boxes in both the Modify and Display rows. Edit the remaining line by clicking on and dragging the line in the window. Click OK when finished.
Transparency	Number: Percent transparency. Move slider to change value. Default = 0

Table D-62: Property Settings for Streamlines (Continued)

Name	Description
Z value	Number: Z value of plane on to which to project the vector visualization. Edit the number to change the value. Note - If the Z value is zero then the vector visualization is considered to be 2D. If the Z value is nonzero, then the vector visualization is considered to be 3D, and the dataspace associated with this vector will be automatically switched to 3D. Default = 0
Direction convention	String List: Choose direction convention. Select Polar, Meteorological, or Wind azimuths. Default = Polar (counterclockwise from X axis)
X stream particles	Number: Number of X stream particles. Choose value. Default = 25
Y stream particles	Number: Number of X stream particles. Choose value. Default = 25
Streamline steps	Number: Number of streamline steps. Choose value (minimum value is 2). Default = 100
Streamline step size	Number: Numeric value for streamline step size. Enter value. Default = 0.2

Table D-62: Property Settings for Streamlines (Continued)

2D Annotation Layer Properties

The Annotation layer appears in the Visualization browser.




Figure D-31: Visualization Browser with Annotation Properties Displayed

The following types of annotations can be added to iTool visualizations: Text, Line, Line Profile, Rectangle, Oval, Polygon, and Freehand annotations. The following table contains properties that control the Annotation layer. Subsequent tables describe the properties specific to each type of annotation.

Property	Control Type: Values
Background color	Color: Color to be used for the Annotation Layer background. For background to display, Transparent property must be set to False . Click to choose from the default color palette, or specify RGB values. Default = [255,255,255] (white)
Transparent	Boolean: Make the annotation layer transparent? Choose True or False . Default = True

Table D-63: Annotation Layer Properties

Text Annotation Properties

These properties control text annotation visualizations. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Values
Text string	String: Text that appears in the annotation. Edit to change the text, or to add formatting commands such as the following: • !C: Add new line. • !U: Add superscript characters. • !D: Add subscript characters. • !N: Return to normal characters. For a complete list of embedded text formatting commands, refer to “Embedded Formatting Commands” (Appendix H, <i>IDL Reference Guide</i>). No default value.
Horizontal alignment	String List: Horizontal alignment of multiple lines within text box. Choose from these values: • Left: Align text along the left border of the text box. • Center: Align text in the center of the text box. • Right: Align text along the right border of the text box. Default = Left
Color	Color: Color to be used for the text. Click to choose from the default color palette, or specify RGB values. Default = [0 , 0 , 0] (black)
Fill background	Boolean: Fill the background of the text with the background color? Choose True or False. Default = False
Transparency	Number: Transparency of the text annotation from 0% to 100%. Move the slider to change the value. Default = 0

Table D-64: Text Annotation Properties

Property	Control Type: Values
Text font	String List: Font used for text annotation. Select a font from the list. Choose from these values: • Helvetica • Courier • Times • Symbol • Hershey 3 Simplex In addition to the above standard fonts, you will also have available all of the other Hershey fonts as well as any TrueType fonts available to IDL. Default = Helvetica
Text style	String List: Style used for text annotation. Select a style from the list. Choose from these values: • Normal • Bold • Italic • Bold italic Default = Normal
Text font size	Number: Font size in points for the text annotation. Edit the number to change the size. Default = 12

Table D-64: Text Annotation Properties (Continued)

Line Profile Annotation Properties

These properties control line profile annotation visualizations. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).


Property	Control Type: Values
Vertex Colors Color Table	User Defined: By selecting Edit Color → Table Edit access the color table to manipulate plot color values 
Color	Color: Color to be used for the line. Click to choose from the default color palette, or specify RGB values. Default = [0 , 0 , 0] (black)
Line style	Line Style: Style of the line profile annotation. Select a line style from the list. Default = _____ (solid line)

Table D-66: Line Profile Annotation Properties

Property	Control Type: Values
Thickness	Line Thickness: Thickness of the line profile annotation in points. Select a thickness from the list. Default = 1
Minimum value	Number: Minimum value for line profile. Edit number to change value. No default value.
Maximum value	Number: Maximum value for line profile. Edit number to change value. No default value.
Histogram plot	Boolean: Show line profile as a histogram plot? Choose True or False . Default = False
Number of points to average	Number: Set number of points to average. Enter a value. Default = 1
Polar plot	Boolean: Show line profile as a polar plot? Choose True or False . Default = False
Fill plot	Boolean: Fill plot? Choose True or False . Default = False
Fill level	Number: Set level to fill. Enter value. Default = 71
Fill color	Color: Color used for fill. For color to display, Fill Plot property must be set to True . Click to choose from the default color palette, or specify RGB values. Default = [255, 255, 255] (white)
Fill transparency	Number: Transparency of the plot fill from 0% to 100%. Move the slider to change the value. Default = 0
Symbol	Symbol: Symbol to appear at regular intervals on the plot line. Choose a symbol from the list. Default = No symbol
Symbol size	Number: Factor from 0 - 1 determining the size of the selected symbol. Move slider to change the size. Default = 0.2

Table D-66: Line Profile Annotation Properties (Continued)

Property	Control Type: Values
Use default color	Boolean: Activate Symbol color property. Choose True or False . Default = False
Symbol color	Color: Color for the selected symbol. Click to choose from the default color palette, or specify RGB values. Default = [0 , 0 , 0] (black)
Symbol thickness	Number: Line thickness from 1 - 9.9 for the selected symbol. Move slider to change the thickness. Default = 1.
Symbol increment	Number: Interval at which symbols will be displayed on the plot line. Influenced by Number of points to average (above). Edit to change the value. Default = 1

Table D-66: Line Profile Annotation Properties (Continued)

Rectangle Annotation Properties

These properties control rectangle annotation visualizations. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Values
Color	Color: Color to be used for the rectangle outline. Click to choose from the default color palette, or specify RGB values. Default = [0 , 0 , 0] (black)
Linestyle	Line Style: Style of the rectangle outline. Select a line style from the list. Default = ————— (solid line)
Thickness	Line Thickness: Thickness of the rectangle outline in points. Select a thickness from the list. Default = 1
Fill background	Boolean: Fill rectangle background? Choose True or False . Default = True
Fill color	Color: Color to be used for the background. For background color to display, Fill Background property must be set to True . Click to choose from the default color palette, or specify RGB values. Default = [255 , 255 , 255] (white)
Transparency	Number: Transparency of the rectangle background fill from 0% to 100%. Move the slider to change the value. Default = 0

Table D-67: Rectangle Annotation Properties

Oval Annotation Properties

These properties control oval annotation visualizations. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Values
Color	Color: Color to be used for the oval outline. Click to choose from the default color palette, or specify RGB values. Default = [0,0,0] (black)
Linestyle	Line Style: Style of the oval outline. Select a line style from the list. Default = ————— (solid line)
Thickness	Line Thickness: Thickness of the oval outline in points. Select a thickness from the list. Default = 1
Fill background	Boolean: Fill oval background? Choose True or False . Default = True
Fill color	Color: Color to be used for the background. For background color to display, Fill Background property must be set to True . Click to choose from the default color palette, or specify RGB values. Default = [255,255,255] (white)
Transparency	Number: Transparency of the oval background fill from 0% to 100%. Move the slider to change the value. Default = 0

Table D-68: Oval Annotation Properties

Polygon Annotation Properties

These properties control polygon annotation visualizations. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Values
Color	Color : Color to be used for the polygon outline. Click to choose from the default color palette, or specify RGB values. Default = [0 , 0 , 0] (black)
Linestyle	Line Style : Style of the polygon outline. Select a line style from the list. Default = ————— (solid line)
Thickness	Line Thickness : Thickness of the polygon outline in points. Select a thickness from the list. Default = 1
Fill background	Boolean : Fill polygon background? Choose True or False . Default = True
Fill color	Color : Color to be used for the background. For background color to display, Fill Background property must be set to True . Click to choose from the default color palette, or specify RGB values. Default = [255 , 255 , 255] (white)
Transparency	Number : Transparency of the polygon background fill from 0% to 100%. Move the slider to change the value. Default = 0

Table D-69: Polygon Annotation Properties

Freehand Annotation Properties

These properties control freehand annotation visualizations. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Values
Color	Color: Color to be used for the freehand shape outline. Click to choose from the default color palette, or specify RGB values. Default = [0 , 0 , 0] (black)
Linestyle	Line Style: Style of the freehand shape outline. Select a line style from the list. Default = ————— (solid line)
Thickness	Line Thickness: Thickness of the freehand shape outline in points. Select a thickness from the list. Default = 1
Fill background	Boolean: Fill freehand shape background. Choose True or False . Default = True
Fill color	Color: Color to be used for the background. For background color to display, Fill Background property must be set to True . Click to choose from the default color palette, or specify RGB values. Default = [255 , 255 , 255] (white)
Transparency	Number: Transparency of the freehand background fill from 0% to 100%. Move the slider to change the value. Default = 0

Table D-70: Freehand Annotation Properties

Legend Properties

These properties control legend annotations. For each property, the type of control and the values that can be assigned are listed. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).




Figure D-32: Visualization Browser with Legend Properties Displayed

Note

This section discusses the properties of the legend container, which can contain multiple legend items of different types. The individual legend types are described in:

- “Legend Contour Items” on page 527
- “Legend Contour Level Items” on page 528
- “Legend Plot Items” on page 530
- “Legend Surface Items” on page 531

Property	Control Type: Values
Layout	String List: Arrange the legend elements in columns or rows. Select a layout from the list. Choose from these values: • Columns • Rows Default = Columns
Sample width	Number: Width in normalized units of the element sample that appears in the legend box. Range = 0.0 to 0.5. Move the slider to change the value. Default = 0.15
Horizontal spacing	Number: Space in normalized units between samples and text in the legend box. Range = 0.0 to 0.25. Move the slider to change the value. Default = 0.02
Vertical spacing	Number: Space in normalized units between lines in the legend box. Move the slider to change the value. Default = 0.02
Text color	Color: Color to be used for the legend text. Click to choose from the default color palette, or specify RGB values. Default = [0,0,0] (black)
Text font	String List: Font used for legend text. Select a font from the list. Choose from these values: • Helvetica • Courier • Times • Symbol • Hershey 3 Simplex In addition to the above standard fonts, you will also have available all of the other Hershey fonts as well as any TrueType fonts available to IDL. Default = Helvetica

Table D-71: Legend Properties

Property	Control Type: Values
Text style	String List: Style used for legend text. Select a style from the list. Choose from these values: • Normal • Bold • Italic • Bold italic Default = Normal
Text font size	Number: Font size in points for the legend text. Edit the number to change the size. Default = 10
Color	Color: Color to use for the legend border. Legend object must be deselected for border attributes to be visible. Click to choose from the default color palette, or specify RGB values. Default = [0, 0, 0] (black)
Linestyle	Line Style: Style of the legend border. Select a line style from the list. Default = ————— (solid line)
Thickness	Line Thickness: Thickness of the legend border in points. Select a thickness from the list. Default = 1
Fill background	Boolean: Fill legend background? Choose True or False. Default = True
Fill color	Color: Color to be used for the background. For background color to display, Fill Background property must be set to True. Click to choose from the default color palette, or specify RGB values. Default = [255, 255, 255] (white)
Transparency	Number: Transparency of the background fill from 0% to 100% Move the slider to change the value. Default = 0%

Table D-71: Legend Properties (Continued)

Legend Contour Items

The following are properties of the top-level Contour legend item. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Values
Show Levels	Boolean: Show contour levels in the legend. Choose True or False . Default = True
Text	String: Text that labels the contour object in the legend.
Text color	Color: Color to be used for the legend text. Click to choose from the default color palette, or specify RGB values. Default = [0, 0, 0] (black)
Text font	String List: Font used for legend text. Select a font from the list. Choose from these values: • Helvetica • Courier • Times • Symbol • Hershey 3 Simplex In addition to the above standard fonts, you will also have available all of the other Hershey fonts as well as any TrueType fonts available to IDL. Default = Helvetica
Text style	String List: Style used for legend text. Select a style from the list. Choose from these values: • Normal • Bold • Italic • Bold italic Default = Normal
Text font size	Number: Font size in points for the legend text. Edit the number to change the size. Default = 12

Table D-72: Contour Legend Properties

Legend Contour Level Items

The following are properties of individual Contour level legend items. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#)

Property	Control Type: Values
Text	String : Text that labels the contour in the legend.
Text color	Color : Color to be used for the legend text. Click to choose from the default color palette, or specify RGB values. Default = [0, 0, 0] (black)
Use text from	String List : Choose a source for the legend text. Choose from these values: • Level value • Level label • User defined Default = Level value
Text format code	String : Text that defines the text format. Edit string to change format. You can edit this value only if Text Format is set to Use Text Format Code . Default = none
Text format	String List : Choose a format code or time interval to use for each legend item. Choose from these values: • None • Use Text Format Code • Filled Fixed Width Integer • Freeform Integer or Float • Float with 2 or 4 decimal places • Exponential with 2 or 4 decimal places • Date (13 formats) • Time (11 formats) Default = None

Table D-73: Contour Level Legend Properties

Property	Control Type: Values
Text font	String List: Font used for legend text. Select a font from the list. Choose from these values: • Helvetica • Courier • Times • Symbol • Hershey 3 Simplex In addition to the above standard fonts, you will also have available all of the other Hershey fonts as well as any TrueType fonts available to IDL. Default = Helvetica
Text style	String List: Style used for legend text. Select a style from the list. Choose from these values: • Normal • Bold • Italic • Bold italic Default = Normal
Text font size	Number: Font size in points for the legend text. Edit the number to change the size. Default = 12

Table D-73: Contour Level Legend Properties (Continued)

Legend Plot Items

The following are properties of Plot legend items. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Values
Text	String : Text that labels the plot object in the legend.
Text color	Color : Color to be used for the legend text. Click to choose from the default color palette, or specify RGB values. Default = [0 , 0 , 0] (black)
Text font	String List: Font used for legend text. Select a font from the list. Choose from these values: • Helvetica • Courier • Times • Symbol • Hershey 3 Simplex In addition to the above standard fonts, you will also have available all of the other Hershey fonts as well as any TrueType fonts available to IDL. Default = Helvetica
Text style	String List: Style used for legend text. Select a style from the list. Choose from these values: • Normal • Bold • Italic • Bold italic Default = Normal
Text font size	Number : Font size in points for the legend text. Edit the number to change the size. Default = 12


Table D-74: Plot Legend Properties

Legend Surface Items

The following are properties of individual Surface legend items. For a description of how a particular control is used, refer to [Appendix B, “Property Controls”](#).

Property	Control Type: Values
Text	String: Text that labels the surface object in the legend.
Text color	Color: Color to be used for the legend text. Click to choose from the default color palette, or specify RGB values. Default = [0 , 0 , 0] (black)
Text font	String List: Font used for legend text. Select a font from the list. Choose from these values: • Helvetica • Courier • Times • Symbol • Hershey 3 Simplex In addition to the above standard fonts, you will also have available all of the other Hershey fonts as well as any TrueType fonts available to IDL. Default = Helvetica
Text style	String List: Style used for legend text. Select a style from the list. Choose from these values: • Normal • Bold • Italic • Bold italic Default = Normal
Text font size	Number: Font size in points for the legend text. Edit the number to change the size. Default = 12

Table D-75: Surface Legend Properties



Index

Numerics

2D

annotation layer, [513](#)

3D

plots

properties, [445](#)

A

adding

plot axis object, [84](#)

annotating

iTools

contours, [277](#)

freehand type, [83](#)

images, [228](#)

line type, [80](#)

oval type, [82](#)

plots, [299](#)

polygon type, [82](#)

rectangle type, [81](#)

text, [79](#)

toolbar for, [386](#)

types of, [79](#)

vectors, [363](#)

volumes, [320](#)

annotation layer, [513](#)

autosubsampling vectors, [361](#)

axes

adding to

- contours, [273](#)
- images, [218](#)
- iTools, [84](#)
- surfaces, [242](#)
- volumes, [313](#)
- format of tick annotations
 - iTools, [488](#)
- properties, [485](#)

B

- byte scaling
 - properties, [409](#)

C

- canvas zooming, [70](#)
- colorbars
 - adding to
 - contours, [271](#)
 - images, [217](#)
 - plots, [291](#)
 - surfaces, [239](#)
 - volumes, [312](#)
 - properties, [478](#)
- colors
 - changing in contours, [268](#)
 - in iImage, [215](#)
- containers
 - definition, [179](#)
- contour direction
 - properties, [419](#)
- contour magnitude
 - properties, [419](#)
- contours
 - adding an axis, [273](#)
 - adding statistics, [279](#)
 - annotations (iTools), [277](#)
 - colorbar, [271](#), [272](#)
 - colors in, [268](#)

- displaying
 - in iContour, [257](#)
 - in iMap, [342](#)
- filling, [269](#)
- filtering, [274](#)
- flipping, [276](#)
- histogram, [279](#)
- labeling, [266](#)
- legend level properties, [528](#)
- legend properties, [527](#)
- on surface data, [244](#)
- properties, [264](#), [416](#)
- properties described, [453](#)
- convolution
 - filtering, [124](#)
 - properties, [398](#)
- copyrights, [2](#)
- cropping images
 - iTools, [413](#)
- curve fitting
 - for plots, [294](#)
- curve fitting filtering, [403](#)

D

- data
 - importing in iTool, [27](#)
 - manager, [24](#)
- data associations
 - removing, [57](#)
 - replacing, [57](#)
- data manager, [24](#)
- dataspace
 - adding, [63](#)
 - properties, [433](#)
 - range resetting, [131](#)
- displaying
 - contours
 - in iContour, [257](#)
 - in iMap, [342](#)
 - images

- in iImage, 209
- in iMap, 334
- irregular-grid data, 258
- maps, 327
- multi-channel volumes, 305
- plots
 - 2D plots, 283
 - 3D plots, 284
- regular-grid data, 257
- statistics, 129
- surfaces, 235
- vectors, 355
 - fields, 355
 - streamlines, 359
 - wind barbs, 356
- volumes, 305
- drag quality, 429

E

- error bar plots, 292

F

- file menu, 371
- files
 - operations, 113
 - toolbar, 383
 - writing
 - file writers, 105
- filling
 - contours
 - iTools, 269
- filtering
 - contours, 274
 - convolution, 124
 - data in iTools, 122
 - images in iImage, 220
 - median, 123
 - plots, 297

- smooth filter, 122
- surfaces, 247
- unsharp mask, 125
- flipping
 - contours, 276
 - images, 226
- freehand annotations
 - adding, 83
 - properties, 523

G

- general settings, iTool preferences browser, 97
- gridding wizard, 259

H

- help menu, 382
- histogram
 - adding to a volume, 322
 - for contours, 279
 - plot, 128, 301
 - properties, 397, 482
 - surface, 254

I

- iImage
 - plot profile operation, 229
- iImage images
 - adding
 - axis, 218
 - colorbar, 217
 - surface, 225
 - annotating, 228
 - brightness, 215
 - contouring, 223
 - cropping, 229
 - displaying, 209
 - displaying multiple, 211

- filtering, 220
- flipping, 226
- inverting, 226
- line profiling, 228
- manipulating, 226
- modifying properties, 216
- morphing, 222
- of surface data, 243
- panning, 229
- pixel scaling, 227
- region growing, 227
- registering in iMap, 335
- resampling, 219
- ROIs, 214
- rotating, 226
- scaling, 226
- window level control, 214
- zooming, 227
- iImage panel, 213
- iImage tool
 - color in, 215
 - image properties, 439
- image display
 - in iImage, 209
 - in iMap, 334
 - multiple images, 211
- image panel, 213
- image plane
 - about, 315
 - for volumes, 315
 - properties, 420, 422, 474
- image stack, 322
- images
 - displaying. *See* image display
 - in iImage. *See* iImage images
- iMap panel, 332
- importing
 - data in iTool, 27
- insert menu, 376
- inserting
 - map grid, 344
 - shapefiles, 345
- interval volume
 - extracting, 318
 - properties, 471
- inverting images, 226, 409
- iPlot
 - properties, 442
- irregularly-gridded data, 258
- isosurfaces
 - extracting in volumes, 316
 - properties, 469
- iSurface
 - plot profile operation, 253
- iSurface tool
 - properties, 449
 - using, 233
- iTools
 - annotation toolbar, 386
 - common operations, 112
 - edit menu, 373
 - edit toolbar, 384
 - file menu, 371
 - file toolbar, 383
 - help menu, 382
 - insert menu, 376
 - inserting a visualization, 54
 - manipulator toolbar, 385
 - operations menu, 377
 - view properties, 430
 - window menu, 380
 - window properties, 428
- iVector tool
 - See also* vectors.
 - about, 354
 - displaying vectors, 355
 - properties, 458
 - using, 353
- iVolume panel, 309
- iVolume tool
 - image stack, 322

L

- labeling
 - contours, [266](#)
- layout window, [73](#)
- legalities, [2](#)
- legends
 - adding, [77](#)
 - to contours, [272](#)
 - to plots, [289](#)
 - to surfaces, [241](#)
 - properties, [524](#)
- lights
 - adding to a surface, [240](#)
 - properties, [494](#)
- line annotations
 - adding, [80](#)
 - properties, [516](#)
- lines
 - profiles
 - annotating, [517](#)
 - extracting for a surface, [253](#)
 - in images, [228](#)

M

- Macro Controls dialog, [149](#)
- Macro Editor
 - Add and Remove buttons, [161](#)
 - items
 - annotation, [170](#)
 - history, [166](#)
 - macro, [164](#)
 - Macro Tools, [171](#)
 - Tool Menus, [178](#)
 - visualization, [169](#)
 - macro property sheet, [156](#)
 - macro tree, [156](#)
 - menu bar, [154](#)
 - source property sheet, [161](#)
 - source tree, [159](#)

- using, [153](#)
- macros
 - iTool
 - capturing intermediate manipulations, [144](#)
 - definition, [141](#)
 - exporting, [186](#)
 - importing, [186](#)
 - properties, [395](#)
 - recording, [143](#)
 - running, [146](#)
 - IDL command line, [148](#)
 - Macro Editor, [148](#)
 - Operations menu, [147](#)
 - Selection Change operation, [180](#), [181](#)
 - Tool Change operation, [183](#), [184](#)
 - types, [179](#)
- manipulating images
 - in iTools, [226](#)
- manipulating volume data
 - in iTools, [320](#)
- manipulator toolbar, [385](#)
- map grid
 - inserting, [344](#)
 - properties, [501](#)
- map panel (IMAP), [332](#)
- map projections
 - applying, [328](#)
 - common properties (iTools), [329](#)
 - definition, [328](#)
 - properties, [410](#)
 - vector data, [367](#)
- map register image operation properties (iTools), [411](#)
- mapping
 - images onto geometry
 - iTools, [248](#)
 - See also* texture maps
 - iTool display, [327](#)
- maps, displaying in IMAP, [327](#)
- median
 - filtering, [123](#)

- morphing
 - data, [127](#)
 - images, [222](#)
 - properties, [412](#)
- multi-channel volumes, [305](#)

O

- objects
 - rendering translucent, [132](#)
 - scaling, [65](#)
 - selecting, [61](#)
 - selecting all, [61](#)
 - translating, [64](#)
- operations
 - browser, [93](#), [394](#)
 - common, [112](#)
 - file, [113](#)
 - menu, [377](#)
 - property sheets, [88](#)
- oval annotations, [82](#)
 - properties, [521](#)
- overplotting
 - IPLOT, [286](#)

P

- panel
 - IIMAGE, [213](#)
 - IMAP, [332](#)
 - IVOLUME, [309](#)
- panning images
 - IIMAGE, [229](#)
- parameter editor, [56](#)
- parameters
 - editor, [56](#)
- plot profile operation, [229](#), [253](#)
- plots
 - 3-D iPlot, [284](#)
 - histogram, [128](#)
 - legend, [530](#)

- plotting
 - IPLOT
 - adding a histogram to, [301](#)
 - annotating, [299](#)
 - colorbar, [291](#)
 - curve fitting, [294](#)
 - displaying 2-D, [283](#)
 - displaying 3-D, [284](#)
 - displaying polar, [285](#)
 - error bars, [292](#)
 - filtering, [297](#)
 - legend, [289](#)
 - modifying properties for, [288](#)
 - scaling, [301](#)
 - statistics, [301](#)
 - translating, [299](#)
 - IVECTOR
 - annotating, [363](#)
 - overplotting
 - IPLOT, [286](#)
 - polar plots
 - IPLOT, [285](#)
 - polygon annotations
 - creating, [82](#)
 - properties
 - polygon annotation
 - properties, [522](#)
 - polygonal ROIs, [497](#)
 - preferences
 - browser in iTools, [95](#)
 - preferences browser, [95](#)
 - printing
 - iTools, [134](#)
 - properties
 - 2D annotation layer, [513](#)
 - 3D plot, [445](#)
 - axis, [485](#)
 - byte scale, [409](#)
 - colorbar, [478](#)
 - contour, [416](#), [453](#)
 - contour direction, [419](#)
 - contour legend, [527](#)

- contour legend level, 528
- contour magnitude, 419
- contours, 264
- convolution, 398
- cropping, 413
- curve fitting, 403
- dataspace, 433
- freehand annotation, 523
- histogram, 397, 482
- image, 439
- image plane, 420, 422, 474
- interval volume, 471
- inverting image, 409
- isosurface, 469
- iTool macros, 395
- legend, 524
- lights, 494
- line annotation, 516
- line profile annotation, 517
- map grid, 501
- map projection, 410
- map register image (iTools), 411
- modifying volume, 311
- morphing, 412
- operations browser, 394
- oval annotation, 521
- plot, 442
- plot legend, 530
- polygonal ROI, 497
- rectangle annotation, 520
- region grow, 414
- resample, 406
- Roberts filter, 401
- rotate, 405
- rotate data, 407
- scale data, 408
- shape point, 509
- shape polygon, 505
- shape polyline, 507
- sheets
 - defined, 87

- operations, 88
 - visualization, 88
- smooth filter, 400, 401
- Sobel filter, 402
- statistics, 396
- streamline, 510
- streamlines, 419
- surface, 449
- surface legend, 531
- text annotation, 514
- transform, 406
- unsharp mask filter, 402
- vector, 458
- view, 430
- visualization layer, 431
- visualization type, 437
- volume, 463
- window, 428
- property sheets
 - about, 87
 - iTool operations, 88
 - iTool visualizations, 88

R

- reading
 - files, 99
- rectangle annotations
 - creating, 81
 - properties, 520
- redo iTool operation, 62
- region growing
 - iTool operation properties, 414
- registering
 - images
 - in degrees, 340
 - in meters, 337
 - wizard, 335
- regular-grid data displays, 257
- rendering
 - translucent objects, 132

- volumes, [306](#)
- resampling
 - data, [119](#)
 - images, [219](#)
 - properties, [406](#)
 - surfaces, [246](#)
 - volumes, [314](#)
- resetting
 - dataspace, [131](#)
- Roberts filter, [401](#)
- ROI
 - iTool annotations, [79](#)
 - operations, [133](#)
- rotating
 - data, [115](#), [120](#)
 - images
 - iTool operation, [226](#)
 - left, [117](#)
 - properties, [405](#), [407](#)
 - right, [117](#)
 - surfaces, [249](#)
 - volumes, [320](#)
 - with a mouse, [115](#)

S

- scaling
 - 3-D objects, [66](#)
 - constrained, [66](#)
 - data, [121](#)
 - images, [226](#)
 - objects, [65](#)
 - plots, [301](#)
 - properties, [408](#)
 - surfaces, [251](#)
 - unconstrained, [67](#)
 - unconstrained 2-D objects, [68](#)
 - unconstrained 3-D objects, [69](#)
 - volumes, [320](#)
- selecting
 - objects in iTools, [61](#)

- Shapefile
 - adding in iMap, [343](#)
 - creating a visualization, [343](#)
 - definition, [343](#)
 - inserting, [345](#)
 - Canadian provinces, [351](#)
 - continents, [345](#)
 - countries (high resolution), [346](#)
 - countries (low resolution), [346](#)
 - lakes, [349](#)
 - ivers, [348](#)
 - United States, [350](#)
- ShapePoint, [509](#)
- ShapePolygon, [505](#)
- ShapePolyline, [507](#)
- smooth filtering, [122](#), [400](#), [401](#)
- smoothing
 - volumes, [322](#)
- Sobel
 - filter, [402](#)
- statistics
 - adding to plots, [301](#)
 - adding to volumes, [322](#)
 - displaying, [129](#)
 - properties, [396](#)
 - surface, [254](#)
- Streamlines, [510](#)
- streamlines, [359](#)
 - properties, [419](#)
- styles
 - applying, [189](#)
 - copying, [195](#)
 - creating, [190](#)
 - current style, [195](#)
 - default style, [205](#)
 - definition, [188](#)
 - editing, [202](#)
 - exporting, [206](#)
 - importing, [206](#)
 - types, [189](#)
- subsampling vectors, [360](#)

surfaces

- adding axes, 242
- adding texture map, 248
- adding to an image, 225
- colorbar, 239
- creating contours on, 244
- creating images of, 243
- displaying, 235
- extracting a line profile, 253
- filtering, 247
- histogram for, 254
- legends, 241, 531
- lights, 240
- rotating, 249
- scaling, 251
- statistics, 254

T

text annotations

- adding, 79
- properties, 514

texture mapping. *See* texture maps

texture maps

- iTools, 248

three-dimensional

- plots, 445

trademarks, 2

transforming

- data, 119
- properties, 406
- resampling, 119
- rotate data, 120
- scale data, 121

translating

- objects, 64
- plots, 299
- vectors, 363

translucent object rendering, 132

U

undo iTool operation, 62

unsharp mask filtering, 125, 402

V

vectors

IVECTOR

- autosubsampling, 361
- coloring, 362
- displaying, 355
- fields, 355
- map projection, 367
- properties for, 360
- streamlines, 359
- subsampling, 360
- translating, 363
- wind barbs, 356

properties, 458

view zooming, 70

visualizations

- browser, 90
- creating, 53
- definition of, 52
- exporting, 58
- inserting, 54
- layers, 431
- modifying, 56
- object selection, 90
- property sheets, 88
- type properties, 437

volume panel (IVOLUME), 309

volumes

- adding
 - axis, 313
 - colorbar, 312
 - histogram, 322
 - statistics, 322
- annotating, 320
- displaying, 305

- displaying multi-channel, [305](#)
- extents, [308](#)
- extracting
 - interval volume, [318](#)
 - isosurface, [316](#)
- properties, [311](#), [463](#)
- rendering, [306](#)
- resampling, [314](#)
- rotating, [320](#)
- scaling, [320](#)
- showing an image plane for, [315](#)
- smoothing, [322](#)

W

- wind barbs, [356](#)
- window layout, [73](#)
- window level control, [214](#)
- window menu, [380](#)
- writing
 - dat files, [105](#)
 - text files, [105](#)

Z

- zooming, [70](#)